



ਪੰਜਾਬ ਨੈਸ਼ਨਲ ਬੈਂਕ
...शरसे का प्रतीक !



punjab national bank
...the name you can BANK upon !



**General Services Administrative Division
Plot No. 4, Sector -10 Dwarka 110075**

एक कदम स्वच्छता की ओर

Corrigendum Notice for E-Tender No. 1080, Need Based Repairs of UGF, 1st, 2nd & 5th Floors of Bank's Building at 7, Bhikaiji Cama Place, New

S no	Tender BOQ Item No	Existing	Modified
1	5	Providing and fixing partition in position as per design with 2" x 2" Aluminium/Maranti section finished frame work @ 2'0" c/c both ways screwed to the floor with M.S. Cleats and to be treated with anti termite oil. The frame work will be cladded with 12mm thk bwr. ply both sides and to be finished with approved 1 mm laminate(color with vertical grain) as per design with adhesive. 3" high laminated skirting to be fixed bottom side of the partition. Extra frame work to be fixed for fixing glass. In the glazed partition 10mm thk. Etched glass with sand blusting/granular blasting to be provided duly fixed with . wooden lipping 37mm x 19 mm all complete duly polished. The work to be completed as per design approval of the Engineer in charge.	Providing and fixing partition in position as per design with 2" x 2" Maranti section finished frame work @ 2'0" c/c both ways screwed to the floor with M.S. Cleats and to be treated with anti termite oil. The frame work will be cladded with 12mm thk bwr. ply both sides and to be finished with approved 1 mm laminate(color with vertical grain) as per design with adhesive. 3" high laminated skirting to be fixed bottom side of the partition. Extra frame work to be fixed for fixing glass. In the glazed partition 10mm thk. Etched glass with sand blusting/granular blasting to be provided duly fixed with . wooden lipping 37mm x 19 mm all complete duly polished. The work to be completed as per design approval of the Engineer in charge.
2	6	Providing and fixing tables/counters made out of 19mm thk bwr grade board of approved make cladded with 1.0 mm laminate as per design in all visible areas. All the exposed edges to be covered with wooden lippings and mouldings duly malamine polish. The drawers to be made out of 19mm thk bwr. board duly laminated in the front of every workstation ,sides to be made out of 19mm bwr. ply and bottom to be made out of 12mm bwr. ply and it should play in drawer sliding channels. The inside of the drawer and the table to be duly paint . A legrest to be provided duly paint made out of 3"x2" thk wooden section. A shutter to be made by 19mm bwr. board cladded with 1.0 mm laminate .The necessary locks handles to be provided in each drawers and shutters. 3" x 1/2" wooden skirting to be provided in all visible areas duly polished. The table should have key board tray and tea tray duly finished with 1.0 mm laminate. The necessary wire managers to be provided on the tables and provision for lights to be kept if required in the front of the table. 19mm bwr. board & 12mm ply panel fix front side as per design including the raised level & perforations. All the exposed wooden areas to be duly malamine polished The work to be completed as per design and approval of the Engineer in Charge.(width of table= 2'6")	Providing and fixing counters made out of 19mm thk bwr grade board of approved make cladded with 1.0 mm laminate as per design in all visible areas. All the exposed edges to be covered with wooden lippings and mouldings duly malamine polish. The drawers to be made out of 19mm thk bwr. board duly laminated in the front of every workstation ,sides to be made out of 19mm bwr. ply and bottom to be made out of 12mm bwr. ply and it should play in drawer sliding channels. The inside of the drawer and the table to be duly paint . A legrest to be provided duly paint made out of 3"x2" thk wooden section. A shutter to be made by 19mm bwr. board cladded with 1.0 mm laminate .The necessary locks handles to be provided in each drawers and shutters. 3" x 1/2" wooden skirting to be provided in all visible areas duly polished. The table should have key board tray and tea tray duly finished with 1.0 mm laminate. The necessary wire managers to be provided on the tables and provision for lights to be kept if required in the front of the table. 19mm bwr. board & 12mm ply panel fix front side as per design including the raised level & perforations. All the exposed wooden areas to be duly malamine polished The work to be completed as per design and approval of the Engineer in Charge.(width of Counters = 2')
3	7	Providing and fixing vertical /roller blinds of 1 mm thick of approved shade and pattern. The rate shall include necessary scoch gard treatment on both sides. The overlapping should be uniform and adequate.Necessary oparative arrangements,frames to be provided. The work to be completed as per specification and approval of the Enigneer in Charge. The Base rate should not be less than Rs. 900/- Per SQM	Providing and fixing roller blinds of 1 mm thick of approved shade and pattern. The rate shall include necessary scoch gard treatment on both sides. The overlapping should be uniform and adequate.Necessary oparative arrangements,frames to be provided. The work to be completed as per specification and approval of the Enigneer in Charge. The Base rate should not be less than Rs. 900/- Per SQM
4	9	Supply fitting and fixing of metalic false ceiling matching as per the existing tone with quality and design	Supply fitting and fixing of metalic false ceiling matching as per the existing tone with quality and design. The size of metalic false ceiling is 1270 mmX305mm with 50 mm color edge.
5	23	Supply and fixing of basin with carrying charges as per existing pattern (fitted in granite counter) with all accessories	Supply and fixing of basin as per existing pattern (fitted in existing granite counter) or equivalent with all accessories including charges for removaing of existing basin.
6	24	Replacement of faulty taps including all accessories and other plumbing and sanitary fittings with permisiion from Engineer in charge.	Providing and fixing of C P pillar cock
7	25	Replacement of faulty urinals and other plumbing and sanitary fittings with permision from Engineer in charge.	Item considered to be deleted. Bidders requested to put item cost as ZERO.
-----sd----- (Asst. General Manager)			