

STANDARD ONLINE OPEN TENDER FOR CONTRACTOR

PUNJAB NATIONAL BANK

Invites

Online Tender for Carrying out Carpentry, Electrical LAN Cabling, Air Conditioning and & other miscellaneous allied works for Staff Training Centre of Punjab National Bank at 3RD floor of Rava Tower, Lutuma, Barshapara, A K Azad Road Guwahati, Assam, Pin- 781008

PART A

TECHNICAL BID

**Punjab National Bank,
Circle Office Guwahati
Nilgiri Mansion, Bhangagarh
Guwahati- 781005
Contact No.6291947564/8402946118
e-mail: - coguwgad@pnb.co.in**

1. INDEX

S NO	DESCRIPTION	PAGE NO
	PART A – TECHNICAL BID	
1	INDEX	2
2	NOTICE INVITING TENDER	3-6
3	INSTRUCTION TO BIDDERS	7-9
4	PURPOSE OF TENDER	10
5	ELIGIBILITY CRITERIA	11-13
6	APPENDIX TO FORM OF TENDER	14
7	ARTICLES OF AGREEMENT	15-63
8	GENERAL CONDITIONS OF CONTRACT (GCC)	17-44
9	SPECIAL CONDITIONS OF CONTRACT	45-51
10	LETTER SUBMITTING TENDER	52
11	LETTER OF TRANSMITTAL	53
12	ANNEXURE-I: BIDDER'S INFORMATION	54
13	ANNEXURE-II: UNDERTAKING FOR LOCAL CONTENT FROM BIDDER	55
14	ANNEXURE-III: UNDERTAKING FOR NON-BLACKLISTING / DEBARRING AND BACK TO BACK WORKS	56
15	ANNEXURE-IV: BIDDERS' FINANCIAL INFORMATION	57
16	ANNEXURE-V: REFERENCE LIST	58
17	ANNEXURE-VI: COMPLIANCE STATEMENT	59
18	ANNEXURE-VII: UNDERTAKING FOR PROCUREMENT FROM COUNTRY SHARING LAND BORDER WITH INDIA	60
19	ANNEXURE-VIII: DETAILS OF INSURANCE POLICIES	61
20	ANNEXURE-IX: INTEGRITY PACT	62-68
21	ANNEXURE-X: GUARANTEE BOND FOR WATER PROOFING WORKS	69-70
22	ANNEXURE-XI: GUARANTEE BOND FOR ANTI-TERMITE WORKS	71-72
23	LIST OF PREFERRED MAKE OF MATERIAL	73-75
	PART B - COMMERCIAL BID	
24	COMMERCIAL BID (TO BE QUOTED ONLINE)	76-124

NOTICE INVITING TENDER

1. Online tenders are invited on item rate basis on behalf of Punjab National Bank from intending, bonafide & experienced contractors, reputed firms (proprietary/ partnership) /company / organization registered in India under Partnership Act, 1932 / Companies Act, 1956 and their subsequent revisions / amendments, who fulfill the eligibility criteria mentioned in the tender documents for **Carpentry, Electrical LAN Cabling, Air Conditioning and & other miscellaneous allied works for Staff training Centre of Punjab National Bank at 3RD floor of Rava Tower, Lutuma, Barshapara, A K Azad Road Guwahati, Assam, Pin- 781008**

Tender schedule will be as under:

1.	Tender Reference	NIT/PNB/STCGHY/COGHY/2024-25/01
2.	Date of commencement of Tender download	04.06.2024 from 11:30 hrs
3.	Last date and time for acceptance of queries	10.06.2024 till 12:00 hrs
4.	Date, Time & Address of Pre-bid meeting	10.06.2024 at 15:00 hrs At Office Of Chief Manager, GSAD, Punjab National Bank, Circle Office Guwahati, Nilgiri Mansion, G S Road, Bhangagarh, Guwahati, Assam, Pin 781005
5.	Last date and time for downloading tender	18.06.2024 up to 17:00 hrs
6.	Last date and time for Bid preparation and Hash Submission	18.06.2024 up to 17:00 hrs
7.	Last Date and time Bid re-encryption and Submission of Envelopes Containing Technical Bid, Tender Fee and EMD in Tender Box	19.06.2024 till 10:00 hrs Envelopes Containing Technical Bid, Tender Fee and EMD to be submitted in Tender Box at Punjab National Bank, Circle Office Guwahati, Nilgiri Mansion, G S Road, Bhangagarh, Guwahati, Assam, Pin 781005
8.	Date and Time of Opening of Technical cum Eligibility Bid	19.06.2024 from 16:00 hrs
9.	Cost of Tender Document	Rs. 1,770/- (non-refundable i/c GST @18%) in the form of Demand Draft in favour of Punjab National Bank payable at Guwahati or online payment in non-customer account (A/c No:3796003171160 & IFSC Code: PUNB0379600) of (the procuring office of Bank)
10.	Earnest Money Deposit	Earnest Money Deposit (EMD) of ₹1,95,676/- (Rupees One Lakh Ninety-Five Thousand Six Hundred Seventy-Six Only. EMD shall be accepted in form of Insurance Surety Bonds, Account Payee Demand Draft (in favour of Punjab National Bank payable at Guwahati), Fixed Deposit Receipt (lien to be marked in favour of PNB), Bankers' Cheque (in favour of PNB) or Bank Guarantee (including e-Bank Guarantee) (from any Scheduled Commercial

		Bank other than PNB) or online payment in non-customer account (i.e. (A/c No:3796003171160 & IFSC Code: PUNB0379600) of (the procuring office of Bank). EMD is to be submitted with Envelope-I. EMD should be valid within the bid validity period of 90 days after the date of opening of commercial bid. The bidder shall also extend the EMD validity without giving any reasons, for the duration whatever requested by the Bank.
11.	Validity of Tender	90 days
12.	Estimated Cost put to tender	Rs. 97,83,797.00 i/c of all taxes (Rupees Ninety Seven Lakh Eighty Three Thousand Seven Hundred Ninety Seven only)
13.	Time of Completion	45 days
14.	Place of Physical Bid Submission & Opening of Bids	Punjab National Bank, Circle Office Guwahati, Nilgiri Mansion, G S Road, Bhangagarh, Guwahati, Assam, Pin 781005
15.	Contact Person	Chief Manager, GAD, Punjab National Bank, Circle Office Guwahati, Nilgiri Mansion, G S Road, Bhangagarh, Guwahati, Assam, Pin 781005 Contact details : +91-6291947564 Sr. Manager GAD: 8402946118 Email:- coguwgad@pnb.co.in

Bank will be following the e-procurement process. The complete details of the requirements for participation in the e-procurement process of the Bank are available on the website <https://etender.pnbnet.in> which may be referred for details & clarification. It is mandatory for the bidder to get itself registered on Bank's website for submission of online bids.

Note: - Technical bids will be opened in the presence of bidders who choose to attend as above. The above schedule is subject to change. Notice of any changes will be published on Bank's website (www.pnbindia.in & <https://etender.pnbnet.in>) wherever feasible. Further, please note that commercial bid opening date and time will be intimated to the technically qualified bidders at a later date.

- Online tenders are invited on item rate basis on behalf of Punjab National Bank from experienced contractors, reputed firms (proprietary/ partnership)/ company/ organization registered in India under Companies Act, who fulfil the eligibility criteria mentioned in the tender documents for the Carpentry, Electrical, LAN Cabling, Air Conditioning & other miscellaneous allied works at 3rd Floor of Rava Tower, Lutuma, Barshapara, A K Azad Road, Guwahati, Assam against Payment of ₹1,770/- (non-refundable towards cost of tender and i/c GST @ 18%), in two envelope system containing (1) Technical Bid (2) Commercial bid. Tender purchase fee of ₹1,770/- i/c GST@18%) may be submitted in form of demand draft in a separate envelope or online payment in non-customer account (A/c No:3796003171160 & IFSC Code: PUNB0379600) of (the procuring office of Bank) with **EMD**. Commercial bid shall be submitted online only.
- The Bidders intending to participate in this tender are required to get enrolled on the Bank's website i.e. <https://etender.pnbnet.in> Enrolment on the above mentioned website is mandatory.

4. As the bids of the Bidders have to be digitally signed by the Electronic/Digital Signature of the respective Bidder before submitting the bids online, the bidders are advised to obtain Electronic/ Digital Signature Certificates (Class III & above both encryption & Signing) in order to bid for the tender.
5. The Tender Documents containing detailed terms & conditions can be downloaded online directly from the portal <https://etender.pnbnet.in> (or pnbindia.in) as per tender schedule attached and shall be submitted online.
6. All the bidders are required to submit Demand Draft in favour of Punjab National Bank, **Guwahati** or online payment in non-customer account (A/c No:3796003171160 & IFSC Code: PUNB0379600) of (the procuring office of Bank) of ₹ 1,770/- towards the cost of tender document and EMD of ₹ 1,95,676/- (Rupees One Lakh Ninety-Five Thousand Six Hundred Seventy-Six Only) in form of Insurance Surety Bonds, Account Payee Demand Draft (in favour of PNB payable at Guwahati), Fixed Deposit Receipt (lien to be marked in favour of PNB), Bankers' Cheque (in favour of PNB) or Bank Guarantee (including e-Bank Guarantee) (from any Scheduled Commercial Bank other than PNB) or online payment in non-customer account (i.e. (A/c No:3796003171160 & IFSC Code: PUNB0379600) of (the procuring office of Bank) by 18.06.2024 till 17:00 hrs, failing which, the bids shall be summarily rejected.
7. Bidders may submit their queries regarding any technical clarification before 10.06.2024 up to 12:00 Hrs. No queries shall be entertained after last date fixed for acceptance of queries.
8. Pre-bid meeting is scheduled on 10.06.2024 at 15:00 hrs. Intending bidders who are willing to participate in the tendering process may attend the Pre-Bid meeting at scheduled time.
9. Clarifications of Bank on RFP may be downloaded from the "Corrigendum/ Addendums" section of the above mentioned portal up to 15:00 hrs. on 10.06.2024 after clarification on queries. No deviation on the above shall be entertained by the Bank thereafter.
10. Based on the clarification of conditions by the Bank, an intending bidder shall submit its unconditional acceptance on the prescribed format along with tender document.
11. Bidders who have submitted Tender Fee and EMD in the non-customer Bank account specified in the tender document shall mandatorily submit copy of transaction receipt as proof of submission. Any other mode of payment, i.e., Insurance Surety Bonds, Account Payee Demand Draft, Fixed Deposit Receipt (lien to be marked in favour of PNB), Bankers' Cheque (in favour of PNB) or Bank Guarantee (including e-Bank Guarantee) (from any Scheduled Commercial Bank other than PNB) shall be submitted in original. Commercial bid of only those bidders shall be opened who submit their tender in line with requirements of tender documents and are acceptable to the Bank and the bidder who do not submit the EMD & tender fee, as the case may be, their tenders shall be summarily rejected.
12. First Tender Fee & E.M.D. Envelope shall be opened, and if the hard copy of the same is received on time i.e. up to 17:00 Hrs on 18.06.2024 only then technical bid shall be opened online. Hard copy i.e. EMD amount of ₹ 1,95,676/- (Rupees One

Lakh Ninety-Five Thousand Six Hundred Seventy-Six Only) and Tender Fee amount of ₹ 1,770/- is to be submitted physically by the bidder in the office of the Dy. General Manager, Punjab National Bank, Circle Office Guwahati, Nilgiri Mansion, Bhangagarh, Guwahati- 781005 on or before 17:00 Hrs on 18.06.2024.

13. The commercial bid of technically eligible bidder who meets the eligibility criteria stipulated in tender documents will be opened online in the presence of participants or representatives of participant bidders as per the schedule attached. The Date for opening of commercial bids shall be intimated later.
14. The Tenders shall be valid for a period of not less than 90 days after the date of opening of commercial bid online.
15. All disputes arising out of or in connection with this agreement shall be deemed to have arisen in Guwahati and only the courts of Guwahati shall have the jurisdiction to determine the same.
16. Please note that “**hash submission**” and “**bid re-encryption**” are compulsory activities for participation in the bid. Further, all bidders who have submitted the bid with “hash submission”, will necessarily have to re-encrypt their bid, failing which the bid will remain encrypted and the bid will not be considered for opening.
17. For any further information/Queries please contact **Chief Manager, General Services Administration Division, Circle Office Guwahati, Nilgiri mansion, Bhangagarh Guwahati, Assam, 781005, e-mail: - coguwgad@pnb.co.in, Cont No.6291947564/ 8402946118.**
18. The Bank reserves the right to accept/reject any or all the offers submitted in response to this advertisement without assigning any reason whatsoever.
19. The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tenders without assigning any reasons whatsoever.
20. Please note that, on tendering procedure through the electronic tendering system refer to the Instructions for Using the Electronic Tendering System document available along with the tender documents on <https://etender.pnbnet.in>.
21. Bidder must submit documentary proof in respect of all above mentioned criteria while submitting the proposal. Proposal of bidders who do not fulfill the above criteria or who fail to submit documentary evidence thereon would be rejected.
22. Bidders registered under MSEs will also necessarily submit Tender Cost and EMD (There is no exemption for MSEs for procurement of works). If MSE bidders do not enclose Tender Cost or EMD, their bid will be summarily rejected as NON-RESPONSIVE.
23. It shall be mandatory to sign the integrity pact as mentioned in tender documents by the bidder failing which bidder will stand disqualified for tendering process and their bid shall be rejected summarily.

Chief Manager

INSTRUCTION TO BIDDERS

1. BIDDING PROCESS (TWO STAGES)

For the purpose of the present job, a three-envelope bidding process will be followed. The response to the present tender will be submitted in two parts:

- Technical bid
- Commercial bid

The bidders will have to submit the technical bid in Banks e-procurement system as well as in hard copy and commercial bids in only online form through Bank's e-procurement system.

1.1 TECHNICAL BID

TECHNICAL BID will also contain the Compliance statement as per the Terms & Conditions mentioned in the Tender Documents, and NOT contain any pricing or commercial information at all. Technical bid documents with any commercial information will be rejected.

In the first stage, only TECHNICAL BIDs will be opened and evaluated. Only those bidders confirming compliance to all the terms & conditions of Tender document shall be short-listed for commercial stage.

1.2 COMMERCIAL BID

In the second stage, the COMMERCIAL BID of only those bidders, whose technical bids are short listed, will be opened.

2. SUBMISSION OF BIDS

2.1 Bidders are required to strictly submit their bids in electronic form using the e-procurement system at <https://etender.pnbnet.in> the Bank by using their digital certificates of class II and above (both encryption and signing). All the interested bidders should register themselves in the e-procurement system <https://etender.pnbnet.in> for submitting the bids online, if they have not done earlier. The Tender document and further corrigendum, if any can also be downloaded from Bank's website www.pnbindia.in. Bids received after closing of the bid in the e-procurement system are summarily rejected without any reason. The commercial bid should be submitted online only.

Envelope No.1- Tender Cost & EMD – Marked Cover-I

Envelope No.1 shall contain Cost of Tender Document of **Rs. 1,770/- (Rupees One Thousand Seven Hundred and Seventy only) (including GST)**, in the form of Demand Draft or online payment in non-customer account (A/c No:3796003171160 & IFSC Code: PUNB0379600) of (the procuring office of Bank) which shall be non-refundable along with **Earnest Money Deposit (EMD)** of ₹ 1,95,676/- (Rupees One Lakh Ninety-Five Thousand Six Hundred Seventy-Six Only). EMD shall be accepted in form of Insurance Surety Bonds, Account Payee Demand Draft (in favour of Punjab National Bank payable at Guwahati), Fixed Deposit Receipt (lien to be marked in favour of Bank), Bankers' Cheque (in favour of Punjab National Bank) or Bank Guarantee (including e-Bank Guarantee) (from any Scheduled Commercial Bank other than Punjab National Bank) or online payment in non-customer account (i.e. A/c No:3796003171160 & IFSC Code: PUNB0379600) of (the procuring office of Bank). EMD is to be submitted with Envelope-

I. EMD should be valid within the bid validity period of 90 days. The bidder shall also extend the EMD validity without giving any reasons, for the duration whatever requested by the Bank. This envelope shall be super scribed “**Tender Cost and EMD for Carpentry, Electrical, LAN Cabling, Air Conditioning and Other Miscellaneous allied works for Staff Training Centre Guwahati at 3rd floor of Rava Tower, Lutuma, A K Azad Road, Guwahati, Assam.**”

Envelope No. 2 – Technical Bid – Marked Cover-II

Envelope No. 2 shall contain technical bid (one set of duly signed tender document except commercial bid). Each page and correction duly signed by Bidders including tender form duly filled in with complete details and descriptions. Bidder shall submit supporting documents in support of eligibility criteria as mentioned in tender documents. This envelope shall be super scribed “**Envelope No. 2 - Carpentry, Electrical, LAN Cabling, Air Conditioning and Other Miscellaneous allied works for Staff Training Centre Guwahati at 3rd floor of Rava Tower, Lutuma, A K Azad Road, Guwahati, Assam.**”

Both Envelope No. 1 and Envelope No. 2 shall be contained in a large envelope superscribed Carpentry, Electrical, LAN Cabling, Air Conditioning and Other Miscellaneous allied works for Staff Training Centre Guwahati at 3rd floor of Rava Tower, Lutuma, A K Azad Road, Guwahati, Assam” which should reach the below mentioned address before the final date & time of bid submission mentioned in the tender schedule.

**Dy. General Manager,
Punjab National Bank,
Circle Office Guwahati,
Nilgiri Mansion Bhangagarh
Guwahati, Assam- 781005**

1. LIST OF DOCUMENTS TO BE SUBMITTED

- 1.1 Earnest Money Deposit & Tender Document cost (Sealed Cover: **Envelope No.1- Tender Cost & EMD – Marked Cover-I**).
- 1.2 Documents required in Technical Bid Envelope (Sealed Cover: **Envelope No. 2 – Technical Bid – Marked Cover-II**):
 - a) Bidders undertaking letter
 - b) Supporting documents as per Eligibility Criteria
 - c) Performance/Completion Certificate from clients
 - d) Bidder Information
 - e) Acceptance of Compliance Statement
 - f) Duly signed Tender document and corrigendum, if any
 - g) Power of attorney in favour of authorized person signing the Bid documents.
 - h) Certificate of Incorporation & Partnership Deed, if applicable
 - i) PAN No.
 - j) ESI & EPF Registration, if applicable
 - k) GST Registration No.
 - l) Copy of last three years audited balanced sheet, Profit & Loss Statement, Balance Sheet and ITR.
 - m) List of similar work completed in last 7 (Seven) years with details enclosing completion certificate from the principal employer / clients along with the names of two responsible clients/ persons with address & telephone number who will be in position to certify about quality as well as past performance of your organization.

- n) List of Govt./ Quasi-Govt. Deptt. and other organizations of repute with whom the company is empanelled.

Note:

- a. All pages of the bid documents must be signed by authorized person.
- b. All pages of the bid documents should be numbered in serial order i.e. 1, 2, 3...
- c. Commercial bid to be submitted in e-procurement process only. No hardcopy of the same be enclosed with the supporting documents. Submission of Commercial Bid along with Physical submission of tender document will summarily lead to rejection of the bid.

4. PRELIMINARY EXAMINATION

4.1 Bank will examine the bids to determine whether they are complete, whether any computational errors have been made, whether required information has been provided as underlined in the bid document, whether the documents have been properly signed, and whether bids are generally in order.

4.2 The bid determined as not in order as per the eligibility criteria will be rejected by the Bank. The decision of the Bank is final towards evaluation of the bid documents.

5. EVALUATION AND AWARD CRITERIA

5.1 After opening of the technical bids, all the documents and annexure (except commercial documents/offer) will be evaluated first by the Bank. First, received bids will be evaluated based on the eligibility criteria. Technical bids of only those bidders satisfying the eligibility criteria will be evaluated.

5.2 Only those bidders satisfying the technical requirements and accepting the terms and conditions of this document shall be short-listed for further steps.

5.3 PNB will determine to their satisfaction whether the bidder selected as having submitted the best evaluated responsive bid is qualified to satisfactorily perform the contract. The decision of PNB will be final in this regard.

5.4 The determination will take into account bidder's financial, technical and support capabilities, based on an examination of documentary evidence submitted by bidders in support of eligibility criteria. Further, to determine the Bidder's eligibility / past performance as part of evaluation of technical bid, Bank may, at its discretion:

- Carry out site visits at works previously executed by the bidder.
- Visit the workshops / manufacturing facilities etc. of the bidder.
- Seek Confidential Reports from previous clients of Bidder to ascertain their past performance.

The bidder shall have no objection to the above and shall extend their full cooperation, including coordinating the visits to their workshops or sites of their previous clients.

5.5 The award of contract will be based on evaluation of technical and commercial bids. The decision of the Bank is final towards evaluation of the bid documents.

PURPOSE OF TENDER

Bank intends to take up **Carpentry, Electrical LAN Cabling, Air Conditioning and & other miscellaneous allied works for Staff Training Centre of Punjab National Bank at 3RD floor of Rava Tower, Lutuma, Barshapara, A K Azad Road Guwahati, Assam, Pin- 781008** as per details given in schedule of quantities/tender documents.

ELIGIBILITY CRITERIA

1. The Bidder should possess the requisite experience, resources and capabilities in providing the services necessary to meet the requirements, as described herein. The Bidder should also possess the technical know-how and the financial wherewithal that would be required to complete the scope of work. The Bid must be complete in all respects and should cover the entire scope of work as stipulated in the tender document. Bidders not meeting the Eligibility Criteria will not be considered for further evaluation and bid submitted by them shall be summarily rejected.
2. This invitation of bids is open to all intending, bonafide & experienced contractors (proprietary / partnership / private / limited company) registered in India under Partnership Act, 1932 / Companies Act, 1956 and their subsequent revisions / amendments, provided they fulfill the minimum eligibility criteria as below. Consortium/Joint Ventures and Special Purpose Vehicles are not eligible for the tender and the bid, if any, submitted by them shall be summarily rejected. Proposals not complying with minimum eligibility criteria, as enumerated below, will be rejected and will not be considered for evaluation of technical bid.
3. The proposal should adhere to the following minimum eligibility criteria:

S. No.	Minimum Eligibility Criteria
1.	<p>The Bidder should have satisfactorily completed similar works during last 7 (seven) years ending last day of the month of 30.04.2024 with Central/State Government Department/Central Autonomous Body/Central Public Sector Undertaking/City Development Authority/Municipal Corporation of City formed under any Act by Central/State Government and published in Central/State Gazette/ Scheduled Commercial Banks or its subsidiaries/Private organizations should be either of the following: -</p> <p style="padding-left: 40px;">2. One similar nature work amounting to ₹ 78.27 Lakh</p> <p style="text-align: center;">Or</p> <p style="padding-left: 40px;">3. Two similar nature work amounting to ₹ 48.92 Lakh</p> <p style="text-align: center;">Or</p> <p style="padding-left: 40px;">4. Three similar nature work amounting to ₹ 39.14 Lakh</p> <p>Similar work means Composite Renovation works including Carpentry, Electrical LAN Cabling, Air Conditioning and & other miscellaneous allied works of Office premises executed under one agreement.</p> <p>Cumulative works executed under rate contract shall not be treated as one work.</p> <p>Components of work executed other than those included in definition of similar shall be deducted while calculating cost of similar work. Bidder shall submit abstract of cost of work in support of the same.</p>

	<p>Certificates of satisfactory completion of similar work should be issued by an Authority not below the rank of Executive Engineer/Chief Manager of Principal Employer / Client department and the same are to be uploaded on Bank's website along with supporting documents.</p> <p>In case the similar work/s is of private nature other than Central/State Government/Central Autonomous Body/Central Public Sector undertaking/City Development Authority/ Municipal Corporation of city, they shall be required to submit T.D.S. Traces / Certificates for such works issued by respective Principal Employer/ Clients.</p> <p>The value of executed works shall be brought to current costing level by enhancing the actual value of work at simple interest of 7% per annum, calculated from the date of completion to the last date of receipt of application for tender.</p>
2.	<p>The minimum average annual turnover of Bidder for the last three financial years i.e. 2021-2022, 2022-2023 & 2023-2024 must not be less than ₹ 29.35 Lakh. Bidder to upload audited Balance sheet, Profit & Loss statement and trading account details for these financial years, if applicable.</p> <p>The multiplication factor of 7% per annum simple interest is not applicable on the Annual Financial Turnover figures.</p>
3.	<p>The Applicant should not have been black-listed/ barred by any Central/ State Government Department/ Central Autonomous Body/ Central Public Sector Undertaking/ City Development Authority/ Municipal Corporation of City formed under any Act by Central/ State Government and published in Central/ State Gazette/ Public Sector Banks etc. Further, similar eligible works should not have been carried out on Back to Back basis and the Applicant shall have to furnish undertaking as under. An undertaking in this regard is to be submitted to Bank by Bidder (on stamp paper of Rs.100/-)</p> <p><i>"I/ We undertake and confirm that</i></p> <ol style="list-style-type: none"> <i>1. Eligible similar work(s) has/ have not been executed through another agency on back to back basis.</i> <i>2. I/ We have not been black-listed/ debarred by any office of Bank/ DFS or regulators like RBI, SEBI, IRDA etc/ Department of Expenditure, Ministry of Finance Government Agency."</i> <p><i>Further that, if such a violation comes to the notice of the Bank, then I/we shall be debarred for bidding in Bank in future forever. Also, if such violation comes to the notice of the Bank before date of start of work, the Bank shall be at liberty to forfeit the entire amount of Earnest Money Deposit."</i></p>

** In case, the company/bidder does not have the audited Balance Sheet for period ending March 2024, provisional balance sheet certified by their Statutory Auditors will be acceptable.

Note: The bidder must submit the Compliance Statement failing which the bids may not be taken for further evaluation.

- The bidder should be Class-I local supplier. "Class-I local supplier" means a supplier or service provider, whose goods, services or works offered for procurement, meets the minimum "local content" as prescribed for Class-I local supplier as per DPIIT vide OM P-45021/2/2017PP (BE-II) dated 16.09.2020 issued the Public Procurement (Preference to Make in India) Order 2017-revision. The "local content" requirement to categorize a supplier as "Class-I local supplier" is

minimum 50%. “Local content” means the amount of value added in India which shall, unless otherwise prescribed by the nodal ministry, be the total value of the item procured (excluding net domestic indirect taxes) minus the value of imported content in the item (including all customs duties) as a proportion of the total value, in percent.

5. **Verification of “local content”:** The “Class-I local supplier” with the bid document shall be required to submit self-certification the bidder meets the local content requirement for “Class-I local supplier” as per Annexure-II.
6. Bidder must submit documentary evidence in respect of all above mentioned criteria while submitting the proposal. Proposal of bidder who do not fulfill the above criteria or who fail to submit documentary evidence thereon would be rejected.
7. Bidder has to upload scanned and legible copies of all supporting documents on Bank’s e-procurement website <https://etender.pnbnet.in> for its scrutiny.
8. The Bank reserves the right to request for any additional information and also reserves the right to reject or accept the bid of a bidder, if in the opinion of Bank the qualification data is incomplete or the bidder is found not qualified to satisfactorily execute the requirements of the project and no communication shall be entertained in this regard in future.

APPENDIX TO FORM OF TENDER

1.	Defects Liability period	12 Months from date of virtual completion of work. Virtual completion of the project will be certified and recorded by official assigned by Bank/ Site Engineer.
2.	Date of Commencement	Date of start of work shall be reckoned as immediate from the date of award of work.
3.	Stipulated time of completion	45 days from the date of commencement of work.
4.	Period of Final Measurements	1 (One) months from the Date of Virtual Completion
5.	Liquidated Damages	1.0% of the contract amount shown in the tender per week subject to the ceiling of 10% of the accepted contracted sum.
6.	Minimum Value of work for Interim Certificate	₹ 65,22,532/-
7.	Total Security Deposit	8% of the contract sum
8.	Performance Security	Performance Security (inclusive of EMD) will be 3% of the contract sum. Performance security for works shall be returned to the party within 14 days after virtual completion of work.
9.	Retention Money for defect liability period	8% of the gross value of each interim bill with maximum of 5% of the contract value
10.	Period of Honouring Certificate	15 days from date of receipt of certificate from the official assigned by Bank/ Site Engineer
11.	Refund of total Security Deposit	<p>Retention money will be refunded within 30 days after end of the defect liability period, provided that contractor has satisfactorily carried out all the works attended to all defects in accordance with the conditions of the Contract, including the site clearance.</p> <p>After completion of work, Retention money can be refunded after obtaining a Bank Guarantee of equivalent amount for a time period till the end of defect liability period plus claim period. Bank Guarantee should be from any Scheduled Commercial Bank other than Punjab National Bank. Claim period would be considered as mentioned on Bank Guarantee or 03 Months after the end of defect liability whichever is later.</p> <p>Bank guarantee if any submitted by the contractor/bidder shall remain valid for claim period or a period of 90 days beyond the date of completion of all contractual obligations.</p>

ARTICLES OF AGREEMENT

This agreement is made at on..... Day of..... 20.... between Punjab National Bank, a body corporate constituted under the Banking Companies (Acquisition and transfer of Undertaking Act 1970) having its Corporate office at Plot No. 4, Sector 10, Dwarka, New Delhi – 110075 and its office at **Punjab National Bank, Circle Office Guwahati, Nilgiri Mansion Bhangagarh, Guwahati, Assam- 781005** (Hereinafter referred to as "The Bank " which expression shall be deemed to mean and include its successors, administrators and permitted assigns) of the one part & (herein after called "the Successful Bidder/Contractor" which expression shall be deemed to mean and include its successors, administrators and permitted assigns) of the other part.

WHEREAS the Bank is desirous of executing work of **Carpentry, Electrical, Lan Cabling, Air Conditioning & other miscellaneous allied works at 3rd Floor of Rava Tower, Lutuma, A K Azad Road, Guwahati, Assam** and has by letter of acceptance dated.....accepted a tender by the Contractor for the execution, completion & maintenance of such work.

After discussion, the Bank and the bidder agree to enter into this agreement on the terms and condition set out hereunder:

NOW THIS AGREEMENT WITNESSES AS FOLLOWS:

1. In this agreement words and expressions shall have the same meaning as are respectively assigned to them in the said conditions of contract hereinafter referred to:
2. The following documents, terms and conditions contained therein shall form and construe as integral part and parcel of this agreement and be read as part and parcel of this agreement, viz.
 - a. Original tender document duly signed and stamped on each page by the authorised signatory of the bidder;
 - b. Relevant correspondence letters / communications forming parts of contract and referred to in acceptance letter;
 - c. Acceptance of Award of Work;
 - d. Bill of quantities ;
 - e. Corrigendum/Addendums (if published); and
 - f. Other additional documents as may be required.
3. The aforesaid documents shall be taken as complementary and mutually explanatory of one another, but in the case of ambiguities of discrepancies the latest documents issued by the Bank shall prevail over the earlier documents.
4. In consideration of payment to be made by the Bank to the successful bidder as hereinafter mentioned, the successful bidder hereby covenants with the Bank to perform execute, complete and maintain the work in due respects and in conformity with the provision of the contract and tender documents.
5. The Bank hereby covenants to pay the Contractor/successful Bidder in consideration of the execution, completion of the work such sums as shall become payable hereunder at the time(s) and in the manner prescribed in the said conditions and schedule/ bill of quantities (i.e. commercial bid) prescribed in the contract.

6. All disputes or differences whatsoever arising between the parties shall be settled amicably. If parties are not able to solve amicably, the same shall be settled by arbitration by a sole Arbitrator to be nominated by the competent authority of Punjab National Bank in accordance with Arbitration and Conciliation Act 1996 and the Rules and Regulations framed thereunder, as may be amended from time to time. The award made in pursuance thereof shall be binding on the parties.. Venue of arbitration shall be at Guwahati and the language shall be English. The Parties to the arbitration shall bear their own costs. The Arbitrator shall give a reasoned award.

7. All disputes arising out of or in connection with this agreement shall be deemed to have arisen in Guwahati and only the courts of Guwahati shall have the jurisdiction to determine the same.

8. Notices as required by the agreement that shall be entered with the successful bidder shall be sent to the addresses as would be mentioned first therein or such other addresses as the Parties may designate from time to time, and shall be sent by certified or registered mail with acknowledgement due on receipt.

SIGNED AND SEALED AND DELIVERED BY THE

Said

Said

(Name)

(Name)

on behalf of the Contractor

on behalf of the Bank

In the presence of

In the presence of

Name:

Name

Address:

Address:

This form is included in the tender documents only for the information of the bidders. Only the successful bidder will be in due course, required to complete the form.

GENERAL CONDITIONS OF CONTRACT (GCC)

Except where provided for in the description of the individual items in the Schedule of quantities and in the specification and conditions laid down herein after and in the drawings, the work shall be carried as per standard specifications and under the directions of the Bank.

1) INTERPRETATION

In construing these conditions, the specifications, the schedule of quantities, tender and agreement, the following words shall have the meaning herein assigned to them except where the subject of context otherwise requires:

- i. Employer: The term employer shall denote Punjab National Bank with their Head Office at Plot No. 4, Sector 10, Dwarka, New Delhi – 110075, and any of its employees or representative authorized to act on its behalf.
- ii. The Bank: The term Bank shall mean Punjab National Bank, the Employer.
- iii. The Engineer in charge: The term means Engineer of the Bank deployed to look after the work.
- iv. Contractor: The term Contractor shall mean M/s _____(name and address of the Contractor) and his/their heirs, legal representatives assigns and successors.
- v. Site: The site shall mean the site **3rd Floor of Rava Tower, Lutuma, A K Azad Road, Guwahati, Assam** where the works are to be executed as shown within boundary on the Site Plan including any building and erections thereon allotted by the employer for the Contractor's use.
- vi. Site Engineer: The Site Engineer may be appointed by the Bank. The Bank may also determine the number of Site Engineers and the supporting staff at site office- to assist him/ her and also whether the Site Engineer shall be temporary or permanent. As far as possible, the Site Engineer should assume charge of his post before the Contractor reports onsite of work. Where more than one Site Engineer is appointed, one of them shall be designated as Senior Site Engineer by the Bank and the other Site Engineer shall be reporting to the Senior Site Engineer.
- vii. Specifications and Drawings: The work is to be carried out by the Contractor in accordance with drawings, specifications, the schedule of quantities and any further drawings, which may be supplied, or any other instruction, which may be given by the Employer from time to time during the execution of the work.
- viii. Drawings relating to work given to the Contractor together with a copy of schedule of quantities are to be kept at site and Employer shall be given access to such drawings or schedule of quantities whenever necessary.
- ix. In case any detailed drawings are necessary, Contractor shall prepare such detailed drawings and/or dimensional sketches therefore and have it confirmed by the employer prior to taking up such work.
- x. The Contractor shall ask in writing for all clarifications on matters occurring anywhere in drawings, specifications and schedule of quantities or to additional instructions at least ten (10) days ahead of the time when it is required for implementations so as to enable the Employer to give a decision thereon.

- xi. "The Work" shall mean the work or works to be executed or done under this contract.
- xii. "Act of Insolvency" shall mean any act as such as defined by the Presidency Towns Insolvency Act or Provincial Insolvency Act or any Amending Statutes.
- xiii. "The Schedule of Quantities" shall mean the schedule of quantities as specified and forming part of this contract.
- xiv. Order of precedence for any ambiguity in the schedule of quantities, general conditions, special conditions, specifications and drawings for the Contractor shall be as per the decision of the Employer and the same will be binding on the Contractor, and shall be read as under in the decreasing order of importance.
 - a) Schedule of Quantities.
 - b) Drawings.
 - c) Special Conditions
 - d) General Conditions.
 - e) Standard (Technical) Specifications of Contract.
 - f) C.P.W.D specifications.
 - g) Bureau of Indian Standards specifications.
 - h) State P.W.D./General Engineering Practice.
 - i) Integrity Pact.

Any ambiguity observed shall be brought to the notice of Employer and shall be executed only after obtaining approval from the Employer. In case of any ambiguity between the above, the most stringent one shall follow.

2) SCOPE OF WORK

The work consists of **Carpentry, Electrical, Lan Cabling, Air Conditioning & other miscellaneous allied works at 3rd Floor of Rava Tower, Lutuma, A K Azad Road, Guwahati, Assam** in accordance with the "Schedule of Quantities". The Civil, Interior Furnishing, Furniture, Electrical, Sanitary & Plumbing, Air Conditioning etc. works are within the scope of this tender. It includes furnishing all materials, labour, tools and equipment and management necessary for and incidental to the completion of the work. All work, during its progress and upon completion, shall conform to the lines, elevations and grades as shown on the drawings furnished by the Employer. Should any detail essential for efficient completion of the work be omitted from the drawings and specifications it shall be the responsibility of the contractor to inform the Employer and to furnish and install such detail with Employer's concurrence only, so that upon completion of the proposed work the same will be acceptable and ready for use.

Employer or his representative may in their absolute discretion issue further drawings and/or written instructions, details, directions and explanations, which are, hereafter collectively referred to as "The Employer's instructions" in regard to:

- a) The variation or modification of the design quality or quantity of works or the addition or omission or substitution of any work; or
- b) Any discrepancy in the drawings or between the schedule of quantities and/or drawings and/or specification; or

- c) The removal from the site of any defective material brought thereon by the contractor and the substitution of any other material thereof; or
- d) The demolition removal and/or re-execution of any work executed by the contractors; or
- e) The dismissal from the work of any persons employed there upon; or
- f) The opening up for inspection of any work covered up; or
- g) The rectification and making good of any defects under clauses hereinafter mentioned and those arising during the maintenance period (retention period).

The contractor shall forthwith comply with and duly execute any work comprised in such Employer's or his representative's instructions, provided always that verbal instructions, Directions and explanations given to the contractor's or his representative upon the works by the Employer or his representative shall, if involving a variation, be confirmed in writing to the contractor(s) within seven days. No works for which rates are not specifically mentioned in the commercial bid shall be taken up without written permission of the Employer or his representatives. Rates of items not mentioned in the commercial bid shall be fixed by the Employer as provided in Clause "Variation/Deviation" hereunder.

Regarding all factory made products for which ISI marked products are available, only products bearing ISI marking shall be used in the work unless otherwise specifically requested by Bank.

3) VISIT OF SITE

Intending Bidder shall visit the site and make himself thoroughly acquainted with the local site conditions, nature and requirements of the works, facilities of transport conditions, effective labour and materials, accesses and storage for materials and removal of rubbish. The Bidder shall provide in their bid for cost of carriage, freight and other charges as also for any special difficulties and including police restriction for transport etc. for proper execution of work as indicated in drawings. The successful Bidder will not be entitled to any claim of compensation for difficulties faced or losses incurred on account of any site conditions which existed before the commencement of the work or which in the opinion of the Employer might be deemed to have reasonably been inferred to be so existing before commencement of work.

4) TENDERS

The e-tender should be submitted by bidder duly quoted commercial bid and also digitally signed.

The commercial bid shall be filled in as follows:

- i. The rates column to be filled.
- ii. The employer reserves the right to reject the lowest or any tender.

The Bank reserves the right to accept the tender in full or in part and the bidder shall have no claim for revision of rate or other conditions if his tender is accepted in parts.

The bidders should note that the tender is strictly on item rate basis and their attention is drawn to the fact that the rates for each and every item should be correctly worked out and self-supporting. The Employer may call upon a bidder for the detailed analysis of any or all of the rates shall be quoted/submitted by the Contractor. The Employer shall not be bound to recognize the Contractor's analysis.

The works shall be paid for as "measured work" on the basis of actual work done and not as "lump sum" contract.

All items of work described in the schedule of quantities are to be deemed and paid as complete works in all respects and details including preparatory and finishing works involved directly related to and reasonably detectable from the drawings, specifications and schedule of quantities and no further extra charges shall be allowed in this connection. In the case of lump sum charges in the tender in respect of any item of works, the payment of such items of work shall be made for the actual work done on the basis of lump sum charges as shall be assessed to be payable by the Employer and the same shall be binding on the Contractor.

The Employer has power to add to, omit from any works as shown in drawings or described in specifications or included in schedule of quantities and intimate the same in writing to the Contractor. However, no addition, omission or variation shall be made by the Contractor in any of the works without authorization from the Employer, and any such variation by the Bank shall not vitiate the contract.

The bidder shall note that his bid shall remain open for consideration for a period of 90 days from the date of opening of commercial bid.

5) CONTACTING THE BANK

Any effort by a bidder to influence the Bank in evaluation of the bid, bid comparison or contract award decision may result in the rejection of the Bidders' bid. Bank's decision will be final and without prejudice and will be binding on all parties.

6) CLARIFICATIONS OF BIDS

The Bank to assist itself in the examination, evaluation and comparison of bids may, at its discretion, ask any bidder for a clarification. The response should be in writing and no change in the price or substance of the bid shall be sought, offered or permitted.

7) AMENDMENT OF BIDDING DOCUMENTS

At any time prior to the last Date and Time for submission of bids, the Bank at its sole discretion may, for any reason, modify the Bidding Documents through amendments. All amendments shall be uploaded on the Bank's websites (www.pnbindia.in and <https://etender.pnbnnet.in>) and shall be binding on all who are interested in bidding.

In order to provide prospective Bidders a reasonable time to take into account the amendment if any, while preparing their bid, the Bank may, at its discretion, extend the deadline for submission of bids.

8) MODIFICATION AND WITHDRAWAL OF BID BY THE BIDDER

- i. Modification of the submitted bid shall be allowed on-line and the bidder may modify and resubmit the bid on-line only before the deadline of Bid Hash Preparation. For modification of e-bid, bidder has to rework and upload/resubmit digitally signed modified bid on bank's e-tendering portal i.e. <https://etender.pnbnnet.in>.
- ii. Bids once submitted will be treated as final and no bid may be modified subsequent to the deadline for Bid Hash Preparation.
- iii. No bid may be withdrawn in the interval between the deadline for submission of bids and the expiration of period of bid validity specified in tender documents. For withdrawal of bid after the end date of online bid submission, the bidder will have to make a request in writing to Tender Inviting Authority of Bank. Withdrawal of bid may be allowed till issue of issue of work order with the following provision of penal action:

a) If the request of withdrawal is received before fixing the date for opening of commercial bid, the EARNEST MONEY DEPOSIT submitted by bidder will be forfeited and bidder will be debarred for 6 months from participating in tenders in Punjab National Bank. The commercial bid of remaining technically qualified bidders will be opened and the tender process shall go on.

b) If the request of withdrawal is received after fixing the date for opening of commercial bid, the EARNEST MONEY DEPOSIT submitted by bidder will be forfeited and bidder will be debarred for 1 year from participating in tenders in Punjab National Bank. The commercial bid of all technically qualified bidders including this bidder (if he found technically eligible) will be opened and action will follow as under:

c) If the bidder withdrawing his bid is other than L-1, the tender process shall go on.

d) If the bidder withdrawing his bid is L-1, the re-tendering shall be done.

9) AGREEMENT

The successful Contractor may be required to sign agreement as may be drawn up to suit local conditions and shall pay for all stamps and legal expenses, incidental thereto.

10) RELATIONSHIP BETWEEN PARTIES:

The engagement of bidder shall not constitute the appointment of either Party as the legal representative or agent of the other Party. This engagement is on a Principal to Principal basis between the Parties hereto. No Party to this engagement shall have any right or authority to assume, create or incur any liability or any obligation of any kind, express or implied, against or in the name of or on behalf of the other Party to this Agreement except as may be specifically provided.

11) PUBLICITY

In connection with the transactions contemplated by this engagement/agreement each Party agrees that it will not use other Parties name, marks, symbols, or logos in any advertising, promotional material, press release, publication, public announcement, or through other media, whether written or oral, without the prior written consent of such other Party.

12) NON-EXCLUSIVITY:

It is expressly agreed that the engagement/agreement between the parties, shall be on a non-exclusive basis. Bank reserves its right to appoint/ engage one or more contractors/ agencies/ service providers to provide the like services or/ and work concurrently during the currency of engagement.

13) GOVERNMENT AND LOCAL RULES

The Contractor shall confirm to the provisions of all local Bye-laws and acts relating to the work and to the regulations etc. of the Government and local authorities and of any company with whose system the structure is proposed to be connected. The Contractor shall give all notices required by said act, rules, regulations and Bye- laws etc. and pay all fees payable to such concerned administrative/municipal authorities for execution of the work involved. The cost if any shall be deemed to have been included in his quoted rates, taking into account all liabilities for licenses etc. He shall indemnify the employer against such liabilities and shall defend all actions arising from such claims or liabilities.

14) TAXES AND DUTIES

The bidders must include in their quoted bid prices all duties, royalties, cesses, labour cess, GST or any other taxes or local charges, as applicable. TDS shall be deducted at source and the certificate in respect of TDS shall be issued by the Bank as per rule. Any variation in taxes and duties and/or imposing any new taxes and duties during currency of contract or extended period shall be borne by the bidder. No claim whatsoever on this account shall be entertained.

15) PROVISIONAL SUM (P.S.)

All provisional sums described in the schedule of quantities as P.S. shall be exclusively allotted to the purchase of materials and not for any handling and fixing to be done by the Contractor. Such cost of handling and fixing with profit (including transport charges if required) shall be separately included in the contract price as described in the schedule of quantities. The disposal of the amounts covered under this head shall be absolutely at the discretion of the Employer. The Contractor is liable to make payments for these materials to the suppliers on certificate or orders issued by the Employer and shall realize them through his bills from the Employer.

16) QUANTITY OF WORK TO BE EXECUTED

The quantities shown in the schedule of quantities are intended to cover the entire work but the Employer reserves the right to execute only a part or the whole or any excess thereof without assigning any reason therefore and the same shall be binding on the Contractor.

17) OTHER PERSONS ENGAGED BY THE EMPLOYER

The employer reserves the right to execute any part of the work included in this contract or any work which is not included in this contract by other agency or persons and Contractor shall allow all reasonable facilities and use of his scaffolding for the execution of such work.

18) TOTAL SECURITY DEPOSIT

The Total Security Deposit on the contract should be 8% of the contract amount. Total Security Deposit comprises of the following:

i) Earnest Money Deposit

The bidder will have to deposit Earnest Money Deposit (EMD) of **₹1,95,676/- (Rupees One Lakh Ninety-Five Thousand Six Hundred Seventy-Six Only)**. EMD shall be accepted in form of Insurance Surety Bonds, Account Payee Demand Draft (in favour of Punjab National Bank payable at Guwahati), Fixed Deposit Receipt (lien to be marked in favour of PNB), Bankers' Cheque (in favour of PNB) or Bank Guarantee (including e-Bank Guarantee) (from any Scheduled Commercial Bank other than PNB) or online payment in non-customer account (i.e. A/c No:3796003171160 & IFSC Code: PUNB0379600) of (the procuring office of PNB). EMD is to be submitted with Envelope-I. EMD should be valid within the bid validity period of 90 days after the date of opening of commercial bid. The bidder shall also extend the EMD validity without giving any reasons, for the duration whatever requested by the Bank.

Bid Securities (i.e. EMD) of unsuccessful bidders shall be returned within 30 days of declaration of result of technical evaluation. EMD of successful contractor be kept in sundries account of Bank. The employer is not liable to pay any interest on the Earnest Money.

ii) Performance Security

Performance Security will be 3% of the contract sum. This performance security will be inclusive of EMD amount. Successful Bidder need to submit the performance security within 3 days of award of work. The performance security can be submitted in form of Insurance Surety Bonds, Account Payee Demand Draft (in favour of PNB payable at Guwahati, Fixed Deposit Receipt (lien to be marked in favour of PNB), Bankers' Cheque (in favour of PNB) or Bank Guarantee (including e-Bank Guarantee) (from any Scheduled Commercial Bank other than PNB) or online payment in non-customer account (i.e. A/c No:3796003171160 & IFSC Code: PUNB0379600) of (the procuring office of PNB). Performance security for works shall be returned to the Successful Bidder within 14 days after virtual completion of work

iii) Retention Money

- a) The retention percentage (i.e. deduction from the interim bill) shall be 8% of the gross value of each interim bill.
- b) The maximum amount of retention money shall be 5 % of the contract value.
- c) Retention amount will be refunded within 30 days after expiry of defects liability period provided he has satisfactorily carried out all the works, attended to all defects in accordance with the conditions of the Contract, including the site clearance.
- d) After completion of work, Retention money can be refunded after obtaining a Bank Guarantee of equivalent amount for a time period till the end of defect liability period plus claim period. Bank Guarantee should be from any Scheduled Commercial Bank other than Punjab National Bank. Claim period would be considered as mentioned on Bank Guarantee or 3 months after the end of defect liability whichever is later.
- e) Bank guarantee if any submitted by the contractor/bidder shall remain valid for a period of 90 days beyond the date of completion of all contractual obligations.

19) CONTRACTOR TO PROVIDE EVERYTHING NECESSARY

The Contractor shall provide everything necessary for the proper execution of work according to the intent and meaning of the drawings, schedule of quantities and specifications taken together whether the same may or may not be particularly shown or described therein provided that the same can reasonably be inferred there from and if the Contractor finds any discrepancies therein, he shall immediately and in writing refer the same to the employer whose decision shall be final and binding.

The rates quoted against individual items will be inclusive of everything necessary to complete the said items of work within the contemplation of the contract and beyond the unit price. No extra payments will be allowed for incidental or contingent work, labour and/or materials inclusive of all taxes and duties whatsoever except for specific taxes, if any, stipulated in the tender documents.

The Contractor shall supply, fix and maintain at his own cost for the execution of work, all tools tackles, machinery and equipment and all the necessary centering, scaffolding, fencing, boarding, watching and lighting by night as well as by day required not only for the proper execution and protection of the said work but also for the protection of the public and safety of any adjacent roads, streets, walls, houses, buildings all other erections, matters and things and Contractor shall take down and remove any or all such centering, scaffolding, planking, timbering, strutting, shoring etc. as occasion shall be required or when ordered to do so and shall fully reinstate and matters and things distributed during the execution of works to the satisfaction of the Employer.

The Contractor shall at all times give access to workers by the Employer or any men employed on the buildings.

20) TIME OF COMPLETION, EXTENSION OF TIME & PROGRESS CHART

20.1) Time of completion

The entire work is to be completed in all respects within the stipulated period **45 Days** from the commencement date. Time is the essence of the contract and shall be strictly observed by the Contractor.

The work shall not be considered as completed until the Employer have certified in writing that work has been completed and the defects liability period shall commence from the date of such certificate.

20.2) Extension of Time

If, in the opinion of the Employer the works be delayed

- a) By reason of instruction from the employer in consequence of proceedings taken of threatened by or disputes, with adjoining or neighboring owners or
- b) By the works, or delay, of other contractors or tradesmen engaged or nominated by the Employer and not referred to in the specification or
- c) By reason of authorized extra and additions or
- d) By reason of any combination of workmen or strikes or lock-out effecting any of the building trades or
- e) From other causes which the employer may consider are beyond the control of the Contractor, the Employer at the completion of the time allowed for the contract, shall make fair & reasonable extension of the time for completion in respect therefore. In the event of the Employer failing to give possession of the site upon the day specified above the time of completion shall be extended suitably.

In case of such strikes or lock-outs, as are referred to above, the Contractor shall immediately give the Employer, written notice thereof. Nevertheless, the Contractor shall use his best endeavors all that to prevent delay, and shall do all that may be reasonably required, to the satisfaction of the Employer to proceed with the works and on his doing so that it will be ground of consideration by the Employer for an extension of time as above provided. The decision of Employer as to the period to allow for an extension of time for completion hereunder (Which decision shall be final and binding on the Contractor) shall be promulgated at the conclusion of such strike or lock-out and the employer shall then, in the event of an extension being granted, determine and declare the final completion date. *The provision in clause 20.4 with respect to payment of liquidated damages shall, in such case, be read and construed as if the extended date fixed by the employer were substituted for and the damage shall be deducted accordingly.*

20.3) Progress of work

During the period of execution, the Contractor shall maintain proportionate progress on the basis of a programmed chart submitted by the Contractor immediately before commencement of work and agreed to by the Employer. Contractor should also include planning for procurement for scarce material well in advance and reflect the same in the programmed chart so that there is no delay in completion of project. A Progress report of the work is to be submitted by the Contractor fortnightly in the format approved by the Employer.

20.4) Liquidated Damages

Should the work be not completed to the satisfaction of the Employer within the stipulated period, the Contractor shall be bound to pay to the employer a sum calculated as given

below by way of liquidated damages and not as penalty during which the work remains uncommenced or unfinished after the expiry of the completion date.

0.5% of the contract amount shown in the tender per week subject to the ceiling of 7.5% of the accepted contracted sum. Any delay beyond this, Punjab National Bank shall be free to terminate the contract and get the work done from an alternate source at the risk of the contractor.

21) TOOLS, STORAGE OF MATERIALS, PROTECTIVE WORKS AND SITE OFFICE REQUIREMENTS

The Contractor shall provide, fix up and maintain in an approved position proper office accommodation for the contractor's representative and staff which offices shall be open at all reasonable hours to receive instruction notices or communications and clear way on completion of the works and make good all work disturbed.

All drawings maintained on the site are to be carefully mounted on boards of appropriate size and covered with a coat of approved varnish. They are to be protected from ravages of termites, ants, and other insects.

The contractor shall provide at his own cost all artificial light required for the work to complete the work within the specified time.

The contractor shall arrange for temporary latrines and other welfare provision as per the applicable labour laws for the use of workers and field staff and keep the same in a clean and sanitary condition to the satisfaction of the Public Health Authorities and shall cause such latrines and soil to be cleared away whenever necessary and shall make good all the works disturbed by these conveniences.

Every precaution shall be taken by the contractor to prevent the breeding of mosquitoes on the works during the construction, and all receptacles cisterns, water tanks etc. used for the storage of water must be suitably protected against breeding of mosquitoes. The contractor shall indemnify the Employer against any breach of rules in respect of anti-malarial measures.

The contractor shall not fix or place any placards or advertisement of any description or permit the same to be fixed or placed in or upon any boarding, gantry, building structure other than those approved by the Employer.

Protective- Measures: The contractor from the time of being placed in possession of the site must make suitable arrangements for watching, lighting and protecting the work, the site and surrounding property by day, by night, on Sundays and other holidays.

Contractor shall indemnify the Employer against any possible damage to the building, roads, or members of the public in course of execution of the work.

Storage of materials: The contractor shall maintain proper storage and adequate protection of the materials etc. and other work that may be executed on the site including the tools and materials and remove same on completion.

Godown shall be erected / provided for storing about six weeks' requirement of material. Structure shall be water-proof from all the sides and top. Material should be stored one feet-above the ground level and have pucca/ wooden raised floor.

Tools: Theodolite levels, prismatic compass, chain, steel and metallic tapes and all other surveying instruments found necessary on the works shall be provided by the contractor for the due performance of this contract as instructed by the Official assigned by Bank/ Site Engineer. All measuring tapes shall be of steel and suitable scaffolding and ladders that may be required for safely taking measurement shall be supplied by the contractor.

The mistries and the supervisors on the works shall carry with them always a one metre or two metre steel tape, a measuring tape of 30 metres, a spirit level, a plumb bob and a square and shall check the work to see that the work is being done according to the drawing and specifications. The Official assigned by Bank/ Site Engineer will use any or all measuring instruments or tools belonging to the contractors as he chooses for checking the works executed or being executed on the contract. The contractor should cover in his rates for making provision for all reasonable facilities for the use of his scaffolding, tools and plant etc., for their work and no claims shall be entertained afterwards by the Employer in any case whatsoever.

22) NOTICE AND PATENTS OF APPROPRIATE AUTHORITY AND OWNERS

The Contractor shall confirm to the provisions or any acts of the legislature relating to the work, and to the regulations and by-laws of any authorities, and / or any water, lighting and other companies, and / or authorities with whose system the structures were proposed to have renovated and shall before making any variation from the drawings or specifications that may be associated to so confirm, give the Employer written notice, specify the variations proposed to be made and the reasons for making them and apply for instructions thereon. The Employer on receipt of such intimation shall give a decision within a reasonable time.

The Contractors shall arrange to give all notices required for by the said acts, regulations or By- laws to be given to any authority, and to pay to such authority or to any public officer all fees that may be properly chargeable in respect of the work and lodge the receipts with the Employer.

The Contractor shall indemnify the Employer against all claims in respect of patent rights, royalties, and damages to buildings, roads or member of public in course of execution of work and shall defend all actions arising from such claims and shall keep the Employer saved harmless and indemnified in all respects from such actions, costs and expenses.

23) CLEARING SITE AND SETTING OUR WORKS

The site shall be cleared of all obstructions, loose stone, and materials rubbish of all kinds.

24) CONTRACTOR IMMEDIATELY TO REMOVE ALL OFFENSIVE MATTERS FROM THE SITE

The Contractor shall keep the surroundings of work places free from water, debris and excess / waste materials at his own expenses Electrical or other power driven equipment to the satisfaction of the Employer for the purpose, until the site is handed over to the Employer. The Contractor shall arrange for the disposal of the same so accumulated to the satisfaction of the Employer and the local authority and no claims will be entertained afterwards if he does not include in his rates for the purpose.

25) ACCESS

Any authorized representative of the Employer shall at all reasonable times have free access to the works and / or to the workshops, factories or other places where materials are being prepared or constructed for the work and also to any place where the materials

are lying or from where they are being obtained, and the Contractor shall give every facility to the Bank or their representatives necessary for inspection and examination and test of the materials and workmanship. Except the representatives of the Employer, no person shall be allowed at any time without the written permission of the Employer.

26) MATERIALS, WORKMANSHIP, SAMPLES, TESTING OF MATERIALS

All the works specified and provided for in the specification or which may be required to be done in order to perform and complete any part thereof shall be executed by the Contractor in the best and most workman like manner with materials of the best and approved quality of the respective kinds in accordance with the particulars contained in and implied by the specifications and as represented by the drawings or according to such other additional particulars and instructions as may from time to time be given by the Employer during the execution of the work, and to his entire satisfaction.

If required by the Employer the Contractor at his own cost shall have to carry out tests on materials and workmanship in approved materials testing laboratories or as prescribed by the Employer to prove that the materials etc. under test confirming to the relevant IS standards or as specified in the specifications. The necessary charges for preparation of sample, transporting, testing etc. shall have to be borne by the Contractor. No extra payment on this account would in any case be entertained by the Employer.

All the materials (except where otherwise described) stores and equipment required for the full performance of the work under the contract must be provided through normal channels and must include charge for import duties, sales taxes, octroi, GST and other charges and must be the best of their kind available and contractors must be entirely responsible for the proper and efficient carrying out of the work. The work must be done in the best workman like manner. Samples of all materials to be used must be submitted to the Employer when so directed by the Official assigned by Bank/ site Engineer and a written approval from Employer must be obtained prior to placement of order of such materials.

During the inclement weather the Contractor shall suspend works for such times as the Employer may direct and shall protect from damage all work during course of execution. Any damage (during repair & renovation) to any part of the work for any reason due to rain, storm or neglect of Contractor shall be rectified by the Contractor in an approved manner at no extra cost to the Bank.

Should the work be suspended by reason of rain, strike, lock-outs or any other cause, the Contractor shall take all precautions necessary for the protection of work and at his own expense shall make good any damage arising from any of these causes.

The Contractor shall cover up and protect from damage, from any cause, all new work and supply all temporary doors, protection to windows, and any other requisite protection for the execution of the work whether by himself or special tradesmen or sub-Contractor and any damage caused must be made good by the Contractor at his own expenses.

Contractor to carry out all mandatory tests as per CPWD specifications besides the tests required to be done as ordered and desired by the Bank to prove that quality of material conforms to tender provisions. Cost of such tests shall be borne by the contractor and no extra payment in this regard shall be payable.

27) REMOVAL OF IMPROPER WORK

The Employer shall during the progress of the work have power to order in writing from time to time the removal of any materials etc. from the work within such reasonable time or times as may be specified in the order which in the opinion of the Employer are not in accordance with specification or instructions. The employer shall have the said powers in case of the substitution or proper re-execution of any work executed with materials or workmanship is not in accordance with the drawings and specifications or instructions. In case the Contractor refuses to comply with the order the Employer shall have the power to employ and pay other agencies to carry out the work and all expenses consequent thereon or incidental there to as certified by the Employer. Such expenses or costs paid by the Employer shall be borne by the Contractor or may be deducted from any money due to or that may become due to the Contractor.

28) SITE ENGINEER

The term "Site Engineer" shall mean the person posted at site by Employer to superintend the work. The Contractor shall afford the Site Engineer every facility and assistance for examining the works and materials for checking and measuring work and materials. The Site Engineer shall have no power to revoke, alter, enlarge or relax any requirements of the Contractor or to sanction any day work, additions, alterations, deviations, or omissions or any extra work whatever, except in so far as such authority may be specially conferred by a written order of the Employer.

The Site Engineer shall have power to give notice to the Contractor or to his foreman of non- approval of any work or materials and such work shall be suspended or the use of such materials shall be discontinued until the decision of the Employer is obtained. The work will from time to time be examined by the Engineer from the premises department of the Employer and the Site Engineer, if any, but such examination shall not in any way exonerate the contractor from the obligation to remedy and defects which may be found to exist at any stage of the work or after the same is complete. Subject to the limitations of this clause, the Contractor shall take instruction only from the Employer.

29) CONTRACTOR'S EMPLOYEES

The Contractor shall employ technically qualified and competent supervisors for the work who shall be available (by turn) throughout the working hours to receive and comply with instructions of the Employer. The Contractor shall engage at least one experienced Engineer as Site-in-Charge for execution of the work. The Contractor shall employ in connection with the work persons having the appropriate skill or ability to perform their job efficiently.

The Contractor shall employ local labourers on the work as far as possible. No labourer below the age of eighteen years and who is not an Indian national shall be employed on the work. Any Labourer supplied by the Contractor to be engaged on the work on day work basis either wholly or partly under the direct order or control of the Employer or his Representatives, shall always be deemed to be a person employed by the Contractor.

The Contractor shall maintain relevant records and comply with the provisions of all applicable labour legislations, rules and regulations framed thereunder, both state and central, including but not limited to the requirements of:-

- a. The Payment of Wages Act
- b. Employer's Liability Act
- c. Workmen's Compensation Act
- d. Contract labour (Regulation 7 Abolition) Act, 1970 and Central Rules 1974
- e. Apprentices Act 1961

- f. Minimum Wages Act 1948.
- g. Industrial Disputed Act. 1947.
- h. Maternity Benefit Act 1961.
- i. ESI Act.
- j. Payment of Bonus Act.
- k. Payment of Gratuity Act.
- l. The Employees' Provident Funds and Miscellaneous Provisions Act, 1952
- m. Any other Act are enactment relating thereto and rules framed there under from time to time.

The Contractor shall keep the Employer saved, harmless and indemnified against all the claims under applicable labour laws or otherwise, if any, of the workmen or any other person and all costs and expenses as any be incurred by the Employer in connection with any claim that may be made by any workman or any other person. The successful bidder shall be responsible for settling any claim / compensation against any and all damages and accidents caused due to negligence on the part of his employees/workers engaged by it for fulfilling the obligations under this agreement and keep Bank indemnified from any compensation / liability.

Bank shall not be responsible for any violation by the Contractor on the above mentioned acts/ rules. The Contractor shall be wholly/ solely responsible for any claim in the above referred subjects

The contractor shall be responsible for all statutory provisions and deductions towards ESI, PF or any other applicable Labour Laws, as the case may be or any other levies and taxes shall be borne by the contractors.

The contractor shall be responsible for payments of all statutory dues with respect to each of his personnel/employees engaged by him to render service under this Agreement with respect to each applicable/extant labour law. No dues/contributions under any labour legislations as applicable, remain payable by the Employer with respect to his personnel/employees, and the contractor shall produce all records to the Engineer-in-charge or any other statutory authority as and when called for. The Engineer- in-charge does not hold any responsibility on account of any lapses in this regard. The contractor shall submit an undertaking in this regard with each bill confirming payment of all dues of sub-contractors and all statutory wages to labour working under him/her/sub-contractor.

Bank shall not be held responsible for any penalty on failure of the any Labour Regulations. Bank shall have the power to inspect the Wage Register and for physical verification of salary paid to the staff with reference to any records of the Contractor and to insist the Contractor to comply with Laws.

The Contractors shall arrange to provide first-aid treatment to the labourers engaged on the works. He shall within 24 hours of the occurrence of any accident at or about the site or in connection with execution of the works, report such accident to the employer and also to the competent authority where such report is required by law.

30) DISMISSAL OF WORKMEN

The Contractor shall in the request of the Employer immediately dismiss from works any person employed thereon by him who may in the opinion of the Employer be unsuitable or incompetent or who may misconduct himself. Such discharges shall not be the basis of claim for compensation or damages against the Employer or any of its officers or employee.

31) ASSIGNMENT

The whole of the works included in the contract shall be executed by the Contractor and the Contractor shall not directly or indirectly transfer, assign or sublet the Contract or any part, share or interest therein nor, shall take a new partner without written consent of the Employer and no subletting shall relieve the Contractor from the full and entire responsibility of the contract or from active superintendence of the work during their progress.

32) PROTECTION OF WORKS AND PROPERTY

The contractor shall continuously maintain adequate protection of all his work from damage and shall protect the Punjab National Bank's properties from injury or loss arising in connection with the contract. He/ She shall make good any such damage, injury, loss, except due to causes beyond his control and due to his fault or negligence.

He/ She shall take adequate care and steps for protection of the adjacent properties. The contractor shall take all precautions for safety and protection of his temporary / permanent / contract employees/workers engaged on the works and shall comply with all applicable provisions of state/central Government and local bodies including all applicable safety laws and building codes to prevent accidents, or injuries to persons or property of about or adjacent to the place of work.

The Contractor shall be responsible for all injury to the worker or workmen or persons, animals or things and for all damages to the project works, materials, equipment, structural and / or decorative part of property which may arise from the operations or neglect of himself or employees/workers whether such injury or damage arise from carelessness, accident or any other cause whatsoever in any way connected with the carrying out of this contract.

The clause shall be held to include inter-alia any damage to buildings whether immediately adjacent or otherwise and any damage to roads, streets, foot paths or ways as well as damages caused to the buildings and the works forming the subject of this contract by rain, wind or other inclemency of the weather.

The Contractor shall reinstate, rectify and remedy all damages of every sort mentioned in this clause so as to deliver the whole of the contract works complete and perfect in every respect and so as to make good or otherwise satisfy all claims for damages to the property or third party.

33) DAMAGE TO PERSONS AND PROPERTY

The Contractor shall be responsible for all injury to the worker or workmen or persons, animals or things and for all damages to the project works, materials, equipment, structural and / or decorative part of property which may arise from the operations or neglect of himself or employees whether such injury or damage arise from carelessness, accident or any other cause whatsoever in any way connected with the carrying out of this contract.

The clause shall be held to include inter-alia any damage to buildings whether immediately adjacent or otherwise and any damage to roads, streets, foot paths or ways as well as damages caused to the buildings and the works forming the subject of this contract by rain, wind or other inclemency of the weather. The Contractor shall indemnify the Employer and hold harmless in respect of all and any expenses arising from any such injury or damages to persons or property as aforesaid and also in respect of any claim

made in respect of injury or damage under any acts of compensation or damage consequent upon such claim.

The Contractor shall reinstate, rectify and remedy all damages of every sort mentioned in this clause so as to deliver the whole of the contract works complete and perfect in every respect and so as to make good or otherwise satisfy all claims for damages to the property or third party.

34) INSURANCE

Unless otherwise instructed the Contractor shall insure the works for all risk (include fire & third party) of the Contractor for 125% of the total tender value in the joint names of the Punjab National Bank and the contractor (the name of Punjab National Bank placed first in the policy) and keep them insured until the virtual completion of the contract against any loss or damage of the material and of project. The insurance must be placed with a company approved by Punjab National Bank for such amount and for any further sum if called to do so by Punjab National Bank. The premiums of such further sum being allowed to the Contractor as an authorized extra. The Contractor shall deposit the policy and receipt of premium paid with Punjab National Bank within three (3) days from the date of issue of work order unless otherwise instructed.

In default of the Contractor insuring as provided above, Punjab National Bank on its behalf may so insure and may deduct the premiums paid from any money due, or which may become due to the Contractor. The Contractor shall as soon as the claim under the policy is settled or the work reinstated by Insurance Company should they elect to do so, proceed with due diligence with the completion of the works in the same manner as though the fire has not occurred and in all respects under the conditions of the contract. The Contractor in case of rebuilding or reinstatement after fire shall be entitled to extension of time for completion, as the Employer may deem fit.

35) ACCOUNTS RECEIPT & VOUCHERS

The Contractor shall, upon the request of the Employer furnish them with all the invoices, accounts, receipts and other vouchers that they may require in connection with the works under this contract. If the Contractor shall use materials less than what he is required under the contract, the value of the difference in the quantity of the materials he was required to use and that he actually used shall be deducted from his dues. The decision of the Employer shall be final and binding on the Contractor as to the amount of such materials. The Contractor is required to use for any work under this contract.

36) MEASUREMENTS

Before taking any measurement of any work the Official assigned by Bank/ Site Engineer or a subordinate deputed by him shall give reasonable notice to the Contractor. If the Contractor fails to attend at the measurements after such notice or fails to countersign or to record the difference within a week from the date of measurement in the manner required by the Official assigned by Bank/ Site Engineer then in any such event the measurements taken by the Official assigned by Bank/ Site Engineer or by the subordinate deputed by him as the case may be is final and binding on the Contractor and the Contractor shall have no right to dispute the same.

37) PAYMENTS

All bills shall be prepared & submitted by the Contractor in the form prescribed by the Employer. Normally one interim bill shall be prepared each month subject to minimum value for interim certificate as stated in these documents. The bills in proper forms must

be duly accompanied by detailed measurements in support of the quantities of work done and must show deductions for all previous payments, retention money etc. The bill shall be checked at site by Official assigned by Bank/ Site Engineer who shall issue a certificate after due scrutiny of the Contractor's bill which may be further verified by the Employer and the Contractor shall be entitled to payment thereof within the period of honouring certificates named in these documents, as per final verified amount by the Employer. In case of delay, an Adhoc advance of 75% of the billed amount /assessed work done may be paid on the request of the Contractor for the smooth progress of work at the sole discretions of the Bank.

The amount as stated in an interim certificate shall be the total value of work properly executed and secured advance on the materials as described under the heading of secured advance less the amount to be retained by the Employer as Retention Money vide clause 18 (iii) of these conditions and less installments previously paid under these conditions, provided that such certificate shall only include the value of said material and goods as and from such time as they are reasonably, properly and not prematurely brought to or placed adjacent to the work and then only if adequately protected against whether or other casualties.

The Employer will deduct retention money as described in Clause 18 (iii) of these Conditions. The refund of retention money will be made as specified in the said clause.

If the Employer had supplied any materials or goods to the Contractor, the cost of any such materials or goods will be progressively deducted from the amount due to the Contractor in accordance with the quantities consumed in the work.

All the interim payments shall be regarded as payment by way of advance against the final payments only and not as payments for work actually done and completed and shall not preclude the requirement of bad or unsound or imperfect or unskilled work to be removed and taken away and be reconstructed or re-erected or to be considered as an admission of the due performance of the contract or any part thereof in any respect or the accruing of any claim. Any interim payments shall not conclude determine or affect in any way the powers of the Employer under these conditions or any of them as to the final settlement and adjustment of the accounts or otherwise or in any other way to vary or affect the contract. The final bill shall be submitted by the Contractor within one month of the date fixed for completion of the work or of the date of certificate of virtual completion furnished by Employer and payment shall be made within 30 Days from the date of submission of appropriate invoice.

38) SECURED ADVANCE FOR MATERIAL AT SITE

The secured advance will be paid up to an amount not exceeding 75% of the invoiced value of the materials, (The amount of secured advance should not exceed 75% of the material element cost in the tendered rate of the finished item of work subject to ceiling of 65% of quoted rates) brought to site for permanent incorporation into the work up to the date of bill on production of supporting bills / vouchers. The secured advance on the non-perishable materials will be paid on execution of the indemnity bond/Bank guarantee.

39) FINAL PAYMENTS

The period of Final Measurements will be one (1) Month from the date of Completion. The final bill shall be accompanied by a certificate of completion from the Employer, payments of final bill shall be made after deduction of Retention Money as specified in clause 18 (iii) of these condition, which sum shall be refunded after the completion of the Defects liability period and rectification of defects to the entire satisfaction of the Employer. The

acceptance of payments of the final bill by the Contractor would indicate that he would have no further claim in respect of the work executed.

40) VARIATION / DEVIATIONS

The Contractor may when authorized and shall, when directed in writing by the Employer add or omit, or vary the works shown in the drawings or described in the specifications or included in the commercial bid. The Contractor on his own accord shall make no addition omission or variation without such authorization or direction of the Employer. A verbal authorization of direction by the Employer shall when confirmed correctly by the Contractor in writing within 3 days shall be deemed to have been given in writing.

The Contractor shall send to the Employer once in every month a statement giving particulars, as full and as much detailed as possible, of all claims for any additional payment to which the Contractor may consider himself entitled and of all extra or additional works ordered by the Employer which he has executed during the preceding month.

No interim claim for payment for any such work or expense, will be considered which has not been included in such a statement provided always that the Contractor shall be entitled after taking Employer's sanction to authorize payment to be made for any such work or expense, notwithstanding the Contractor's failure to comply with this condition.

The rates for additional, altered substituted work shall be arrived at in accordance with the following rules:-

- i. The net rates in the commercial bid shall determine the valuation of (the rates for) the extra work (items) where such extra work is of similar character and is executed under similar conditions as the work price mentioned therein.
- ii. If the rates for the extra altered or substituted or (deviated) work are not provided for (available) in the schedule of quantities, they shall, to the extent possible be derived out of rate given in that schedule for similar or near similar items. For the purpose of such deviation, where necessary and when so directed, the Contractor shall furnish detailed analysis for the said similar or near similar items in the contract schedule.
- iii. In respect of contract which incorporates more than one schedule, the rate applicable in case (i) above if not provided for in the Schedule pertaining to the work in which the addition, alteration or substitution (deviation) occurs shall be taken as the lowest applicable rate in other schedules. Similarly in case (ii) above if similar in near similar items cannot be found in the schedule pertaining to the work in which the addition, alteration or substitution (deviation) occurs, similar or near similar items from the other schedule shall be adopted.
- iv. In the case of additional, altered substituted (deviated) for which rates cannot be reasonably be derived as at (ii) and (iii) above, the rates shall be worked out adopting market rate, substantiated by purchase bills / vouchers using factors and constants for quantum of materials, labour, T&P and sundries from standard analysis of rates adopted by the CPWD and adding 15% towards profit & overheads and taxes and multiplied by (total quoted tendered amount divided by estimated cost put to tender), if tendered amount is below the estimated cost put to tender. However, if tendered amount is above the estimated cost put to tender, the extra item shall be calculated by market rate analysis (i.e. market rates sustained by purchase bill / vouchers dependable printed price schedule of materials of different type shall be adopted, using factors and constant for quantum of materials, labour, T&P and sundries, from standard analysis of rates adopted by the

CPWD, and adding 15% towards profit & overheads and taxes). When called upon to do so the Contractors shall submit his purchase bills / vouchers to the Employer.

- v. The question as to what particular items, being similar or near similar to the additional, altered or substituted (deviated) work in the contract schedule are to be adopted for deviation of rates for the additional, altered or substituted deviated work and whether the said rates cannot be derived from similar or near similar items in the contract schedule shall be decided by the Employer and the same shall be binding on the Contractor.
- vi. In case (ii) to (iv) the Contractor is required to submit his analysis of rates adopting the principles enunciated, after scrutinizing the analysis any other papers furnished will allow such rates as he considers reasonable after obtaining Employer's sanctions.
- vii. Where extra work is of such a nature that it cannot be properly measured or valued, the Contractor shall be allowed day work priced at the net rates stated in the tender or commercial bid or if not so stated then in accordance with the minimum local day work rates and wage for the district notified by the concerned authority provided that in either case if required by the Employer, vouchers, muster rolls and other documents, required for proper verification of the labour employed and the materials deployed on the said work and the costs thereof be delivered to the Official assigned by Bank/ site Engineer or his representative on or before the end of the week following that in which work has been executed.
- viii. The question as to whether extra work is of such nature that it cannot be properly measured or valued will be decided by the Employer. The margin to be allowed on actual costs to the Contractor towards profit and overhead shall be 15% and taxes and multiplied by (total quoted tendered amount divided by estimated cost put to tender), if tendered amount is below the estimated cost put to tender. However, if tendered amount is above the estimated cost put to tender, the extra item shall be calculated by market rate analysis (i.e. market rates sustained by purchase bill / vouchers dependable printed price schedule of materials of different type shall be adopted, using factors and constant for quantum of materials, labour, T&P and sundries, from standard analysis of rates adopted by the CPWD, and adding 15% towards profit & overheads and taxes).

41) DEVIATION FOR TENDER QUANTITIES UPTO 25% & ABOVE 25%

The tender rates shall hold good for any increase in the tendered quantities up to variation of 25%. In case tender quantities of an individual item exceeds the deviation limit of 25% the rates for the excess quantities over and above the deviation limit shall be payable as per market rates analysis or quoted rates in tender, whichever is lower. The market rates analysis sustained by purchase vouchers / bill using constant only of materials, Labour, T&P etc. from all Indian Standard analysis of rates published by Delhi Analysis of Rates with 15% towards Contractors profit. & Overheads and taxes.

42) SUBSTITUTION

Should the Contractor desire to substitute any materials and workmanship, he/they must obtain the approval of the Employer in writing for any such substitution well in advance. Materials designated in this specification indefinitely by such terms as "Equal" or "other approved" etc., specific approval of the Employer has to be obtained in writing. The rate of substitution item shall be calculated as per market rate analysis, sustained by purchase vouchers / bill using constant only of materials, labour, T&P etc. from all Indian Standard analysis of rates published by CPWD with 15% towards Contractors profit & Overheads and taxes and multiplied by (total quoted tendered amount divided by estimated cost put to tender), if tendered amount is below the estimated cost put to tender. However, if

tendered amount is above the estimated cost put to tender, the extra item shall be calculated by market rate analysis (i.e. market rates sustained by purchase bill / vouchers dependable printed price schedule of materials of different type shall be adopted, using factors and constant for quantum of materials, labour, T&P and sundries, from standard analysis of rates adopted by the CPWD, and adding 15% towards profit & overheads and taxes).

43) PREPARATION OF BUILDING WORKS FOR OCCUPATION AND USE ON COMPLETION

The whole of the work will be thoroughly inspected by the Contractor and deficiencies and defects put right. On completion of such inspection and Contractor shall inform the Employer that he has completed the work and it is ready for inspection.

On completion, the Contractor shall clean all equipment's and does the painting work etc. He will leave the entire installation neat and clean and ready for immediate use and to the satisfaction of the Bank.

44) CLEARING SITE ON COMPLETION

On completion of the works, the Contractor shall clear away and remove from the site all constructional plant, surplus materials, rubbish and temporary works of every kind and leave the whole of the site and the works clean and in a workman like condition to the satisfaction of the Employer.

45) DEFECTS AFTER COMPLETION

The defects liability period (D.L.P.) shall commence from the certified date of Virtual Completion issued by the Employer. The Contractor shall make good at his own cost and to the satisfaction of the Employer all defects, other faults which may appear within twelve (12) Months after completion of the work. In default, the Employer may employ and pay other persons to amend and make good such damages, losses and expenses consequent thereon or incidental thereto shall be made good and borne by the Contractor and such damages, losses and expenses shall be recoverable from him by the employer or may be deducted by the Employer, in lieu of such amending and making good by the Contractor, deduct from any money due to the Contractor a sum equivalent to the cost of amending such work and in the event of the amount retained being insufficient, recover that balance from the Contractor from the amount retained under clause no. 18 together with any expense the Employer may have incurred in connection therewith.

46) CONCEALED WORK

The Contractor shall give due notice to the Employer whenever any work is to be buried in the earth, concrete or in the bodies of walls or otherwise becoming inaccessible later on, in order that the work may be inspected and correct dimensions taken before such burial, in default whereof the same shall, at the option of the employer be either open up for measurement at the Contractor's expense or no payment may be made for such materials. Should any dispute or difference arise after the execution of any work as to measurements etc., or other matters which cannot be conveniently tested or checked, the notes of the Employer shall be accepted as correct and binding on the Contractor.

47) WATCH AND LIGHTING

The Contractor shall provide and maintain at his own expense all lights, guards, fencing and watching when and where necessary or required by Employer for the protection of the works or for the safety and convenience of those employed on the works or the public.

48) CONTROL RECORDS

The under noted record books at the site of work shall be maintained in addition to normal routine requirements by the Contractor at all times which shall be made accessible to the Employer as and when required by it:

- a. Work site order book.
- b. Instruction by Bank's officers.
- c. Test registers of other materials / fittings fixtures equipment as stipulated in the tender.
- d. Register of drawings and working details.
- e. Log book of defects.
- f. Hindrances register giving details of commencement and removal of each hindrance.
- g. Dismantled materials account register.
- h. Specifications of C.P.W.D. & I.S.I. as applicable to the contract.

These registers are required to be signed by the Official assigned by Bank/ Site Engineer.

49) SECURITY ARRANGEMENT

The following arrangement shall be ensured by the Contractor:

- i. Proper arrangements to keep all records under lock and key.
- ii. Watch and ward and security of materials; and
- iii. Movement of material and stores, shall be through Bank gate pass only.

When the work is completed to the satisfaction of the Employer and handed over to the Bank, the responsibility of proper security arrangement then shall rest with the Bank.

50) HANDING OVER BUILDING / PROJECT WORK TO THE EMPLOYER

All the handing and taking over report and inventories / statement shall be prepared in quadruplicate. Such reports and inventories shall be signed by:

- i. The Contractor (only the relevant papers).
- ii. Official assigned by Bank/ Site Engineer, and
- iii. Competent Authority in the Bank.

The following inventories / statements shall be prepared:

- i. Inventory of all equipments; and
- ii. Information folders & test reports for installations and as built drawings.

The Engineer on behalf of the Employer associated with this operation, shall be apprised of the importance to carry out periodic inspections (at two months interval) for defects not rectified or fresh ones that crop up and issuing notice for their rectification to the concerned Contractors and the final inspection just before the expiry of the defects liability period.

51) SAFETY CODES

i) SCAFFOLDING

a. Suitable scaffolds shall be provided for workmen for all works that cannot safely be done from the ground, or from solid construction except in the case of short duration work which can be done "safely from ladders" when a ladder is used, it shall be of rigid construction made either of good quality wood or steel. The steps shall have a minimum width of 450 mm and a maximum rise of 300 mm. Suitable hand hold of good quality wood or steel shall be provided and the ladder shall be given an inclination not steeper than 1/4 to 1 (1/4 horizontal and 1 vertical).

b. Scaffolding or staging more than 4M, above the ground floor, swung or suspended from an overhead support or erected with stationery support shall have a guard rail properly bolted, braced or otherwise secured, at least 1M, above the floor or platform of

such scaffolding or staging and extending along the entire length of the outside and ends thereof with only such openings as may be necessary for the delivery of materials. Such scaffolding or staging shall be so fastened as to prevent it from swaying from the building or structure.

c. Working platforms, gangways and stairway shall be so constructed that they do not sag unduly or unequally and if the height of the platform, gangway or stairway is more than 4m, above ground level or floor level, they shall be closely boarded and shall have adequate width and be suitably fenced as described in (ii) above.

d. Every opening in the floor of a building or in a working platform shall be provided with suitable means to prevent the fall of persons or materials by providing suitable fencing or railing whose minimum height shall be 1M.

e. Where ever there are open excavations in ground, they shall be fenced off by suitable railing and danger signals installed at night so as to prevent persons slipping into the excavations.

f. Safe means of access shall be provided to all working places. Every ladder shall be securely fixed. No portable single ladder shall be over 9M, in length while the width between side rails in rung ladder shall in no case, be less than 290 mm, for ladder up to and including 3M, in length for longer ladders this width shall be increased at least 20 mm for each additional meter of length.

g. A sketch of the ladders and scaffolds proposed to be used shall be prepared and approval of the Engineer obtained prior to construction.

ii) OTHER SAFETY MEASURES

a. All personnel of the Contractor working within the site shall be provided with safety helmets. All welders shall wear welding goggles while doing welding work and all metal workers shall be provided with safety gloves. Persons employed on metal cutting and grinding shall wear safety glasses.

b. Adequate precautions shall be taken to prevent danger from electrical equipment. No materials on any of the sites of work shall be so stacked or placed as to cause danger or inconvenience to any person or the public.

c. The Contractor shall at all times be liable to comply with the applicable labour laws relating to the safety of the workers engaged by it.

iii) DEMOLITION/DISMANTLING

Before any demolition/dismantling work is commenced and also during the process of the work:

a. No electric cable or apparatus which is liable to be a source of danger over a cable or apparatus used by the operator shall remain electrically charged.

b. All practical steps shall be taken to prevent danger to persons employed from the risk of fire or explosion or flooding. No floor, roof or other part of the building shall be so over-loaded with debris or materials as to render it unsafe.

iv) PERSONAL SAFETY EQUIPMENTS

All necessary personal safety equipment as considered adequate by the Engineer including but not limited to the following should be kept available by the Contractor for the use of person/ workers employed/engaged on the site and maintained in a condition suitable for immediate use, and the Contractor should take adequate steps to ensure proper use of equipment by those concerned.

- i. Those engaged in white washing and mixing or stacking or cement bags or any materials, which are injurious to the eyes, shall be provided with protective goggles.
- ii. Those engaged in welding works shall be provided with welder's protective eyesight lids.
- iii. Stonebreakers shall be provided with protective goggles and protective clothing and seated at sufficiently safe intervals.
- iv. The Contractor shall not employ men below the age of 18 years and women on the work of painting with products containing lead in any form. Wherever men above the age of 18 years are employed on the work of lead painting, the following precaution should be taken:
 - a) No paint containing lead or lead products shall be used except in the form of paste or ready-made paint.
 - b) Suitable face masks should be supplied for use by the workers when paint is applied in the form of spray or a surface having lead paint dry rubbed and scrapped.
 - c) Overalls shall be supplied by the Contractor to the workmen and adequate facilities shall be provided, to enable the working painters during the execution of work.

When the work is done near any public place where there is risk of drowning all necessary equipments should be provided and kept ready for use and all necessary steps taken for prompt rescue of any person in danger and adequate provision should be made for prompt first aid treatment of all injuries likely to be sustained during the course of the work.

52) RIGHTS OF TECHNICAL SCRUTINY BY CHIEF TECHNICAL EXAMINER

The work is liable to be technically audited by the Chief Technical Examiner of the Central Vigilance Commission, Government of India from time to time. Any defects, improvements or testing etc. pointed out by the Chief Technical Examiner should be carried out by the Contractor at his own cost and any deduction suggested by the CTE will be affected.

The Employer shall have a right to cause a technical examination and audit of works and the final bills of the Contractor including all supporting vouchers, abstract etc. to be made at the time of payment of the final bill. If as a result of this examination or otherwise any sum is found to have been over paid in respect of any work done by the Contractor under the contract the Contractor shall be liable to return the amount of over payment and it shall be lawful for the Employer to recover the same from him from any sum or sums due to him and in any other manner legally permissible and if it is found that the Contractor was paid less than what was due to him under the contract in respect of any work executed by him under it, the amount of such under payment shall be duly paid by the Employer.

Any sum of money due and payable to the Contractor (including Security Deposit returnable to him) under this contract may be appropriated by the Employer and set off against any claim of the Employer of the payment of a sum of money arising out of or under any other contract made by the Contractor with Employer.

53) IDLE LABOUR

Whatever the reasons may be, no claim for idle labour, additional establishment cost of hire and labour charges of tools and plants would be entertained under any circumstances by the Employer and the decision of the Employer shall be binding on the Contractor.

54) FORCE MAJEURE

Any failure or delay by bidder or Bank in performance of its obligations, to the extent due to any failure or delay caused by fire, flood, earthquake or similar elements of nature, or acts of God, war, terrorism, riots, civil disorders, rebellions or revolutions, acts of governmental authorities or other events beyond the reasonable control of non-performing Party, is not a default or a ground for termination.

Such events may include, but are not restricted to, war or revolution and epidemics. If a force majeure situation arises, the Contractor shall notify within ---days the Bank in writing of such condition and the cause thereof. Unless otherwise directed by the Bank in writing, the Contractor shall continue to perform its obligation under the contract to the extent possible mitigate the consequences of the force majeure event and make all necessary alternative arrangements to perform their obligations and accordingly, and shall seek all alternative means of performance not prevented by the force majeure event.

Provided further that in case of delay of Services, which shall be solely decided by the Bank, the Bank shall not be held liable for non-performance of its obligations under the Agreement and the Bank shall have the right to terminate this Agreement without giving any further notice to the Vendor. Further, Bank also reserves the right to assign the work to other Vendor without any consequences and claims at the risk and cost/ responsibility of the contractor.

55) SUSPENSIONS

If the Contractor, except on account of any legal restraint upon the Employer preventing the continuance of the work, abandons, suspends work or in the opinion of the Employer, the Contractor neglects or fails to proceed with due diligence in the performance of his part of the contract, the Employer shall have the power to give notice in writing to the Contractor requiring the work be proceeded within a reasonable manner and with reasonable dispatch, such notices purport to be a notice under this clause.

After such a notice is served upon the Contractor, , the Contractor shall not be at liberty to remove from the site of the works or from any ground contiguous thereto any plant or materials , and such an obligation shall subsist from the date of such a notice being served until the notice be complied with by the Contractor. If the Contractor fails s to comply with such a notice for a period of 7 (seven) days to proceed with the works as therein prescribed, the Employer may proceed as provided in clause 59 (Termination of contract by Employer).

56) DELINQUENCIES OF CONTRACTORS

The under noted delinquencies/ defaults/ misconduct/ misdemeanors on the part of bidder or enlisted contract will attract disciplinary action in accordance with the clause 58 mentioned herein below:

- i. Incorrect information about credentials, about his performance, equipment, resources, technical staff etc.
- ii. Non-submission of the fresh/ latest Income Tax Clearance certificate.
- iii. Irregular tendering practice.
- iv. Submission of tender containing for too many arithmetical errors and freak rates.
- v. Revocation of a tender without any valid reasons.
- vi. Tardiness in commencing work.
- vii. Poor organization at site & lack of his personal supervision.
- viii. Ignoring Employer's Notices for replacement/ rectification of rejected materials, workmanship etc.
- ix. Violation of any of the important conditions of contract, i.e. site facilities, insurance, labour laws, ban on subletting etc.
- x. Lack of promptitude and co-operation in measurement of work and settlement of final account.
- xi. Non-submission of vouchers and proofs of purchase etc.
- xii. Tendency towards putting up - false and untenable claims.
- xiii. Tendency towards suspension of work for frivolous reasons.
- xiv. Bad treatment of labour.

- xv. Bad treatment of Sub-Contractors (piece workers) and un-business like dealing with suppliers of materials.
- xvi. Lack of co-operation with nominated Contractors or Employer's Labour.
- xvii. Contractor becoming Bankrupt or insolvent.
- xviii. Contractor's conviction by any court of law.
- xix. Failure to satisfactorily rectify defects during Defects Liability period (DLP) and discovery of latent defects in Contractors work after the expiry of DLP of his contract.

57) DISCIPLINARY ACTION AGAINST (DELINQUENCIES OF) CONTRACTOR.

The award of the under noted disciplinary action shall be considered:

- i. Placing of an embargo on the issue of tenders or temporary suspension from the Employer's approved list.
- ii. Permanent ban on issue of tenders & removal from the Employer's approved list.
- iii. Circulation of the Contractor name to other public Undertaking or Government Department or concerned regulatory authorities of Contractor, if any, for non-entertainment of this publication for contract work.

58) TERMINATION OF CONTRACT BY EMPLOYER

In the following circumstances/ events, the contract shall be terminated by the Employer:-

- i. If the Contractor being a company goes into liquidation whether voluntary or compulsory; or
- ii. Being a firm, stand dissolved; or
- iii. If the official assignee in insolvency or receiver of the contractor in insolvency, repudiates the contract; or.
- iv. If receiver of the contractor's firm appointed by the court shall be unable to, within 14 days after notice to him requiring him to do so, to show to the reasonable satisfaction of the employer that he is able to carrying out and fulfill the contract and if so required by the employer to give reasonable security therefore.
- v. If the contractor:
 - a) Suffers execution to be issued;
 - b) Suffers any payment under this contract to be attached by or on behalf of and of the creditors of the Contractor;
 - c) Assigns, charges or encumbers this contract or any payment due or which become due to the contractor hereunder
 - d) Neglects or fails to observe and perform all or any of the acts, matters of things by this contract, to be observed and performed by the Contractor within three clear days after the notice shall have been given to the Contractor in manner hereinafter mentioned requiring the Contractor to observe or perform the same
 - e) Uses improper materials or workmanship in carrying on the works
 - f) In the opinion of the Employer does not exercise such due diligence and make such due progress as would enable the work to be completed within due time agreed upon, and fails to proceed to the satisfaction of the Employer after three clear days' notice requiring the Contractor so to do shall have been given to the Contractor as hereinafter mentioned,
 - g) Breaches any of the conditions of the contract in any of the abovesaid cases or otherwise;
 - h) Any threat is perceived or observed on the security of Bank's data / property out of any action by the staff deployed for monitoring / configuration etc., by service provider.

The Bank may notwithstanding previous waiver determine the contract by a notice in writing to the effect as hereinafter mentioned, but without thereby effecting the powers of the Employer & the obligations & liabilities of the contractor the whole of which shall continue in force as fully as if the contract, had not been so determined and as if the works

subsequently executed had been executed by or on behalf of the contract (without thereby creating any trust in favour of the contractor).

Further the Employer or his agent, or servant:

- i. may enter upon and take possession of the work and all plants, tools, scaffoldings, sheds, machinery, steam and other power utensils and materials lying upon premises or the adjoining lands or roads and sell the same as his own property;
- ii. may employ the same by means of his own servants and workmen in carrying on and completing the works;
- iii. by employing any other Contractors or other persons or person to complete the works and the Contractor shall not in any way interrupt or do any act, matter of thing to prevent or hinder such other Contractors or other persons or persons employed for completing and finishing or using the materials and plants for the works.

When the works stands completed, or as soon thereafter as conveniently may be, the Employer shall give notice in writing to the Contractor to remove his surplus materials and plants, and should the Contractor fail to do so within a period of fourteen (14) days after receipt of the notice by him, the Employer may sell the same by public auction and shall give credit to the Contractor for the amount so released.

Any expenses or losses incurred by the Employer in getting the works carried out by other Contractors shall be adjusted against the amount payable to the Contractor by way of selling his tools and plants, or due on account of work carried out by the Contractor prior to engaging other Contractors or against the Security Deposit.

59) DISPUTES AND ARBITRATION:

All disputes or differences, whatsoever, arising between the parties out of or in relation to the terms and conditions, meaning and operation or effect of this Agreement or breach thereof shall be settled amicably.

In case they are not able to settle the disputes or differences between them amicably, the matter may be referred to a sole arbitrator mutually agreed upon after issue of at least thirty (30) days' notice in writing to the other party clearly setting out there in the specific disputes and the same shall be settled by arbitration in accordance with the Indian Laws relating to arbitration, i.e. in accordance with the provision of the Indian Arbitration and Conciliation Act, 1996 and Rules and Regulations framed thereunder including all amendments up to date and the award made in pursuance thereof shall be binding on the parties. The matter may be referred to a sole arbitrator nominated by the Bank, who shall give a reasoned award and the award made in pursuance thereof shall be binding on the parties.

The venue of arbitration shall be Guwahati.

All arbitration proceeding shall be conducted in English and a daily English record of such proceeding shall be maintained.

Any appeal against the arbitration award will be subject to the jurisdiction of courts at Guwahati only.

The Contractor shall continue to work under the work Contract during the arbitration proceedings unless otherwise directed in writing by the bank, unless the matter is such that the works/services cannot possibly be continued until the decision of the arbitrator or of the presiding arbitrator, as the case may be, is obtained.

However during such a contingency, the Bank shall be entitled to make alternative arrangements to tackle the situation in any manner it deems fit, at the cost of the Vendor which may also be adjusted by the Bank from the Performance Bank Guarantee, being treated as default so that the business of the Bank is not disrupted.

60) EXCEPTED MATTERS FROM ARBITRATION

If the dispute or difference pertains to the under noted matters (called excepted matters) the decision in writing of the Employer shall be final, conclusive and binding on the parties.

- a. Instructions given by the Employer;
- b. Transactions with local authorities.
- c. Proof of quality of materials.
- d. Assigning or under letting of the contract.
- e. Certificate as to the causes of delay on the part of the Contractor and justifying extension of time.
- f. Rectifying of defects pointed out during the defects liability period.
- g. Notice to the Contractor to the effect that he is not proceeding with due diligence.
- h. Certificate that the Contractor has abandoned the contract.
- i. Notice of the determination of the contract by the Employer.

61) OTHER TERMS & CONDITIONS:

Bank shall not entertain any claim arising on account of damages, compensation or expenses payable as a result of any accident or injury sustained by any workman/staff of the bidder or any claim under the Workman's Compensation Act. The bidder may obtain necessary insurance cover to meet any of the above contingencies.

The Contractor and his staff shall abide by the regulations/requirements of Security Department and strictly follow the rules. Bank's security staff will have the right to check, search or interrogate any of the Contractor's staff while entering/ remain present/ leaving the Bank premises for security purposes.

The bidder shall be responsible for any loss/damage to the materials and other assets of the Bank by his staff deployed for duty.

The bidder shall also be wholly responsible for theft, burglary, fire or any other mischievous act and conduct done by their staff.

NOTICES

Notices as required by the agreement that shall be entered with the successful bidder shall be sent to the addresses as would be mentioned first therein or such other addresses as the Parties may designate from time to time, and shall be sent by certified or registered mail with acknowledgement due on receipt.

62) CLAUSES REGARDING BIDDERS FROM COUNTRIES SHARING LAND BORDER WITH INDIA

- i. Any bidder from a country which shares a land border with India will be eligible to bid in any procurement whether of goods, services (including consultancy services and non-consultancy services) or works (including turnkey projects) only if the bidder is registered with the Competent Authority. Further, any bidder (including bidder from India) having specified Transfer of Technology (TOT) arrangement with an entity from a country which shares a land border with India, shall also require to be registered with the same competent authority.

ii. "Bidder" (including the term 'bidder', 'consultant' or 'service provider' in certain contexts) means any person or firm or company, including any member of a consortium or joint venture (that is an association of several persons, or firms or companies), every artificial juridical person not falling in any of the descriptions of bidders stated hereinbefore, including any agency branch or office controlled by such person, participating in a procurement process.

iii. "Bidder (or entity) from a country which shares a land border with India" for the purpose of this Order means: -

- a) An entity incorporated, established or registered in such a country; or
- b) A subsidiary of an entity incorporated, established or registered in such a country; or
- c) An entity substantially controlled through entities incorporated, established or registered in such a country; or
- d) An entity whose beneficial owner is situated in such a country; or
- e) An Indian (or other) agent of such an entity; or
- f) A natural person who is a citizen of such a country; or
- g) A consortium or joint venture where any member of the consortium or joint venture falls under any of the above

iv. The beneficial owner for the purpose of (iii) above will be as under:

- a) In case of a company or Limited Liability Partnership, the beneficial owner is the natural person(s), who, whether acting alone or together, or through one or more juridical person, has a controlling ownership interest or who exercises control through other means.

Explanation: -

i. "Controlling ownership interest" means ownership of or entitlement to more than twenty-five per cent. of shares or capital or profits of the company;

ii. "Control" shall include the right to appoint majority of the directors or to control the management or policy decisions including by virtue of their shareholding or management rights or shareholders agreements or voting agreements;

- b) In case of a partnership firm, the beneficial owner is the natural person(s) who, whether acting alone or together, or through one or more juridical person, has ownership or entitlement to more than fifteen percent of capital or profits of the partnership;

- c) In case of an unincorporated association or body of individuals, the beneficial owner is the natural person(s), who, whether acting alone or together, or through one or more juridical person, has ownership of or entitlement to more than fifteen percent of the property or capital or profits of such association or body of individuals;

- d) Where no natural person is identified under (a) or (b) or (c) above, the beneficial owner is the relevant natural person who holds the position of senior managing official;

- e) In case of a trust, the identification of beneficial owner(s) shall include identification of the author of the trust, the trustee, the beneficiaries with fifteen percent or more interest in the trust and any other natural person exercising ultimate effective control over the trust through a chain of control or ownership.

- v. An Agent is a person employed to do any act for another, or to represent another in dealings with third person.

- vi. The successful bidder shall not be allowed to sub-contract works to any contractor from a country which shares a land border with India unless such contractor is registered with the Competent Authority.
- vii. The registration shall be valid at the time of submission of bid and at the time of acceptance of bid.
- viii. If the bidder was validly registered at the time of acceptance / placement of order, registration shall not be a relevant consideration during contract execution.

SPECIAL CONDITIONS OF CONTRACT

- 1) The bidder shall acquaint himself with the proposed site of work before quoting his rates. The contractor should note and bear in mind that the Bank shall bear no responsibility for the lack of acquaintance of site and other conditions or any information relating thereto or on their part.
- 2) If for any reasons, any part of the site is not available temporarily for some time for part of the work under the contract, the agreed construction schedule shall be suitably modified and contractor shall diligently divert his men and materials to utilize them appropriately, profitably and no claim of damages whatsoever shall be entertained on this account. However, the contractor shall be allowed extension of time for completing the work as deemed fit by the competent authority. The contractor shall also not be entitled to any compensation for any loss suffered by him and revision in the rates quoted by him.
 - a. On account of delay in commencing the work by the contractor.
 - b. On account of reduction in the scope of work.
 - c. On account of suspension of work or abandoned after award of work.
- 3) The contractor shall provide, at his own cost instruments for weighing and measuring purpose at the site of work as may be necessary for execution of the work.
- 4) The contractor shall construct a sample unit of different activities complete in all respect as per the directions of the Engineer-in-charge. This sample unit shall be got approved from the Engineer-in-charge before commencing the mass work.
- 5) The contractor shall take care of all safety precautions pertaining to construction of work, such as scaffolding, ladder, working platforms, gangways, electric arc/ gas welding, use of hoist and construction machinery. Nothing extra shall be paid for scaffolding for any of the items of work unless specifically mentioned in the nomenclature. Contractor should quote rates accordingly.
- 6) On account of security consideration, some restrictions may be imposed by the security staff on the working and/ movement of men and materials etc. The contractor shall be bound to follow all such restrictions/ instructions and he shall organize his work accordingly. No claim on this account, whatsoever, shall be payable.
- 7) No hindrance / inconvenience shall be caused in the operation / working / movement of Bank personnel / customers / visitors and their vehicles due to the execution of the project / storage or placement of materials / debris / construction waste / excavated materials by the contractor. Contractor shall at all times ensure safe and convenient access to building entry for Bank staff working in the building & take all precautions to ensure that Bank's official work going on in the building is not hampered. The contractor shall take all precautions to avoid accidents by exhibiting necessary caution boards day and night, speed limit boards, red flags, red lights and providing barriers. No hindrance shall be caused to traffic during the execution of the work.
- 8) The contractor shall be responsible for the watch and ward of all materials brought by the contractor to site against pilferage and breakage during the period of installation and thereafter till the works are physically handed over to the Bank.
- 9) The contractor shall take all preventive measures against any such damage caused by rain, snowfall, floods or any other natural calamity, whatsoever during the execution of

the work. The contractor shall be fully responsible for any damage to the owner's property and to the work for which the payment has been advanced to him under the contract.

10) The work will be carried out in the manner complying, in all respects, with the requirements of relevant bye-laws of the local body under the jurisdiction of which the work is to be executed or as directed by the Engineer-in-Charge and nothing extra shall be paid on this account.

11) The contractor shall comply with proper and legal orders and directions of the local or public authority or municipality and abide by their rules and regulations and pay all fees and charges which may be liable.

12) The contractor shall give due notices to Municipal, Police and/or other authorities that may be required under the law/rules under force in the area and obtain all requisite licenses for temporary obstructions / enclosures and pay all charges which may be leviable on account of his execution of work under the agreement. Nothing extra shall be payable on this account in any case whatsoever.

13) All materials to be incorporated in the work shall be arranged by the contractor and shall be in accordance with the specifications laid down. Samples of all items are to be fabricated by the Contractor prior to taking up the mass production. The Contractor shall take prior written approval of the Bank before proceeding for mass production.

14) The Contractor shall use materials bearing ISI/BIS Certification Mark unless otherwise specified or allowed in writing by the Engineer-in-Charge. Any material banned by the Bank shall not be used in the work.

15) The contractor shall submit to the Engineer-in-charge samples of all materials for approval. Such samples of materials which affect aesthetics of the work shall also be got approved from the Engineer-in-charge of the project before procuring bulk supplies. These approved samples shall be preserved and retained in the custody of the Engineer-in-charge as standards of materials till the completion of the work. The cost of such samples shall be borne by the Contractor and nothing shall be payable on this account over the Agreement rates.

16) The contractor shall be required to get all the necessary mandatory and other tests as per the specifications/ IS codes, carried out on materials/ work from an approved laboratory as per the direction of the Engineer-in-charge. The testing charges and conveyance from the site shall be borne by the contractor.

17) In case any material / work is found sub-standard the same shall be rejected by the Engineer-in-charge and the same shall be removed from the site of work within 48 hours, failing which the same shall be got removed by the Engineer-in charge at the risk and cost of the contractor without giving any further notice and time. In order to ensure quality of work during its execution, the Engineer-in-charge may require samples for mandatory or routine testing of materials. All costs of these samples, their packaging, conveyance from the site to the testing laboratory and return, shall be borne by the contractor.

18) Even ISI marked materials may be subjected to quality test at the discretion of the Engineer in-charge. Whenever ISI marked materials are brought to the site of work the contractor shall, if required by the Engineer-in-charge, furnish manufacturer's test certificate or test certificate from approved testing laboratory to establish that the materials procured

by the contractor, satisfy the provisions of relevant ISI codes. The testing charges shall be borne by the contractor.

19) The material required for testing shall be supplied free of charge by the contractor. The cost of tests shall be borne by the contractor.

20) The work shall be executed and measured in metric system. The metric dimensions given in the schedule of quantities and drawing etc. shall be followed. (The dimension in FPS units wherever indicated are for guidance only) The figures in the drawings shall be followed.

21) The contractor shall be responsible for completing the work and for satisfying all terms and conditions of the Contract without any extra payment over his quoted rates unless otherwise specified. The contractor shall quote his rate for various items of work accordingly and no claim whatsoever shall be entertained for any incidental or extra work involved in the execution of the work as per nomenclature of the item and the specifications indicated in the tender documents.

22) Subject to the nomenclature of the item as per schedule of quantities, the specification indicated in the tender documents, the rates quoted shall include cost of all materials including royalty and taxes if any, labour, sundry inputs, execution of work at all heights, levels, pattern and design for all leads, lifts and depths including overhead charges and contractor's profit. Nothing extra shall be paid on this account.

23) The rate shall be inclusive of making design, pattern and execution of work as per Architectural drawings, at all levels and heights.

24) Other agencies doing works related with this project will also simultaneously execute the works and the contractor shall afford necessary co-ordination for un-hindered completion of these sub-works.

25) The contractor shall give a satisfactory performance test of installations individually and as a whole to ensure their proper functioning before the work is finally declared and completed and accepted.

26) The contractor shall continue to maintain watch and ward to safeguard the Owner's property in his possession until the same is formally handed over as per directions of the Engineer-in-charge. Nothing extra over agreement rates shall be paid on this account.

27) All tools, plants and measuring or weighing equipment shall be arranged by the contractor himself and nothing extra shall be paid to the contractor on this account.

28) The quantities of various items incorporated in the tender are approximate. However, the payments shall be made to the contractors on the basis of actual measurements taken at site.

29) The contractor shall protect the adjoining buildings or works and the work under execution from fire and shall make adequate arrangements for fire protection and firefighting and if any property is damaged, by fire due to the negligence of the contractor, the same shall be made good by the contractor at his own cost, to the entire satisfaction of Engineer-in charge.

- 30) The contractor shall provide adequate lighting arrangements as approved by the Engineer in-charge for carrying out the work during night time, if so required and also provide all other facilities for the labour employed to carry out the work as per direction of Engineer in-Charge.
- 31) In order to achieve the targeted date of completion the contractor may have to work in multiple shifts, round the clock including public and gazetted holidays and nothing extra shall be paid on this account.
- 32) All materials, articles and workmanship shall be of respective best quality and kind for the class described in the schedule of quantities and specifications. All materials, so used in different items of work shall be subject to the approval of the Engineer-in-charge.
- 33) The TDS or any other statutory levels/taxes incorporated from time to time shall be deducted progressively from the running account bills, as applicable at the time of payment. No claim in this regard shall be entertained.
- 34) No extension of time shall be granted to the contractor on account of rains or inclement weather conditions.
- 35) For any clarification/ doubt, the Bank may organize regular meetings with Contractor. The contractor shall attend such meetings invariably as and when required.
- 36) In respect of the work of other agencies, where the commencement or progress of such work of any other agency is dependent upon the completion of particular portions of the contractor's work or generally upon the contractor maintaining progress in accordance with the approved coordinated construction program, it shall be the responsibility of the Contractor to complete such portions and maintain such progress.
- 37) The contractor shall have to do all drilling of holes and cutting of walls, chases or other elements of the building for the complete and proper installation of the pipe lines/ ducts and other equipments by using electrically operated tools such as drills/ chases cutting machine etc. Manual drilling or chiseling or cutting shall be permitted on special request only. Prior permission for the same is to be obtained from the Bank.
- 38) No chiseling or cutting or drilling of RCC columns, beams, girders and other principal structural members shall be done unless prior permission has been granted by the Engineer in charge in writing.
- 39) All chases and openings made by the contractor for his pipe lines shall be filled/ covered over with cement plaster in reasonable manner. Before rough plastering on the pipe surfaces the concealed pipes shall be secured to the wall by using proper supports/ clamps.
- 40) The contractor will neither be allowed to construct labour hutments nor his workforce be allowed to stay.
- 41) All spaces allotted to the contractor as described above shall be vacated and all structures removed from site at any time as and when required and directed by the Engineer-in charge, unconditionally and without any reservation. The Engineer-in-charge will not be obliged to give any reason for such removal. Upon receiving instructions to vacate the space, the contractor shall immediately remove all his structures, materials, etc. from the sources and clear and clean-up the site to the satisfaction of the Engineer-in-charge.

- 42) It shall be the responsibility of the Contractor to safeguard the site and ensure that no illegal encroachments are made by outside elements within the area allotted to the contractor. Upon completion of the work or earlier as required by Engineer-in-Charge, the contractor shall vacate the land totally without any reservation.
- 43) The security of workmen, materials, equipment stores etc. within the area allotted to the contractor shall be the responsibility of the contractor.
- 44) The site of work shall have required equipments for various tests at site by the contractor at his own cost and nothing extra shall be payable on this account.
- 45) The contractor shall arrange the required minimum plant and equipments at site for the execution of work. These may have to be increased depending on the requirement of the site.
- 46) The quantities indicated are for guidance only. However, it may vary to any extent and the contractor should not have any financial or other implications for such variations. The Bank reserves to reduce the scope of work of any item if the contractor fails to deliver the works in time and the contractor shall not ask for any financial consideration for such deletion of scope of the work.
- 47) The contractor shall take photographs of site prior to commencement of work, during construction and after completion of work as suggested and shall submit the photographs in soft and hard copies to Bank for which no extra payment will be made.
- 48) Layout of works shall be got checked by Engineer-in -charge & only then further work shall be taken by after approval.
- 49) All electrical works shall be got carried out through licensed Electrical Contractor having experience of similar work. Successful bidder to submit the details of licensed Electrical Contractor before start of Internal Electrification Work. The work shall be executed as per specifications and strictly in keeping with relevant IS code and rules and regulations of authorities.
- 50) The work should be carried out as per latest CPWD specification and as per the standard engineering practice. All measurements shall be made as per CPWD norms.
- 51) Site should be cleaned every day and all the unusable material/malba shall be removed from the site and unusable materials shall be stacked properly so that there is no hindrance for staff and public failing which bank will remove the same at their level and suitable amount shall be recovered from the contractor's bill.
- 52) The contractor shall be required to maintain the coordination with the Building Maintenance Contractor, if required.
- 53) No old / dismantled material shall be used by the contractor in the work under any circumstances unless otherwise specified or under instructions of the bank.
- 54) The bidder shall visit the site and examine the rebate items and site conditions before quoting the rates.
- 55) Dismantling & taking away includes the disposal of unserviceable material / malba to approved municipal yard.

- 56) The Rebate items shall be the property of the contractor. Rates of rebate item shall be considered as negative by the system while calculating the value of tender.
- 57) The Contractor shall comply with the provisions of Contract, Labour (Regulation & Abolition) Act, 1970, Minimum Wages Act and all other Labour Laws and other Statutory Regulations (both Central and State) that may be enforced from time to time by the appropriate authorities. Bank shall not be held responsible for any penalty on failure of the any Labour Regulations. Bank shall have the power to inspect the Wage Register and for physical verification of salary paid to the staff with reference to any records of the Contractor and to insist the Contractor to comply with Laws.
- 58) Contractor should obtain necessary permission that may be required for the purpose of this Contract from such authorities as may be prescribed by Law from time to time.
- 59) Contractor or his authorized representative should visit the site frequently as required by the Bank and meet Bank's Engineer with prior appointment for any clarifications and to receive instructions, take measurements, etc. at the site.
- 60) The Contractor should arrange to issue photo identity card to his workers.
- 61) Any act of indiscipline / misconduct / theft / pilferage on the part of any employee engaged by the Contractor resulting in any loss to Bank in kind or cash will be viewed seriously and Bank will have the right to claim damages or levy fine and / or terminate the Contract forthwith, if necessary.
- 62) In case of any default or failure on Contractor's part to comply with all / any one of the Terms/ Conditions, Bank reserves to itself the right to take necessary steps to remedy the situation including, inter-alia, the deduction of appropriate amount(s) from dues otherwise payable to Contractor and / or by taking recourse to appropriate recovery proceedings.
- 63) Keeping the area clean and removal of debris: Contractor shall arrange to dispose off debris, any other waste product created while carrying out the work, outside Bank's premises. The Contractor shall take due care while disposing of such waste materials and ensure that any rules / regulations laid down by Municipal Corporation or any other statutory body are not violated. The Contractor shall be responsible and answerable to any complaint arising out of improper disposal of waste material. Quoted rates shall involve the cost of same and no extra payment shall be made towards this account.
- 64) It is mandatory to provide purchase voucher of the material where basic rates are given in Bill of Quantities (BOQ). However, Bank may instruct the contractor to submit purchase voucher/test certificate of any material.
- 65) BOQ nomenclature shall prevail over any drawing/detail.
- 66) The specification for the entire work shall be in accordance with latest CPWD specifications and latest IS codes. Whenever these codes are silent, the same shall be governed by sound engineering practice and the decision of the Bank in matter of interpretation shall be final and binding on the contractor.
- 67) Electricity & Water shall not be provided by Bank to Contractor. Necessary arrangement/ sourcing/ extension, if required, shall be done by the contractor at his own cost with the approval of Bank. No extra payment will be made to the contractor for the same.

Contractor shall have to arrange for D. G. set / temporary power supply at his/ her own cost, risk and responsibility to carry out the works at site whenever required for and asked by the Bank. The contractor shall at his own cost arrange for necessary power/ lighting for the work and water consumption for the entire period of contract. However, Bank may provide electricity & water from their existing source at site for which Bank will recover 0.5% of the contract sum from the contractor for electricity & water from their running bills / final bill. But in no way Bank will be held responsible for continuous supply of electricity.

68) Contractor shall associate a specialized agency for specialized works such as water proofing work, anti-termite treatment work, etc. having suitable experience in the field and same shall be got approved from the Bank prior to execution of the specialized work within 3 days' time with credentials of the agency. Contractor should get approval from Bank before commencement of the specialized work. Contractor to give 10 (ten) year performance guarantee on a non-judicial stamp paper of Rs. 100 as per Performa attached (Guarantee Bond for specialized works) at Annexure 'X' & 'XI'. 10% of specialized works amount shall be withheld during the period of this performance guarantee.

LETTER SUBMITTING TENDER

(To Be Submitted with Bid on Bidder's Letter head)

**Dy. General Manager,
GSAD, Punjab National Bank, Circle Office Guwahati
Nilgiri Mansion, Bhangagarh, Guwahati, Assam, 781005**

Dear Sir,

Reg: Tender for Carpentry, Electrical LAN Cabling, Air Conditioning and & other miscellaneous allied works for Staff training Centre of Punjab National Bank at 3RD floor of Rava Tower, Lutuma, Barshapara, A K Azad Road Guwahati, Assam, Pin-781008

- 1) Having visited the site and examined the drawings, conditions of contract, special conditions of contract, general specifications and detailed specifications, schedules and bill of quantities for the execution of the above named works, we offer to complete and maintain the whole of the said works in conformity with the said drawings, conditions of contract, specifications, schedules and bill of quantities for the sum stated in bill of quantities of this Tender Document No.or such other sum as may be ascertained in accordance with the said conditions of contract.
- 2) We undertake to complete and deliver the whole of the works comprised in the contract within the stipulated time stated in the tender.
- 3) We have independently considered the amount of liquidated damages shown in the Appendix to form of tender hereto and agree that it represents a fair estimate of the loss likely to be suffered, by you in the event of the works not being completed in time.
- 4) We agree to abide by this tender for the period of 90 days from opening of Commercial Bid or extension thereof as required by the Bank from the date fixed for receiving the same and it shall remain binding upon us and may be accepted at any time before the expiry of that period.
- 5) We confirm that the period and rates as referred in the agreement or general conditions of contract are given or summarized in the tender, to which we give our consent and agree to abide by the same.
- 6) We understand that if our tender is accepted, we are to be jointly and severally responsible for the due performance of the contract.
- 7) We understand that you are not bound to accept the lowest or any tender you may receive and may reject all or any tender, accept or entrust the entire work to the Contractor without assigning any reason or giving any explanation whatsoever.
- 8) I/we have deposited Earnest Money Deposit of ₹ 1,95,676/- (Rupees One Lakh Ninety-Five Thousand Six Hundred Seventy-Six Only) which amount is not to bear any interest. I/we do hereby agree that this sum shall be forfeited by you in the event our tender is accepted and I/we fail to execute the contract when called upon to do so.

Dated this day of _____ 202__.

Name of Authorised Signatory_____

Sign and Signature of Authorised Signatory _____

In the capacity of / Designation _____

Duly authorized to sign bids for and on behalf of _____ (IN CAPITALS)

LETTER OF TRANSMITTAL

(To Be Submitted With Bid on Bidder's Letter head)

**Dy. General Manager,
GSAD, Punjab National Bank, Circle Office Guwahati
Nilgiri Mansion, Bhangagarh, Guwahati, Assam, 781005**

Dear Sir,

Reg: Carpentry, Electrical, Lan Cabling, Air Conditioning & other miscellaneous allied works at 3rd Floor of Rava Tower, Lutuma, A K Azad Road, Guwahati, Assam.

Having examined the details given in Press advertisement and tender document No..... for the above work, I/we hereby submit the relevant information.

1. I/We here by certify that all the statement made and information supplied in the enclosed forms A to D and accompanying statement are true and correct.
2. I/We have furnished all information and details necessary for eligibility and have no further pertinent information to supply.
3. I/We submit the following certificates in support of our suitability, technical knowledge and capability for having successfully completed the following eligible similar works:-

S No	Name of the Work	Value of Work	Date of Completion	Certificate issued by

“Certify that the information given in the enclosed tender documents is correct. It is also certified that I/we shall be liable to be debarred, disqualified / cancellation of bid in case any information furnished by me/us found to be incorrect.”

Enclosures:

Date of submission:

Name of Authorised Signatory_____

Sign and Signature of Authorised Signatory _____

In the capacity of / Designation _____

Duly authorized to sign bids for and on behalf of _____ (IN CAPITALS)

Annexure-I:
BIDDER'S INFORMATION

(To Be Submitted With Bid on Bidder's Letter head)

1. Name:
2. Constitution:
3. Address:
4. Names & Addresses of the Proprietor/Partners/Directors, as applicable:
5. Name of Contact Person(s) with their Mobile Numbers:
6. Office Telephone, Fax, e-mail:
7. PAN No.:
8. GST No.:
9. Manpower Employed:
10. Payment Details (A/c Number and IFS Code):
11. Details of Authorised Signatory:

Note: The document authorising the signatory to submit the bid to be provided with the bid.

Name of Authorised Signatory_____

Sign and Signature of Authorised Signatory _____

In the capacity of / Designation _____

Duly authorized to sign bids for and on behalf of_____ (IN CAPITALS)

Annexure-II: Undertaking for Local Content from Bidder

(To be submitted With Bid on bidder's letter head)

**(Designation, Name of Office along with
Complete address to be inserted here)**

Reg: Carpentry, Electrical, Lan Cabling, Air Conditioning & other miscellaneous allied works at 3rd Floor of Rava Tower, Lutuma, A K Azad Road, Guwahati, Assam.

We hereby certify that the local content percentage (%) in the Goods, Works and Services offered across India by M/s _____ having registered office in India at _____ against Tender No: _____ floated by Punjab National Bank for **"Carpentry, Electrical, Lan Cabling, Air Conditioning & other miscellaneous allied works at 3rd Floor of Rava Tower, Lutuma, A K Azad Road, Guwahati, Assam** is in line with definition of minimum local content as prescribed for Class-I local supplier as per DPIIT vide OM P-45021/2/2017-PP (BE-II) dated 16.09.2020 issued the Public Procurement (Preference to Make in India) Order 2017-revision.

M/s _____ is Class-I local supplier and local content percentage is _____ %.

Name of Authorised Signatory _____

Sign and Signature of Authorised Signatory _____

In the capacity of / Designation _____

Duly authorized to sign bids for and on behalf of _____ (IN CAPITALS)

Annexure-III: Undertaking for Non-Blacklisting/ Debarring and Back to Back Works

(To be submitted on stamp paper of Rs. 100/-)

**(Designation, Name of Office along with
Complete address to be inserted here)**

Reg: Carpentry, Electrical, Lan Cabling, Air Conditioning & other miscellaneous allied works at 3rd Floor of Rava Tower, Lutuma, A K Azad Road, Guwahati, Assam.

I/We am/are Participating in the E tender for “Carpentry, Electrical, Lan Cabling, Air Conditioning & other miscellaneous allied works at 3rd Floor of Rava Tower, Lutuma, A K Azad Road, Guwahati, Assam.

I/We hereby Undertake as under :-

"Eligible similar work(s) has/ have not been executed through another agency on back to back basis.

I/ We have not been black-listed/ debarred by any office of Bank/ DFS or regulators like RBI, SEBI, IRDA etc/ Department of Expenditure, Ministry of Finance Government Agency.

Further that, if such a violation comes to the notice of the Bank, then I/we shall be debarred for bidding in Bank in future forever. Also, if such violation comes to the notice of the Bank before date of start of work, the Bank shall be at liberty to forfeit the entire amount of Earnest Money Deposit."

Dated this day of _____ 202__

Name of Authorised Signatory_____

Sign and Signature of Authorised Signatory _____

In the capacity of / Designation _____

Duly authorized to sign bids for and on behalf of _____ (IN CAPITALS)

Annexure-IV: BIDDERS' FINANCIAL INFORMATION

(To Be Submitted With Bid on Bidder's Letterhead)

Name:
Constitution:
Address:

Names & Addresses of the Proprietor / Partners / Directors if applicable:

Contact Person(s) _____

Telephone, Fax, e-mail _____

Number of years of experience _____

Please give brief financial particulars of your firm for the last three accounting years along with the volume of business handled.

(The information will be kept confidential)

Year (Last 3nos. of FY)	20....-....	20....-....	20....-....
Total Turnover (Value in in ₹)			
ITR (Y/ N)			

Name of Authorised Signatory_____

Sign and Signature of Authorised Signatory _____

In the capacity of / Designation _____

Duly authorized to sign bids for and on behalf of _____ (IN CAPITALS)

Annexure-V: REFERENCE LIST

(To Be Submitted with Bid on Bidder's Letterhead)

PROFORMA FOR PERFORMANCE STATEMENT

NAME OF BID

Sr. No	Name of Organization	Duration of Contract	Contract Amount	Date of Order	Contact Person and Telephone no.	Whether services satisfactory? (Attach certificate from client)*

Name of Authorised Signatory _____

Sign and Signature of Authorised Signatory _____

In the capacity of / Designation _____

Duly authorized to sign bids for and on behalf of _____ (IN CAPITALS)

NOTE:

- Bidder to provide relevant certificates from the above mentioned organizations.
- The name and address of the organization along with key persons, their designation, telephone no. and email address should be provided.

* Satisfactory completion and performance certificate from the principal employer / client for satisfactory execution of similar work as defined in eligibility criteria.

Annexure-VI: COMPLIANCE STATEMENT

(To Be Submitted With Bid on Bidder's Letterhead)

DECLARATION:

Please note that any deviations mentioned elsewhere in the bid will not be considered and evaluated by the Bank. Bank reserve the right to reject the bid, if bid not submitted in proper format as per Tender Document.

Compliance	Description	Compliance (Yes/No)
Terms and Conditions	We hereby undertake and agree to abide by all the terms and conditions including all annexure, corrigendum(s) etc. stipulated by the Bank in this Tender Document. (Any deviation may result in disqualification of bids).	

Name of Authorised Signatory_____

Sign and Signature of Authorised Signatory _____

In the capacity of / Designation _____

Duly authorized to sign bids for and on behalf of_____ (IN CAPITALS)

**Annexure-VII: UNDERTAKING FOR PROCUREMENT FROM COUNTRY SHARING
LAND BORDER WITH INDIA**

(To be submitted With Bid on bidder's letter head)

**(Designation, Name of Office along with
Complete address to be inserted here)**

Reg: Carpentry, Electrical, Lan Cabling, Air Conditioning & other miscellaneous allied works at 3rd Floor of Rava Tower, Lutuma, A K Azad Road, Guwahati, Assam.

Note: Tender Issuing Office to Select First Paragraph Only for tender without any subcontracting, i.e., work that does not involve engagement of any sub-agency / sub-contractor / sub-vendor. For other cases, Second Paragraph to be selected.

"I have read the clause regarding restrictions on procurement from a bidder of a country which shares a land border with India; I certify that I am not from such a country or, if from such a country, have been registered with the Competent Authority. I hereby certify that I fulfil all requirements in this regard and is eligible to be considered. [Where applicable, evidence of valid registration by the Competent Authority shall be attached.]"

OR

"I have read the clause regarding restrictions on procurement from a bidder of a country which shares a land border with India and on sub-contracting to contractors from such countries; I certify that I am not from such a country or, if from such a country, have been registered with the Competent Authority and will not sub-contract any work to a contractor from such countries unless such contractor is registered with the Competent Authority. I hereby certify that I fulfill all requirements in this regard and is eligible to be considered. [Where applicable, evidence of valid registration by the Competent Authority shall be attached.]"

Dated this day of _____ 202__.

Name of Authorised Signatory_____

Sign and Signature of Authorised Signatory _____

In the capacity of / Designation _____

Duly authorized to sign bids for and on behalf of _____ (IN
CAPITALS)

Annexure-VIII: DETAILS OF INSURANCE POLICIES

(To be submitted by the successful bidder after award of work on their letterhead)

(Designation, Name of Office along with
Complete address to be inserted here)

Reg: Carpentry, Electrical, Lan Cabling, Air Conditioning & other miscellaneous allied works at 3rd Floor of Rava Tower, Lutuma, A K Azad Road, Guwahati, Assam.

This is in reference to the captioned work awarded to me/us vide your award letter dated _____. In this regard, please find enclosed the policies as under

Type of Policies	Name of Insurance Provider	Amount Insured (Rs.)	Policy No.	Validity
CAR Policy including 3rd Party Liability				
Workman Compensation Policy				

2. We understand that Bank is not liable for damage to any works carried out at site, materials brought or affixed at site unless handed over in total, complete in all respects to the Bank.

3. We undertake that the policies shall remain valid for minimum duration of period of work or up to handover of site, whichever is later.

4. We also understand that the above policies shall be suitably updated to cover any increase in insurance coverage of works / materials at site due to:

- Replacement / rectification of rejected materials, workmanship etc.
- Extension of time.
- Increase in scope of work, including extra items, if any.

5. Bank shall be at the liberty to deduct suitable amounts from our payments due / security deposit for gap in / lack of insurance coverage.

Name of Authorised Signatory_____

Sign and Signature of Authorised Signatory _____

In the capacity of / Designation _____

Duly authorized to sign bids for and on behalf of _____ (IN CAPITALS)

INTEGRITY PACT

To,

.....,
.....,
.....

Reg: **Carpentry, Electrical, Lan Cabling, Air Conditioning & other miscellaneous allied works at 3rd Floor of Rava Tower, Lutuma, A K Azad Road, Guwahati, Assam.**

Dear Sir,

It is here by declared that PNB is committed to follow the principle of transparency, equity and competitiveness in public procurement.

The subject Notice Inviting Tender (NIT) is an invitation to offer made on the condition that the Bidder will sign the integrity Agreement, which is an integral part of tender/bid documents, failing which the bidder/ bidder shall stand disqualified from the tendering process and the bid of the bidder would be summarily rejected.

This declaration shall form part and parcel of the Integrity Agreement and signing of the same shall be deemed as acceptance and signing of the Integrity Agreement on behalf of the PNB.

Yours faithfully

Chief Manager

Annexure-IX: INTEGRITY PACT

(Note to Tender Issuing Office: This Annexure is to be Included in Tenders Which Are Valued ₹ 60 Lacs and above and May be deleted from other tenders)

To,

(Designation, Name of Office along with Complete address to be inserted here)

Sub: **Carpentry, Electrical, Lan Cabling, Air Conditioning & other miscellaneous allied works at 3rd Floor of Rava Tower, Lutuma, A K Azad Road, Guwahati, Assam.**

Dear Sir,

I/We acknowledge that PNB is committed to follow the principles thereof as enumerated in the Integrity Agreement enclosed with the tender/ bid document.

I/We agree that the Notice Inviting Tender (NIT) is an invitation to offer made on the condition that I/ We will sign the enclosed integrity Agreement, which is an integral part of tender documents, failing which I/ We will stand disqualified from the tendering process. I/ We acknowledge that THE MAKING OF THE BID SHALL BE REGARDED AS AN UNCONDITIONAL AND ABSOLUTE ACCEPTANCE of this condition of the NIT.

I/ We confirm acceptance and compliance with the Integrity Agreement in letter and spirit and further agree that execution of the said Integrity Agreement shall be separate and distinct from the main contract, which will come into existence when tender/bid is finally accepted by PNB.

I/ We acknowledge and accept the duration of the Integrity Agreement, which shall be in the line with the enclosed Integrity Agreement.

I/ We acknowledge that in the event of my/ our failure to sign and accept the Integrity Agreement, while submitting the tender/ bid, PNB shall have unqualified, absolute and unfettered right to disqualify the bidder/ bidder and reject the tender/ bid in accordance with terms and conditions of the tender/bid.

Name of Authorised Signatory_____

Sign and Signature of Authorised Signatory _____

In the capacity of / Designation _____

Duly authorized to sign tenders for and on behalf of_____ (IN CAPITALS)

Pre Contract Integrity Pact

Punjab National Bank, a body corporate constituted under the Banking Companies (Acquisition and Transfer of Undertaking) Act 1970 (Act no V of 1970) and having its Head Office at Plot no. 4, Sector 10, Dwarka, New Delhi 110075, hereinafter referred to as “The Principal”, which expression shall mean and include unless the context otherwise requires, its successors in office and assigns of the First Part.

And

M/s. _____ having its registered office at _____ hereinafter referred to as “The Bidder/ Contractor”, expression shall mean and include unless the context otherwise requires, successors and permitted assigns of the Second part.

Preamble

The Principal intends to award, under laid down organizational procedures, contract/s for..... The Principal values full compliance with all relevant laws of the land, rules, regulations, economic use of resources and of fairness/ transparency in its relations with its Bidder(s) and/or Contractor(s).

In order to achieve these goals, the Principal will appoint Independent External Monitors (IEMs) who will monitor the tender process and the execution of the contract for compliance with the principles mentioned above.

Section 1- Commitments of the Principal

(1) The Principal commits itself to take all measures necessary to prevent corruption and to observe the following principles:-

a. No employee of the Principal, personally or through family members, will in connection with the tender for, or the execution of a contract, demand, take a promise for or accept, for self or third person, any material or immaterial benefit which the person is not legally entitled to.

b. The Principal will, during the tender process treat all Bidder(s) with equity and reason. The Principal will in particular, before and during the tender process, provide to all Bidder(s) the same information and will not provide to any Bidder(s) confidential/ additional information through which the Bidder(s) could obtain an advantage in relation to the tender process or the contract execution.

c. The Principal will exclude from the process all known prejudiced person.

(2) If the Principal obtains information on the conduct of any of its employees which is a criminal offence under the IPC/ PC Act, or if there be a substantive suspicion in this regard, the Principal will inform the Chief Vigilance Officer and in addition can initiate disciplinary actions.

Section 2- Commitments of the Bidder(s)/ Contractor(s)

(1) The Bidder(s)/ Contractor(s) commit themselves to take all measures necessary to prevent corruption during any stage of bid process/ contract. The Bidder(s)/ Contractor(s) commit themselves to observe the following principles during participation in the tender process and during the contract execution.

a. The Bidder(s)/ Contractor(s) will not, directly or through any other person or firm, offer promise or give to any of the Principal's employees involved in the tender process or the execution of the contract or to any third person any material or the other benefit which he/ she is not legally entitled to, in order to obtain in exchange any advantage of any kind whatsoever during the tender process or during the execution of the contract.

b. The Bidder(s)/ Contractor(s) will not enter with other Bidders into any undisclosed agreement or understanding, whether formal or informal. This applies in particular to prices, specifications, certifications, subsidiary contracts, submission or non-submission of bids or any other actions to restrict competitiveness or to introduce cartelization in the bidding process.

c. The Bidder(s)/ Contractor(s) will not commit any offence under the relevant IPC/PC Act; further the Bidder(s)/ Contractor(s) will not use improperly, for purposes of competition or personal gain, or pass on to others, any information or document provided by the Principal as part of the business relationship, regarding plans, technical proposal and business details, including information contained or transmitted electronically.

d. The Bidder(s)/ Contractor(s) of foreign origin shall disclose the name and address of the Agents/representatives in India, if any, similarly the Bidder(s)/ Contractor(s) of Indian Nationality shall furnish the name and address of the foreign principals, if any. Further details as mentioned in the "Guidelines on Indian Agents of Foreign Suppliers" shall be disclosed by the Bidder(s)/ Contractor(s). Further, as mentioned in the Guidelines all the payments made to the Indian agent/ representative have to be in Indian Rupees only.

e. The Bidder(s)/ Contractor(s) will, when presenting their bid, disclose any, and all payments made, is committed to or intends to make to agents, brokers or any other intermediaries in connection with the award of the contract.

f. Bidder(s)/ Contractor(s) who have signed the Integrity Pact shall not approach the Courts while representing the matter to IEMs and shall wait for their decision in the matter.

(2). The Bidder(s)/ Contractor(s) will not instigate third persons to commit offences outlined above or be an accessory to such offences.

Section-3 Disqualification from tender process and exclusion from future contracts.

If the Bidder(s)/ Contractor(s) before award or during execution has committed a transgression through a violation of Section 2, above or in any other form such as to put their reliability or credibility in question, the Principal is entitled to disqualify the Bidder(s)/ Contractor(s) from the tender process or take action as per the procedure mentioned in the "Guidelines on Banning of business dealings".

Section 4- Compensation for Damages

(1). If the Principal has disqualified the Bidder(s) from the tender process prior to the award according to Section 3, the Principal is entitled to demand and recover the damages equivalent to earnest Money Deposit/ Bid Security.

(2). If the Principal has terminated the contract according to Section 3, or the Principal is entitled to terminate the contract according to Section 3, the Principal shall be entitled to demand and recover from the Contractor liquidated damages of the contract value or the amount equivalent to Performance Bank Guarantee/ Initial Security Deposit.

Section 5- Previous transgression

(1) The Bidder declares that no previous transgression occurred in the last three years immediate before signing of this integrity pact with any other Company in any country conforming to the anti-corruption approach or with any Public Sector Enterprises or central/ state government department in India that could justify his exclusion from the tender process.

(2). If the Bidder makes incorrect statement on this subject, he can be disqualified from the tender process or action can be taken as per the procedure mentioned in "Guidelines on Banning of business dealing".

Section 6- Equal treatment of all Bidders/ Contractors/ Subcontractors

(1) In case of Sub-contracting, the Principal Contractor shall take the responsibility of the adoption of integrity Pact by the Sub-contractor.

(2) The Principal will enter into agreements with identical conditions as this one with all Bidders and Contractors.

(3) The Principal will disqualify from the tender process all the Bidders who do not sign this Pact or violate its provisions.

Section 7- Criminal charges against violating Bidder(s) / Contractor(s) / Subcontractor (s)

If the Principal obtains knowledge of conduct of a Bidder, Contractor or Sub contractor, or of an employee or a representative or an associate of a Bidder, Contractor or Subcontractor which constitutes corruption, or if the Principal has substantive suspicion in this regard, the Principal will inform the same to the Chief Vigilance Officer.

Section 8- Independent External Monitor

(1) The Principal appoints competent and credible Independent External Monitor for this Pact after approval by Central Vigilance Commission. The task of the Monitor is to review independently and objectively, whether and to what extent the parties comply with the obligations under the agreement.

Sh. Madhusudan Prasad, IAS (Retd.) have been appointed as Independent External Monitors (IEMs) by our Bank. Their e-mail addresses are as under:

Sl.	Name of IEM	e-mail	Mob. No.
1.	Sh. Madhusudan Prasad, IAS (Retd.)	mprasad23@gmail.com	9717585556

(Note to Bidders: the above persons are not to be contacted for generic tender related queries, as the queries must be directed to contact details mentioned in Notice Inviting Tender)

(2) Only Integrity pact related queries to be addressed to IEMs. Also the bids of the bidders who do not sign the Integrity Pact will not be evaluated further.

(3) The Monitor is not subject to instructions by the representatives of the parties and performs his/ her functions neutrally and independently. The Monitor would have access to all Contract documents, whenever required. It will be obligatory for him/her to treat the information and documents of the Bidders/ Contractors as confidential. He/she reports to the Managing Director and CEO, Punjab National Bank.

(4) The Bidder(s)/ Contractor(s) accepts that the Monitor has the right to access without restriction to all project documentation of the Principal including that provided by the Bidder(s)/ Contractor(s). The Bidder(s)/ Contractor(s) will also grant the Monitor, upon his/ her request and demonstration of a valid interest, unrestricted and unconditional access to their project documentation. The same is applicable to Sub-contractor.

(5) The Monitor is under contractual obligation to treat the information and documents of the Bidder(s)/ Contractor(s)/ Subcontractor(s) with confidentiality. The Monitor has also signed declarations on "Non-Disclosure of Confidential Information" and of "Absence of Conflict of Interest". In case of any conflict of interest arising at a later date, the IEM shall inform MD & CEO, Punjab National Bank and recues himself/ herself from that case.]

(6) The Principal will provide to the Monitor sufficient information about all meetings among the parties related to the Project provided such meetings could have an impact on the contractual relations between the Principal and Contractor. The parties offer to the Monitor the option to participate in such meetings.

(7) As soon as the Monitor notices, or believes to notice, a violation of this agreement, he/ she will so inform the Management of the Principal and request the Management to discontinue or take corrective action, or to take other relevant action. The monitor can in this regard submit non-binding recommendations. Beyond this, the Monitor has no right to demand from the parties that they act in a specific manner, refrain from action or tolerate action. The Monitor will submit a written report to the MD & CEO, Punjab National Bank within 8 to 10 weeks from the date of reference or intimation to him by the Principal and, should the occasion arise, submit proposals for correcting problematic situations.

(8) If the Monitor has reported to the MD& CEO, Punjab National Bank, a substantiated suspicion of an offence under relevant IPC/PC Act, and the MD & CEO, PNB has not, within the reasonable time taken visible action to proceed against such offence or reported it to the Chief Vigilance Officer, the Monitor may also transmit this information directly to the Central Vigilance Commissioner.

(9) The word '**Monitor**' would include both singular and plural.

Section 09- Pact Duration

This Pact begins when both parties have legally signed it. It expires for the Contractor 12 months after the last payment under the contract, and for all other Bidders 6 months after the contract has been awarded. Any violation of the same would entail disqualification of the bidders and exclusion future business dealings.

If any claim is made/ lodged during this time, the same shall be binding and continue to be valid despite the lapse of this pact as specified above, unless it is discharged/ determined by MD & CEO, PNB.

Section 10- Other provisions

- (1) This agreement is subject to Indian Law. Place of performance and jurisdiction is the "Place of award of work".
- (2) The actions stipulated in this Integrity Pact are without prejudice to any other legal action that may follow in accordance with the provisions of to the extant law in force relating to any civil or criminal proceedings.
- (3) Changes and supplements as well as termination notices need to be made in writing. Side agreements have not been made.
- (4) If the Contractor is a partnership or a consortium, this agreement must be signed by all partners or consortium members.
- (5) Should one or several provisions of this agreement turn out to be invalid, the remainder of this agreement remains valid. In this case, the parties will strive to come to an agreement to their original intentions.
- (6) Issues like warranty/ Guarantee etc. shall be outside the purview of IEMs.
- (7) In the event of any contradiction between the Integrity Pact and its Annexure, the Clause in the Integrity Pact will prevail.

(For & On behalf of the Principal)

(For & On behalf of Bidder/ Contractor)

(Office Seal)

(Office Seal)

Place.....

Date.....

Witness 1:

Witness 2:

(Name & Address)

(Name & Address)

Annexure-X: GUARANTEE BOND FOR WATER PROOFING WORKS

(Note to Tender Issuing Office: This Annexure is to be Included in Tenders Which Involve Water Proofing Works and May be deleted from other tenders)

The Agreement made thisday of two thousand and betweenson of of (hereinafter called the Guarantor of the one part) and the Punjab National Bank (.....) (hereinafter called the Bank of the other part).

WHEREAS this agreement is supplementary to a contract (hereinafter called the Contract) dated and made between the GUARANTOR of the one part and the Bank of the other part, whereby the Contractor, inter alia, undertook to render the buildings and structures in the said contract recited completely water and leak-proof.

AND WHEREAS GUARANTOR agreed to give a guarantee to the effect that the said structures will remain water and leak-proof for **ten years** from the date of giving of water proofing treatment.

NOW THE GUARANTOR hereby guarantees that water proofing treatment given by him will render the structures completely leak-proof and the minimum life of such water proofing treatment shall be **ten years** to be reckoned from the date after the maintenance period prescribed in the contract.

Provided that the guarantor will not be responsible for leakage caused by earthquake or structural defects or misuse of roof or alteration and for such purpose:

- i) Misuse of roof shall mean any operation which will damage proofing treatment, like chopping of firewood and things of the same nature which might cause damage to the roof;
- ii) Alteration shall mean construction of an additional storey or a part of the roof or construction adjoining to existing roof whereby proofing treatment is removed in parts;
- iii) The decision of the Bank's Officer-in-Charge with regard to cause of leakage shall be final.

During this period of guarantee the guarantor shall make good all defects and in case of any defect being found, render the building water-proof to the satisfaction of the Officer-in-Charge at his cost, and shall commence the work for such rectification within seven days from the date of issue of the notice from the Officer-in-Charge calling upon him to rectify the defects, failing which the work shall be got done by the Bank by some other contractor at the GUARANTOR'S cost and risk. The decision of the Officer-in-Charge as to the cost, payable by the Guarantor shall be final and binding.

That if GUARANTOR fails to execute the water proofing or commits breach thereunder then the GUARANTOR will indemnify the Bank or its successors or assigns against all losses, damages, costs, expenses or otherwise which may be incurred by reason of any default on the part of the GUARANTOR in performance and observance of this supplementary agreement. As to the amount of loss and/or damage and/or cost incurred by the Bank the decision of the Officer-in-Charge will be final and binding on the parties.

IN WITNESS WHEREOF these presents have been executed by the Guarantorand by for and on behalf of the Punjab National Bank on the day, month and year first above written.

Signed, sealed and delivered by Guarantor in the presence of —

- 1.
- 2.

Signed for and on behalf of Punjab National Bank by in the presence of -

- 1.
- 2.

Remarks :

- i) This form is included in the tender document only for the information of bidders. Only the successful bidder will in due course be required to complete this form.
- ii) Stamp Duty of this Agreement will be borne by the successful bidder.
- iii) **The Bond is to be submitted separately by the successful bidder on a non-judicial stamp paper of Rs. 100/- (Rupees One Hundred) only.**

Annexure-XI: GUARANTEE BOND FOR ANTI-TERMITE WORKS

(Note to Tender Issuing Office: This Annexure is to be Included in Tenders Which Involve Anti-Termite Works and May be deleted from other tenders)

The Agreement made thisday of two thousand and betweenson of of (hereinafter called the Guarantor of the one part) and the Punjab National Bank (.....) (hereinafter called the Bank of the other part).

WHEREAS this agreement is supplementary to a contract (hereinafter called the Contract) dated and made between the GUARANTOR of the one part and the Bank of the other part, whereby the Contractor, inter alia, undertook to render the buildings and structures in the said contract recited completely termite-proof.

AND WHEREAS GUARANTOR agreed to give a guarantee to the effect that the said structures will remain termite-proof for **ten years** from the date of giving of anti-termite treatment.

During this period of guarantee the guarantor shall make good all defects and for that matter shall replace at his risk and cost such wooden member as may be damaged by termite and in case of any other defect being found, he shall render the building termite proof at his cost to the satisfaction of the Officer-In-Charge and shall commence the works of such rectification within seven days from date of issuing notice from the Officer-In-Charge calling upon him to rectify the defects falling which the work shall be got done by the Bank by some other Contractor at the guarantor's cost and risk and in the later case the decision of the Officer-In-Charge as to the cost recoverable from the guarantor shall be final and binding.

That if the Guarantor fails to execute the Anti-Termite treatment or commits breaches hereunder then the Guarantor will indemnify the Bank or its successors against all losses damages, cost expenses or otherwise which may be incurred by reasons of any default on the part of the guarantor in performance and observance of this supplementary Agreement. As to the amount of loss and or damage and/or cost incurred by the Bank, the decision of the Officer-In-Charge will be final and binding on the parties.

IN WITNESS WHEREOF these presents have been executed by the Guarantorand by for and on behalf of the Punjab National Bank on the day, month and year first above written.

Signed, sealed and delivered by Guarantor in the presence of —

1.

2.

Signed for and on behalf of Punjab National Bank by in the presence of-

1.

2.

Remarks :

- i) This form is included in the tender document only for the information of bidders. Only the successful bidder will in due course be required to complete this form.
- ii) Stamp Duty of this Agreement will be borne by the successful bidder.
- iii) **The Bond is to be submitted separately by the successful bidder on a non-judicial stamp paper of Rs. 100/- (Rupees One Hundred) only.**

LIST OF PREFERRED MAKE OF MATERIAL

The material of standard quality from the following preferred makes is to be used. In case it is established that the brands specified below are not available in the market, contractor shall submit alternative proposal for the approval of Bank.

Items	Preferred make of materials
Steel	SAIL/ Tata Steel/ JSW Steel Ltd./ RINL/ JSL
Cement	Ultratech/ ACC/ JK Cement/ Ambuja
Plastic Emulsion Paint/Texture / OBD/Duco Paint/Synthetic enamel.	Asian / Dulux / Berger / Nerolac
Exterior Paint / Water Proof Paint/ Bitumastic Paint	Asian / Dulux / Berger / Nerolac
Putty	Birla / JK / Asian paint/ Sakarni
Vitrified Tile	RAK / Kajaria/ Johnson
Ceramic Tile (for kitchen/toilet/ bathroom)	RAK / Kajaria/ Johnson
Pasting Chemicals for Tiles	Pidilite/ Fosroc/ Eurokart/ MYK Laticrete
PVC Tanks	Sintex / Patton/ Supreme/ Astral
C.P. Fittings/ Sanitary ware	Jaquar/ Hindware / Cera / Parryware
Kitchen Sink	Cera/ Nirali/ Hindware/ Neelkanth/ Jayna
G.I. Pipe & Fittings	TATA / Swastik / UNIK / KS /Jindal
C.I. Pipes & Fittings	R.I.F./ SRIF/ KAJEEO
CPVC/ UPVC Pipe/ Accessories	Prakash/ Jindal/ Supreme/ Astral/ Finolex/ Prince
Glass	Modi Guard/Saint Gobain/ Asahi
uPVC doors/ windows	Fenesta/ Rehau/ Prominace/ Saint Gobain/ Kommerling
PVC rigid foam sheet/profile	Greenply/ Century/ Alstone
WPC frame	Century/ Greenply/ Alstone
Plywood/Block Board / MDF	Green / Archidply / DURO/ Century/ Samrat/ Action Tesa/ Kitply
Laminate/ high pressure laminate	Green/ Archidply/ Merino/ AICA/ Century
Adhesive/Glue	Fevicol/ Vemicol
Locks in cabinets, furniture, Door	Godrej/ Dorset/ Hettich/ Link/ Europa
All hardware and fittings i/c door closer	Ebco/ Godrej/ Hettich/ Ozone/ Dorset/ Kich/ Hafelle/ Dorma Kaba/ D-Line
Natural wood veneers	Archidply/ Green/ Duro/ Century
Water based melamine polish	Asian paints / Pidilite Industries/ Dulux/ Berger/ Nerolac
Dash/ Anchor fasteners	Hilti/ Fischer/ Bosch / Wuerth
Water Proofing Chemicals	Cico / SIKA / Pidilite / FOSROC/MYK Laticrete
False ceiling	Knauf (Armstrong)/ Gyproc/ HunterDouglas
Roller Blinds	Vista/ Mac/ D'Decor
Aluminium	Jindal/ Hindalco
Modular Furniture (workstation/storages)	Godrej / Haworth / Steelcase / Herman Miller / Featherlite / Durian

Items	Preferred make of materials
Chairs	Godrej / Featherlite / Wipro
PVC conduit/ fittings	AKG / Precision/ BEC
PVC insulated copper FRLS Cable	Finolex/ Polycab/ Havells/ KEI
PVC / XLPE Multi Core Cables (armored/ unarmoured)	Finolex/ Polycab/ Havells/ KEI
Modular Switch Sockets & accessories	Crabtree / Northwest /Anchor-Roma / SSK / Legrand / ABB
MCB & MCCB	Legrand/Havells/L&T/Siemens/ABB/Schneider
Motor	Crompton/Kirloskar/Bajaj/ Siemens
Light fitting	PHILIPS/Havells/Wipro/Bajaj/Osram
Ceiling/ Wall fan	Crompton / Usha/ Havells/ Orient / Bajaj / Almonard
Exhaust fan	Crompton / Usha/ Havells/Orient/ Bajaj / Almonard
A.C Starter, Plug Socket	Crabtree/Northwest/Legrand/ABB/Schneider/Havells
Fuse Switch Unit (FSU)	L&T / Havells/ Siemens
Cable Lug	Dowell's/Jainsons/3-D/Comet
Cable gland	Jainsons/Comet or equivalent
Distribution board	L&T/Havells/Siemens/Hager/ Legrand/ABB/Schneider
MS conduit & Accessories	BEC/AKG/Precision
Telephone cable	Delton/National/ Finolex/ Polycab/ Havells
Telephone Connector	Krone/ D-link or Equivalent.
Starter & single phasing preventer	SIEMENS/ L&T/ ABB
MV/LT Panel Board	CPRI Approved Manufacturer for the required rating specified in the tender.
CT/PT	Automatic Electric / Crompton / Kappa
Digital Meters	Conzerve / Scheider / Secure / Rishab
HRC Fuse & Fitting	Siemens/L&T/ Hager
Cable tray	Slotco/ Rico/ Profab/ Indiana/ Milestone/MEM/Legrand
Raceway	Slotco/ Rico/ Profab/ Indiana/ Milestone/MEM/Legrand
Chemical Earthing	Universal Altex / Ashlok / JMV/ ERICO
Changeover (On-Load)	L&T/Hager/Siemens/ Legrand
PVC Casing & Capping Fittings	BEC/AKG/ Precision
Pumps	Kirlosker/Crompton Greaves/Wilo/Mather & Platt/KSB
MS Pipe	Jindal/Tata/Sail
Butterfly/ NRV/ Ball/ Gate Valve	Zoloto/ Leader/ Sant/ Kartar
Sprinkler Head	HD/Tyco or equivalent
Flexible Pipe for Sprinkler	HD/Tyco or equivalent
Landing valve	New Age/ Zoloto/ Safex/Onex/new Tech or equivalent
Hose reel, Hose pipe	New Age/ Zoloto/ Safex/Onex/new Tech or equivalent

NOTE:-

1. In case of unavailability of any material of specific make from above mentioned preferred make of material, an equivalent make can be used only after a written approval of the Bank.

2. The contractor shall provide samples of all materials mentioned in the list of makes as required by the Bank. A written approval of these samples shall be sought prior to commencement of any work. Bank reserve the right to enquire the genuineness of any material used at site directly from the manufacturer/ dealer.

COMMERCIAL BID

Sl. No.	DESCRIPTION	UNIT	QTY.	Rate Incl GST	Amount
1	<p>PARTITIONS:FULL HT. FULLY GLAZED PARTITION IN PATCH FITTINGS</p> <p>Providing and fixing of Fixed Glass partition with 10mm thick toughened glass using Standard fittings of above - mentioned makes at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealant wherever required. The top fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling. Rate shall be inclusive of frosted film and bank logo to be fixed over the glass surface as per design and as directed by the architect.</p> <p>OZONE Make: OGL-PR-11 or equivalent, 2 MTRS GLASS WEDGE SYSTEM Shoe screw, shoe, flip cap etc complete.</p>	S.FT.	251	To be quoted online	To be quoted online
2	<p>FULL HT SOLID PARTITION</p> <p>Providing and fixing in position full height solid partition 75 mm thk. as indicated in the drawing excluding the door. The partition shall be made of Aluminium Frame Work of hollow sections of specified sizes given below of approved make conforming to IS: 733 and IS : 1285, fixed with rawl plugs and screws or with fixing clips with vertical & horizontal members at not more than 600 mm center to center all complete including necessary additional supports for fixing of patch fittings of door, bracing, runner etc. so that lateral movement is arrested as per instructions of EIC / Architect. The first horizontal member shall be fixed at ground level and thereafter at every 600mm. Framework shall be fixed with 8/9mm thick BWP grade ply of required width and size as per drawing including cost of making openings for switches, AC facias etc. The rate</p>	S.FT.	1420	To be quoted online	To be quoted online

	includes cost of polishing, adhesives like fevicol, silicon, nails, screws and labour charges etc. all as per instructions of EIC / Architect.. The ply finished Partition shall then be finished with or without 1.0 mm thick laminate of approved shade and make or equivalent on both the sides as per the description as below. Rate shall be inclusive of provision of pencil groove as directed by the Architect. Height of the partitions upto soffit of false ceiling / laminate finish top shall be considered for payment. Alternate, corner vertical members of the partition shall be fixed with necessary brackets / supports at RCC levels. The framework above the false ceiling shall not be considered for payment. The item does not include the doors. FINISHED WITH BOTH SIDE LAMINATE				
3	GLASS WOOL FOR PARTITION Providing and fixing thermal insulation with Resin Bonded Fibre glass wool conforming to IS : 8183,(acoustic insulation material) 32kg/cum density of 50mm thick wrapped in 200G Virgin Polythene bags placed in between partitions and wall panelling and held in position by criss-crossing GI wire. It should be ensured that the fiberglass wool is wire-braced(chicken mesh) to prevent it from 'lumping down' over a period of time. The actual surface area of the insulation only will be measured for payment.	SFT	1420.00	To be quoted online	To be quoted online
4	PANELLING ON WALLS/ COLUMNS - with or without frame Providing and fixing of wall panelling directly on the wall surface with or without any framework with 12mm thick BWP grade ply and then finished with 1.0 mm thick. laminate of approved shade. If the framework is required it shall be of aluminium hollow sections of 50mm x 50mm size 1.5mm thick of JINDAL / INDAL make as internal frame structure placed horizontally & vertically in 550 mm x 550 mm or 600mm x 600mm center to center or as directed by the Architect . All woodwork & laminate shall be finished with two or	S.FT.	112	To be quoted online	To be quoted online

	more coats of Melamine or PU polish over one coat of sealer; all complete as per the instructions of Architect. The rate shall be inclusive of provision of groove with 1.0 mm thick. laminate along all 3 sides of the groove in the panelling of size 12mm x 12mm x 18 mm ht. and as directed by the Architect. This item also includes scaffolding for maximum height upto 4.0 m from floor level. WITH LAMINATE				
5	PANNELLING WITH LECQUERED GLASS OF APPROVED SHADE Providing and fixing of paneling with or without frame so as to receive a plain and even surface in exact plumb line , covered with 9mm thick commercial ply and finished with 6mm thick TEMPERED LECQUERED GLASS of approved shade and make as per the design . Rate shall be inclusive of 100 mm high skirting of silver metal laminate as and where required and as per the direction of the Consultant Architect/ Engineer.	S.FT.	98	To be quoted online	To be quoted online
6	ENTRANCE DOORS - GLAZED DOOR WITH TOUGHENED GLASS (PATCH FITTINGS) Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings(Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(ABOVE MENTIONED MAKES Top Pivot , Top Patch Fittings, Bottom Patch fittings , Floor Spring , Corner lock with strike plate and Euro Profile Cilinder, C Shape Handle 25mm dia X 300mm length) DOORS - WITH OZONE / HAFFLE / YALE / GODREJ MAKE FITTINGS	S.FT.	161	To be quoted online	To be quoted online

7	<p>DOORS ON WOODEN PARTITION WALLS</p> <p>'SOLID DOORS- IN LAMINATE FINISH (WITH OR WITH OUT VISION PANEL AS PER DIRECTION OF the ARCHITECT</p> <p>Providing and fixing solid doors of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 1mm thick laminate/ 4.0 mm thk veneer with mellamine polish of approved shade and make on both sides. The edges finished with steam beach lipping. A door frame of 3.5" x 2" steam beach section shall be provided finished in mellamine. Rate shall include Dead lock, floor springs / door closure (as the case may be), door stopper, a pair of handles 12" SS Brushed finished, 5" hinges 4 Nos., buffers, tower bolts, etc with necessary hardware items and with or with out door frames as mentioned above</p> <p>IN BOTH SIDE LAMINATE FINISH</p>	S.FT.	84	To be quoted online	To be quoted online
8	<p>STORE & PANTRY DOORS WITH / WITHOUT FRAME (2'-6" X 7'-0" SIZE)</p> <p>Providing and fixing 35mm thk flush doors of sizes as shown in the drawing. The door shutter shall be of 35 mm thick for flush shutter of approved make and finished with 1mm thick approved laminate on both sides. A door frame of teak wood shall be provided for the Door. Rate shall include approved door closure, door stopper, a pair of handles 9" SS Brushed finished, 5" hinges 4 Nos., buffers, tower bolts, etc with necessary hardware items and with or with out door frames as mentioned above .</p> <p>Note- Payment shall be paid as per the area of the door shutter (no measurement for the door frame shall be done)</p>	S.FT.	126	To be quoted online	To be quoted online

9	<p>LOW HT RUNNING STORAGE(1'-6"DX2'-6"HT) (BACK CADENZA) Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 3/4" thk plywood for top, base and sides and base 1/4" thk marine plywood, 3/4" thk plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate/ veener on all the edges. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be make equally according to the length of the storage. A 3/4" thk fixed ply wood shelf on battens shall be provided @16" intervals from the base. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All inner surfaces including shutters shall be finished with natural french polish. Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make IN LAMINATE FINISH</p>	S.F.T	80	To be quoted online	To be quoted online
10	<p>OVERHEAD STORAGE AT KITCHEN & OVER WASH BASIN IN DINING AREA (1 foot depth) Providing and fixing over-head storages which consist of 18mm thk. BWP. ply shutter with box type higes of approved make & Steam beach lipping with approved laminate/ veener on all the edges. The shutter should be made of of 18mm thk. BWP. Ply top, sides, rear and bottom. All the external surfaces shall be finished with 1.0mm thk. Laminate (suede finish) of approved make. Division of the shutters shall be made equally according to the length of the storage. The edges of the shutters shall be provided with steam beach lipping. One Ply shelf of 18mm thick BWP.ply removable type supported on side steam beach wood battens on both sides (divided equally) shall be provided. All inner surfaces shall be</p>	S.F.T	84	To be quoted online	To be quoted online

	finished with laminate/ veneer including the shutters.. Rate shall be inclusive of all necessary approved fittings like box type hinges, locks, tower bolts, 100mm SS Brush finished handle etc. IN LAMINATE FINISH				
11	FULL HT STORAGES WITH PARTLY GLAZED FRONT DOOR (FOR LIBRARY) Providing & fixing in position Storage cabinets in Library 450 mm deep and 2100/2400mm high made up of 19 mm phenol bonded block board with openable 8mm glass shutter on plywood frames as per design and 8/9 m.m. phenol bonded ply at back. All external surfaces to be finished with 1.0mm thk laminate of approved shade and make in approved pattern and as directed by the architect. It should have drawers/shelves etc. as per the detailed drawing as prepared by the architect. All edges to have TW lipping as/design duly melamine polished hettich/kaff,handles,locks ,flyrail channels etc. All inner surfaces to be finished with 0.80mm thk laminate of pure white colour of approved make and pattern.	S.FT.	212	To be quoted online	To be quoted online
12	M.S. SLOTTED ANGLE STORAGE Providing and making M.S. slotted angle storage using angles of 18 gauge thickness and shelves of 20 gauge designed as per the specifications of standard manufacturers. Shelves shall be provided at 1'-6" c/c & supported on frames on all four sides with vertical supports as per manufacturers' standard specifications.	S.FT.	42	To be quoted online	To be quoted online
13	SHUTTERS BELOW GRANITE COUNTERS IN KITCHEN & WASH BASING COUNTERS Providing and fixing 19mm thk. BWR ply shutters with ply frame, skirting gap as shown in the drg. shall be maintained. Division of shutters shall be made equally according to the length of the counter. Shutters shall be	S.FT.	148	To be quoted online	To be quoted online

	hinged to the framework and finished with 1.0mm thk. Laminate (suede finish) of approved shade from outside, applied with approved oil paint from the inside and edges of shutters with steam beach lipping. Rate shall be inclusive of all necessary approved fittings like hinges, ball catch, handle, and any necessary hardware items.				
14	TABLES Providing and fixing corner / centre table of below mentioned sizes made with 19 mm BWR Ply legs finished in 1 MM laminate. Item includes 10mm bevelled brown glass fixed in 25 MM SS spacers on top. 'CORNER TABLES(1'-6" x 1'-6" x 1'-6"HT.)	NOS.	5	To be quoted online	To be quoted online
15	TABLES Providing and fixing corner / centre table of below mentioned sizes made with 19 mm BWR Ply legs finished in 1 MM laminate. Item includes 10mm bevelled brown glass fixed in 25 MM SS spacers on top. CENTER TABLES (1'-6" X 2'-6" X 1'-6"HT)	NOS.	2	To be quoted online	To be quoted online
16	PIN-UP BOARDS Providing and fixing pinup boards. It consist 12mm thick soft boards of good density to be mounted over 12mm thick BWP ply. The soft board will be covered with a plain fabric (appox Rs.250 /Rmts. of Maroon Colour) from front and edges. Suitable steam beach moulding 25mm x 25mm size to be fixed on all four sides and will be finished in melamine polish. Note- If Steam beach T.W moulding are not provided around the soft board then the rate of this item shall be reduced to Rs 50.00/ sft as per the estimated rate and actual rate shall be calculated based on contractor rate at the time of bidding and shall be derieved accordingly. Note:Only soft boards provided on other than semi ht partitions shall be measured in this item	S.FT.	48	To be quoted online	To be quoted online

17	BOXING FOR ROLLING SHUTTER WITH LAMINATE FINISH Providing & fixing ¾" BWR ply boxing for the rolling shutters. Necessary wooden framing shall be provided. The boxing shall be finished on all exposed sides by 1mm laminate and internally with enamel paint. Note : rate shall include all necessary hardware fittings, etc.	S.FT	50	To be quoted online	To be quoted online
18	TRAP DOOR FOR ROLLING SHUTTERS WITH LAMINATE Providing and fixing trap doors consisting of 1/2" thk. BWP. ply shutters with a clear opening of 4.5" opening for smooth operation of shutters and rest is closed with mirror screws (for opening for servicing). The shutters shall be finished with approved 1mm laminate, frame of 2" x 1 ½" wood sections shall be provided for proper support and strength. Rate shall be inclusive of necessary fittings like hinges of approved make make), ball catches, tower bolts, etc.	S.FT	14	To be quoted online	To be quoted online
19	Gypsum False Ceiling:-Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I.	S.FT.	2650	To be quoted online	To be quoted online

<p>wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cut-outs made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with : 12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095-(Part I) :2011 (Board with BIS certification marks) No additional load like light fittings etc. shall be directly put on the ceiling frame. Separate suspension system shall be adopted for the same.</p> <p>NOTE: The rate shall be inclusive of provision for core lighting, small moulding, verticals in two levels, 18.75mm x 12.5mm grooves on the edges, cutouts for cove lights and AC grills. Note Only the plan area will be measured for payment. No Extra payment will be made for Grooves, Cutouts, Mouldings etc.)</p>				
--	--	--	--	--

20	<p>MODULAR FALSE CEILING- Providing and Fixing 15 mm thick densified regular edged eco friendly light weight calcium silicate false ceiling tiles of approved texture of size 595 x 595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanised steel sections (galvanising @ 120 grams per sqm including both side) consisting of main 'T' runner suitably spaced at joints to get required length and of size 24x38 mm made from 0.33 mm thick (minimum) sheet, spaced 1200 mm centre to centre, and cross "T" of size 24x28 mm made out of 0.33 mm (Minimum) sheet, 1200 mm long spaced between main'T' at 600 mm centre to centre to form a grid of 1200x600 mm and secondary cross 'T' of length 600 mm and size 24 x28 mm made of 0.33 mm thick (Minimum) sheet to be inter locked at middle of the 1200x 600 mm panel to form grid of size 600x600 mm, resting on periphery walls /partitions on a Perimeter wall angle precoated steel of size(24x24X3000 mm made of 0.40 mm thick (minimum) sheet with the help of rawl plugs at 450 mm centre to centre with 25 mm long dry wall screws @ 230 mm interval and laying 15 mm thick densified edges calcium silicate ceiling tiles of approved texture in the grid, including, cutting/ making opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc., wherever required. Main 'T' runners to be suspended from ceiling using G.I. slotted cleats of size 25x35x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm G.I. adjustable rods with galvanised steel level clips of size 85 x 30 x 0.8 mm, spaced at 1200 mm centre to centre along main 'T', bottom exposed with 24 mm of all Tsections shall be pre-painted with polyster baked paint, for all heights, as per specifications, drawings and as directed by Engineer-in-Charge.</p>	S.FT.	2052	To be quoted online	To be quoted online
----	---	-------	------	---------------------	---------------------

21	WALL PUTTY Providing and applying Wall Putty on walls and columns (average 12mm thick). The rate shall include scrapping, levelling and preparing the surface. The rate shall be inclusive of all types of grooves above the skirting, around the window and door frames. If the average thickness is found to 8mm 6mm or less, then Wall putty will be considered as putti finish at the rate of 50% the quoted rate (Make Birla/Asian/Berger)	S.FT.	2500	To be quoted online	To be quoted online
22	POP PUNNING FOR GYPSUM CEILING Providing and applying POP Punning on Gypsum Ciling (average 6mm thk). The rate shall include scrapping, levelling and preparing the surface. The rate shall include scrapping, levelling and preparing the surface. The rate shall be inclusive of all types of grooves above the skirting, around the windows and door frames. If the average thickness is found to be 4mm or less than POP will be considered as a putti finish and the rate shall be 50% of the quoted rate	S.FT.	2650	To be quoted online	To be quoted online
23	PLASTIC EMULSION ON GYPSUM CEILING Providing & applying plastic emulsion paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make , quality & finish shall be provided.	S.FT.	2650	To be quoted online	To be quoted online
24	PLASTIC EMULSION PAINT ON WALLS Providing and applying Plastic Emulsion Paint of approved brand and shade on walls and ceiling (new work) using rollers to get an even finish. The rate quoted should be inclusive of applying primer, etc. to make the surface ready for applying plastic emulsion paint all complete as per satisfaction of the Bank.	S.FT.	6000	To be quoted online	To be quoted online

25	<p>ROLLER BLINDS: Providing and fixing of Roller Blind should have sturdy aluminium top tube of 38mm diameter, powder coated bottom bar, with suitable roller clutch mechanism and plastic ball chain. The Roller Blind fabric should possess the below mentioned specifications: a) Openness factor - 3-5%, b) Composition –20%-25% polyester and 80%-85% vinyl on polyester c) Core yarn should be Polyester d) Fabric thickness – 0.6-0.75 mm & Weight - 490 gsm ($\pm 5\%$) e) UV blockage – 97% (minimum) f) Leadfreecertified – RoHS compliant g) Flame Retardant – NFPA 701 h) Anti-fungal / Anti-bacterial i) Acoustical Value - NRC 0.15 / SAA 0.18. Aluminium profile should have temper WP consisting of alloy 63400 along with anodizing of 10 micron and powder coating of 60 micron. The tensile strength of profile should be 9.10 Kg/mm square and elongation 18. The control clutch drive unit engineered heavy duty chain drive pulley operating system consisting of gear clutch housing and locking plug containing minimum 6 ribs and inserted at minimum of 38mm into roller tube. It is self-lubricating Exclusive clutch with safety pins for secure bracket installation and unlocking pin for quick manual removal. Universal clutch is most convenient for large windows down to the smallest windows. It shall be driven by a ball chain pulley with ball chain and can be positioned at Right hand or Left hand side of the shade. Clutch gear ratio of 1.75:1 for reduced operating force on larger blinds.. Mounting hardware brackets universal brackets including end plug bracket with lock down retainer device. Brackets finish of powder coated metal installation brackets made of stamped and hardened steel. Roller tube circular-shaped aluminium tube extruded from alloy 63400 and temper WP. Bottom rail flat-shaped extruded aluminium from alloy 63400 and temper WP. Ball chain shall be 2mm diameter cord with plastic balls</p>	S.FT.	1820	To be quoted online	To be quoted online
----	---	-------	------	---------------------	---------------------

	moulded to form an endless ball chain. It is used for raising or lowering action of the shades. Plastic parts all plastic components are UV-stable compounds available white and as approved by the Architect /Bank complete in all respects				
26	COLOURED ACRYLIC SHEET LOGO OF THE BANK, BACK LIT Supplying , fabricating and installation of Bank's Logo of 2 Nos of Triangle (Blue and Yellow Colour) made of coloured acrylic sheet 5-6mm thk in box section, and as per the sizes as mentioned in the detailed drawings . This Coloured Acrylic sheet box logo should be fixed with strip light fitted from inside , as per the direction of the architect. OVERALL SIZE 750MM X 750MM	NOS	2	To be quoted online	To be quoted online
27	COLOURED ACRYLIC SHEET LOGO OF THE BANK, BACK LIT Supplying , fabricating and installation of Bank's Logo of 2 Nos of Triangle (Blue and Yellow Colour) made of coloured acrylic sheet 5-6mm thk in box section, and as per the sizes as mentioned in the detailed drawings . This Coloured Acrylic sheet box logo should be fixed with strip light fitted from inside , as per the direction of the architect. OVERALL SIZE 450MM X 450 MM	NOS	1	To be quoted online	To be quoted online
28	NOTICE BOARD Providing and fixing notice board size as required/ directed (matching with the panel of the cabin) with openable shutter on the front. Made out of 19mm thick Steam beech veneered block board frame and outer frame in 2 1/2" x 1 1/2" Steam beech wood section ,	SFT.	24	To be quoted online	To be quoted online

	concealed hinges , locking arrangement , and glass of (5.5mm thick) with rear panel of SITATEX board , covered with fabric of approved shade. (Basic rate Rs.100/-per mtr , 48" width), fixed to back ply 6mm thick . All complete including melamine polish in stain of required shade. All complete as per approval of the Architect / employer				
29	WALL PAPER Providing fixing and pasting Wall paper as per design & details. The item includes making POP base to get a uniform smooth surface. (base Price Rs. 100/ sqft.without taxes) The fixed area of wall paper shall be considered for payment and not the area of procured material.	SFT	296	To be quoted online	To be quoted online
30	10MM GLASS SHELVES- 250-300MM WIDE Providing and fixing 10mm thk Clear Glass Shelves, 250-300MM WIDE in mirror polished edges as per design. The Glass selves should be fixed with the help of Stainless Steel F Type Glass Shelf Bracket Square 12 Inches, with screws to walls / partitions/ pannelling, at an interval of 24-30" as per design and as directed by the achitect	RFT	24	To be quoted online	To be quoted online
31	RECEPTION TABLE - (4'-6" x 2'-0") Providing and making a table of over all size of top as mentioned above and as per design given. It shall consist of 18mm thk. BWP.Ply top , sides and front and finished with 1.0 mm thk laminate of approved shade and make . All inner surfaces shall be finished with 0.80 mm thk laminate of white colour. It shall also consist of a set of 3 drawer unit with central locking system on the right side of the table and a side cadenza with drawers on top and shutters below as per the detailed drawing, on the left side. The drawer unit and side cadenza should be finished with 1.0 mm thk laminate of approved shade and make on all outer surfaces and all inner surfaces should be finished with 0.80 mm thk laminate of white colour. The front modesty panel shuould be finished 18 mm BWP. ply with laminate (as approved colour /	NOS.	1	To be quoted online	To be quoted online

	shade) with Metallic laminate. A 19mm thk Ply wood boxing at a slope ranging from 150mm to 300mm should be taken from the bottom of the front apron of the table as per design and shall be continued as cutomer ledge horizontally at a height of 300 feet from the table level . This boxing and ledge should be finished with 1mm thk laminate of approved shade and colour.				
32	<p>IN-CHARGE'S TABLE IN LAMINATE OF VEENER LOOK- Overall size :6'-0" x 2'- 6"</p> <p>Fabricating, erecting and fixing of table with top made up of 19mm thk ply and finished with 1.0 mm thk LAMINATE of approved shade and make on top as approved by the architect . The table to include pedestal with two pencil drawers of 100mm deep & a file shutter of 450mm, wire manager, an keyboard tray, CPU trolley. The works to include all hardware like castors, brass hinges, ballcatches, fully extendable drawer slides, locks, handles etc. of approved make.Locks to be of single control type. The front apron of the table shall be fixed with 8mm thk acrylic sheet fixed on 4 nos S.S Studs as per design and as directed by the architect. The clear acrylic sheet on the front apron of the table to be fixed with coloured logo of the bank as per design and size. All exposed surfaces to be finished with 4.0mm thk veneer in machine polish of approved shade and make and all inner surfaces including the inner surfaces of the drawers should be finished with 0.80mm thk balancing laminate of plain ivory colour in matte finish. Rates shall also be inclusive of 12 mm thk clear glass with bevelled edges on all sides to be placed on the table top.</p>	NOS	1	To be quoted online	To be quoted online

33	FACULTY/Admin Table - Overall size :4'-6" x 2' 6" IN LAMINATE FINISHSupply and fixing of table with top made up of 19mm thk ply finished with laminate of 1.0mm thk on top as approved by the architect and wooden beading/ moulding all round melamine polished. The table to include two pencil drawers of 100mm deep & a file shutter of 450mm, a wire manager, a keyboard tray and 250mm wide CPU trolley. The works to include all hardware like castors, brass hinges, ballcatches, fully extendable drawer slides, locks, handles etc. of approved make.Locks to be of single control type. All exposed edges to have wooden lipping stained to match the desk and melamine finished.Design and detail of the table shall be as per Architects design. All the visible external surface to be with 1.0mm thk laminate of approved shade and make. Rates shall also be inclusive of 12 mm thk clear glass with bevelled edges on all sides to be placed on the table top.	NOS	9	To be quoted online	To be quoted online
34	2'-0" Wide Linear running Table in Computer Lab Providing & Fixing in position 2'-0" wide linear / running counter in Computer lab in 25 mm thk. Exterior Grade Block Board of approved make for table top and side supports. The Front apron in 12mm.thk. BWP ply with approved colour Laminate . The top and sides of the counter to be finished on both sides with 1 mm thk. Laminate of approved make and shade / design. A Powder coated Wire manager ,Key Board Drawer size 12" x 20"x 2" deep made out of 12mm. thk. Ply ,Wooden Beading Patty four side in Laminate finish run on with Heavy duty sliding Chanel.	RFT	82.5	To be quoted online	To be quoted online

35	<p>SIDE CADENZA- OVERALL SIZE AS MENTIONED BELOW</p> <p>Providing and laying side cadenza of above sizes and as mentioned in the drawing.It shall consist of 3/4" thk plywood top, side and bases and 1/4" thk back. The edges on th top shall be provided with suitable(as per architect's design)wooden moulding with melamine finish.A pair of 3/4" wood shutters will be provided which will slide on 1" x1" wooden battens above skirting. 1"3/8" deep vertical depression shall be made on each shutters to act as handle as shown in the drawing. All external surfaces should be finished in 1.0mm laminate / veneer of approved shade and make. A 3/4" thk fixed ply wood shelf on battens shall be provided at 16" intervals from the base.Rates shall be inclusive of necessary approved fittings like sliding rollers, locks, tower bolts and any other misc. hardware items</p> <p>IN LAMINATE FINISH -OVERALL SIZE 3'-6" X 1'-6" X 2'-6"</p>	NOS	1	To be quoted online	To be quoted online
36	<p>SIDE CADENZA- OVERALL SIZE AS MENTIONED BELOW</p> <p>Providing and laying side cadenza of above sizes and as mentioned in the drawing.It shall consist of 3/4" thk plywood top, side and bases and 1/4" thk back. The edges on th top shall be provided with suitable(as per architect's design)wooden moulding with melamine finish.A pair of 3/4" wood shutters will be provided which will slide on 1" x1" wooden battens above skirting. 1"3/8" deep vertical depression shall be made on each shutters to act as handle as shown in the drawing. All external surfaces should be finished in 1.0mm laminate / veneer of approved shade and make. A 3/4" thk fixed ply wood shelf on battens shall be provided at 16" intervals from the base.Rates shall be inclusive of necessary approved fittings like sliding rollers, locks, tower bolts and any other misc. hardware items</p>	NOS	5	To be quoted online	To be quoted online

	IN LAMINATE FINISH -OVERALL SIZE 3'-0" X 1'-6" X 2'-6"				
37	Providing and fixing Dining area tables with base structure made from 50mm SS round pipes and 6m SS strips. The top frame to be of 35x35mm Square SS pipes. The table top to have 18-19mm BWR ply finished with 12mm thick synthetic acrylic solid surface (Merino, Hanex or equivalent) with rounded edges on all sides as per design and complete.OVER ALL SIZE- 7'-0" X 3'-0" FINISHED WITH CORIAN	NOS	1	To be quoted online	To be quoted online
38	CLASS ROOM / DINING ROOM TABLE - (3'-6" dia) IN LAMINATE FINISH Providing and making a table of over all size of top as mentioned above. It shall consist of two nos BWP ply 18/19mm and 6/8mm thk sandwitched as per design as Table Top and finished with 6.0mm thk Corian of approved shade and colour as per design . All the edges shall be finished with rounded corian band of matrching shade .It shall be supported on 18/19mm thk comercial ply base as per the design as in the detailed drawing (as approved by the architect), finished with 1.0 mm thk laminate of approved shade.	NOS	20	To be quoted online	To be quoted online
39	Class room Chair with foldable flap: Supplying, Placing in position class room chairs of approved design and make in approved colour, in M.s Powder coated frame and legs, fitted with cushioned seat and back along with a foldable flap / table and basket below for keeping books etc	Nos	40	To be quoted online	To be quoted online
40	WOODEN FLOORING AT INCHARGE'S CABIN Providing & laying 12mm thk HDF Laminate wooden flooring of approved make having atleast 10 years company warranty on the materials as approved	S.FT.	130	To be quoted online	To be quoted online

	by Architect . The cost to include skirting, reducers & Tee sections. This is also to include providing of polythene sheet, Foam of 2mm & glue. Grade to be used: 32. No extra shall be measured for Skirting				
41	<p>INCUMBENCY BOARD Supply and Fixing of Incumbency Board in Training Incharge cabin or at place as directed by the Bank officials/ architect, of overall size 3'-0" x 5'-6", made up of 19mm thk plywood finished with approved shade of 8MM THK Lecquered glass. This should be fitted with 19mm thk and 2" wide plywood patti all around on all sides of lecquered glass. This side patti and all edges/ thickness of plywood should be finished with approved shade of 1.0mm thk laminate in approved pattern and as directed by the architect. It shall consist of 12mm thk toughened glass fixed with 6-8 nos of S.S Studs on the board as per design or as directed at site. The glass shall be embossed or fixed with sticker stating the name and date of incharge joining the office is serial numbers.</p>	NOS	1	To be quoted online	To be quoted online
42	<p>Sun Control Film Providing and fixing in position Sun control film of approved make and shade with required frosting pattern on the glass surface complete as per the directions of EIC/ Architect (Payment shall be made for the finished area of the film actually provided. No deduction shall be made for openings upto 0.1 Sq.m. area each and nothing shall be paid extra for making such openings.)</p>	SFT	1020	To be quoted online	To be quoted online
43	<p>MAGNETIC WHITE BOARD: Providing and fixing of magnetic white board of approved make scratch resistant matt finish P3 surface consisting of ceramic steel of thickness 0.55mm to 0.65 mm, having a weight of 3-4 kgs per sqm. The core material shall be of interior grade 9mm thickness with density 700 to 800 kg/cum. With a backing of galvanized steel of 0.25 mm thickness having approximate weight of 1.96 kgs/sqm. This entire assembly shall be housed in an anodized aluminum extruded section conforming to IS-</p>	NOS	3	To be quoted online	To be quoted online

	6477 and IS-3965/2673 and corners of moulded ABS. The front and back surface will be affixed with 10-15 micron silver matt satin finish. This should be provided with clamp for hanging arrangement with locking facility including one set of accessories comprising of magnets, magnetic dry markers and magnetic eraser 4' x 8' (1200mm x 2400mm)				
44	Light Primary Points in PVC Conduit - Point Wiring for light points, controlled through modular switches complete with PVC boxes & cover plate - The point wiring shall be done with 3x 1.5 sq.mm Fire Resistant Low smoke Low Halogen stranded Cu. Wire in PVC conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600 mm interval & finally finishing the surface & matching the same with the existing surface. The rate should include the cost of all materials, modular switch complete with PVC box & cover plate, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc. The job shall be complete & to the entire satisfaction of the Bank. Circuit wiring to be included in the point wiring rates. The circuit wiring starts from DB to point control box/ switch box using Fire Resistant Low smoke Low Halogen stranded Cu. Wire 2x2.5 sqmm & 1x2.5 sqmm earthing (min size) in 20/25/32 mm PVC conduit. All the wiring shall be carried out in recessed conduits unless instructed by Architect / Engineer in charge	Each	75	To be quoted online	To be quoted online

45	<p>Wall / exhaust Fan Points in PVC Conduit -Point Wiring for wall / exhaust fan, controlled through modular switches complete with PVC boxes & cover plate - The point wiring shall be done with 3x 1.5 sq.mm Fire Resistant Low smoke Low Halogen stranded Cu. Wire in PVC conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement.The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600 mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, modular switch complete with PVC box & cover plate, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. Circuit wiring to be included in the point wiring rates. The circuit wiring starts from DB to point control box/ switch box using Fire Resistant Low smoke Low Halogen stranded Cu. Wire 2x2.5 sqmm & 1x2.5 sqmm earthing (min size) in 20/25/32 mm PVC conduit. All the wiring shall be carried out in recessed conduits unless instructed by Architect / Engineer in charge. One 6A socket will be provided next to fan complete with PVC gang box, modular socket and cover plate.</p>	Each	30	To be quoted online	To be quoted online
46	<p>Light Secondary Points PVC Conduit - Point Wiring for light points interlooped from the primary point. The secondary point wiring shall be done with 3x 1.5 sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) stranded Cu. Wire in PVC Conduit (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement.The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the</p>	Each	118	To be quoted online	To be quoted online

	conduit at every 600 mm interval & finally finishing the surface & matching the same with the existing surface. The rate should include the cost of all materials, modular switch complete with MS box & cover plate, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc. The job shall be complete & to the entire satisfaction of the Bank. All the wiring shall be carried out in recessed conduits unless instructed by Architect / Engineer in charge				
47	Ceiling Fan Point in PVC Conduit - Point Wiring for light points, controlled through modular switches complete with PVC boxes & cover plate - The point wiring shall be done with 3x 1.5 sq.mm Fire Resistant Low smoke Low Halogen stranded Cu. Wire in PVC conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600 mm interval & finally finishing the surface & matching the same with the existing surface. The rate should include the cost of all materials, modular switch, 2 module regulator complete with PVC box & cover plate, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc. The job shall be complete & to the entire satisfaction of the Bank. Circuit wiring to be included in the point wiring rates. The circuit wiring starts from DB to point control box/ switch box using Fire Resistant Low smoke Low Halogen stranded Cu. Wire 2x2.5 sqmm & 1x2.5 sqmm earthing (min size) in 20/25/32 mm PVC conduit. All the wiring shall be carried out in recessed conduits unless instructed by Architect / Engineer in charge	Each	2	To be quoted online	To be quoted online

48	<p>5/6A Primary point in PVC Conduit:- Supply & Installation of point wiring for Raw power plug points on workstations / table/ wall using 2X2.5 + 1x2.5 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from distribution board through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 1 nos of 6/10A , 3/5 pin sockets & 1 No.,6/10A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same.All switches sockets and accessories must be modular.All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in chargeInterconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	25	To be quoted online	To be quoted online
----	---	------	----	---------------------	---------------------

49	<p>5/6A Secondary point in PVC Conduit:- Supply & Installation of point wiring for Raw power plug points on workstations / table/ wall using 2X2.5 + 1x2.5 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from nearby point through PVC Conduit pipe (HMS) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 1 nos of 6/10A , 3/5 pin sockets & 1 No.,6/10A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface. The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc. The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in charge Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	18	To be quoted online	To be quoted online
----	--	------	----	---------------------	---------------------

50	<p>UPS Primary point in PVC Conduit:- Supply & Installation of point wiring for UPS points on workstations / table/ wall using 2X2.5 + 1x2.5 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from distribution board through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 3 nos of 6/10A , 3/5 pin sockets & 1 No.,6/10A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same.All switches sockets and accessories must be modular.All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in chargeInterconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	25	To be quoted online	To be quoted online
----	---	------	----	---------------------	---------------------

51	<p>UPS secondary point in PVC Conduit:- Supply & Installation of point wiring for UPS points on workstations / table/ wall using 2X2.5 + 1x2.5 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire looped from nearest UPS point through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 3 nos of 6/10A , 3/5 pin sockets & 1 No.,6/10A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface. The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc. The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in charge</p> <p>Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	18	To be quoted online	To be quoted online
----	--	------	----	---------------------	---------------------

52	<p>15/16A Primary point in PVC Conduit:- Supply & Installation of point wiring for Raw power plug points on workstations / table/ wall using 2X4 + 1x4 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from distribution board through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 1 nos of 16/20A , 3/5 pin sockets & 1 No.,16/20A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same.All switches sockets and accessories must be modular.All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in chargeInterconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>		17	To be quoted online	To be quoted online
----	---	--	----	---------------------	---------------------

53	<p>15/16A Secondary point in PVC Conduit:- Supply & Installation of point wiring for Raw power plug points on workstations / table/ wall using 2X4 + 1x4 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from nearest power point through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 1 nos of 16/20A , 3/5 pin sockets & 1 No.,16/20A Switch , wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same.</p> <p>All switches sockets and accessories must be modular.</p> <p>All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in charge</p> <p>Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.</p>	Each	3	To be quoted online	To be quoted online
----	---	------	---	---------------------	---------------------

54	AC point in PVC Conduit:-Supply & Installation of point wiring for Air Conditioner on workstations / table/ wall using 2X4 + 1x4 Sq.mm FR LSH (Fire Resistant Low smoke Low Halogen) copper conductor PVC sheathed flexible wire pulled from distribution board through PVC Conduit pipe (HMS Grade) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement. Each point consisting of 1 nos of 20/25A , 3/5 pin sockets & 1 No. Single module 20/25A MCB, 1 Nos 25A Motor starter switch wired together forming one point. The earth wire of green color only. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same.All switches sockets and accessories must be modular.All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in chargeInterconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.	Each	1	To be quoted online	To be quoted online
55	Supply & Laying of Point wiring for Single Phase Cassette AC (1-3.5 TR) near Indoor / Outdoor Unit with 3C x4 sq.mm. (P+N+E) XLPE 1100 volt grade armoured copper conductor cable confirming to IS : 694/1990 including the cost of supplying and installation of weatherproof enclosure and DP 32A MCB. The work includes end termination complete with copper thimbles / lugs and Brass compression	Each	17	To be quoted online	To be quoted online

	gland and cutting hole in Panel board using hole saw.				
56	Supply and laying 25 mm PVC conduit (HMS Grade) through wall / floor / above false ceiling / partition etc. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface. The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.	RM	200	To be quoted online	To be quoted online
57	3x6 sq mm submains wiring in PVC conduit:- Supply and laying of 2x6 sq mm + 1x6 sq mm FR LSH (Fire Resistant Low smoke Low Halogen) stranded Cu. Wire in PVC Conduit (HMS Grade) through wall / floor / above false ceiling / partition etc. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface. The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.	RM	50	To be quoted online	To be quoted online
58	Supply and laying of 3x10 submains wiring in PVC conduit Supply and laying of 2x10 sq mm + 1x10 sq mm FR (Fire Resistant) stranded Cu. Wire in PVC Conduit (HMS Grade) through wall / floor / above false ceiling / partition etc. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface. The rate should include the cost of all materials, labour, T&P,	RM	25	To be quoted online	To be quoted online

	scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.				
59	UPS Input Output Isolation Supply installation testing and commissioning of 4 way SPN DB flush mounted on wall, sheet metal fabricated, powder coated, having dust-proof and vermin 'proof, gasketed and hinged door with all internals such as DIN rails, neutral link, interconnected wiring, complete with earthing legs, housing following switch gears(Double door HORIZONTAL DB) with 2 Nos 63 A DP MCB for Single Phase UPS input and output isolation	Set	1	To be quoted online	To be quoted online
60	UPS MAIN DB SITC of 10 way SPN DB flush mounted on wall, sheet metal fabricated, powder coated, having dust-proof and vermin 'proof, gasketed and hinged door with all internals such as DIN rails, neutral link, interconnected wiring, complete with earthing legs, housing following switch gears(Double door HORIZONTAL DB) i/c 1 Nos 63A DP MCB 10 KA Breaking Capacity o/g 4 nos DP MCB 16A 10 KA Breaking Capacity	Set	1	To be quoted online	To be quoted online
61	UPS DB SITC of 16 way SPN DB flush mounted on wall, sheet metal fabricated, powder coated, having dust-proof and vermin 'proof, gasketed and hinged door with all internals such as DIN rails, neutral link, interconnected wiring, complete with earthing legs, housing following switch gears(Double door HORIZONTAL DB) i/c 1 Nos 40A DP MCB 10 KA Breaking Capacity o/g 14 nos SP MCB 16A 10 KA Breaking Capacity	Set	2	To be quoted online	To be quoted online
62	Emergency Light DB SITC of 6 way SPN DB flush mounted on wall, sheet metal fabricated, powder coated, having dust-proof and vermin 'proof, gasketed and hinged door with all internals such as DIN rails, neutral	Set	1	To be quoted online	To be quoted online

	link, interconnected wiring, complete with earthing legs, housing following switch gears(Double door HORIZONTAL DB) i/c 1 Nos 63A DP MCB 10 KA Breaking Capacity o/g 4 nos SP MCB 16A 10 KA Breaking Capacity				
63	Light DB SITC of 4 way Horizontal DB flush mounted on wall, sheet metal fabricated, powder coated, having dust-proof and vermin 'proof, gasketed and hinged door with all internals such as DIN rails, neutral link, interconnected wiring, complete with earthing legs, housing following switch gears(Double door HORIZONTAL DB) with i/c 1 Nos 40A TPN MCB o/g 12 nos SP MCB 10A 10 KA Breaking Capacity	Set	2	To be quoted online	To be quoted online
64	AC DBSITC of 4 way Horizontal DB flush mounted on wall, sheet metal fabricated, powder coated, having dust-proof and vermin 'proof, gasketed and hinged door with all internals such as DIN rails, neutral link, interconnected wiring, complete with earthing legs, housing following switch gears(Double door HORIZONTAL DB) with i/c 1 Nos 63A TPN MCB o/g 12 nos SP MCB 25 / 32 A 10 KA Breaking Capacity	Set	3	To be quoted online	To be quoted online
65	Power DB SITC of 6 way Horizontal DB flush mounted on wall, sheet metal fabricated, powder coated, having dust-proof and vermin 'proof, gasketed and hinged door with all internals such as DIN rails, neutral link, interconnected wiring, complete with earthing legs, housing following switch gears(Double door HORIZONTAL DB) with i/c 1 Nos 63A TPN MCB o/g 18 nos SP MCB 16A 10 KA Breaking Capacity	Set	3	To be quoted online	To be quoted online

66	<p>SITC OF LT PANEL AS UNDER: (Manufacturrer must be approved from CPRI)Construction: Free Standing with front access, Dust & vermin Proof, Form 3b construction.Supply: 415V, 3Phase, 4 Wire, 50 Hz.Control Supply: 230V Single PhaseFault Level: 36KA for 1 SecFabrication: CRCA Sheet 14SWG for Gland Plate, Load Bearing Structure and Body, 16 SWG for partitions, doors and panels. 25x3 mm neoprene gasket for door, cover and gland plate. 40x5 mm gasket for joints and canopy. DC Locks to be provided on doors, danger plates on front and rear of bus bar chambers, live parts.Cable Entry / Exit : From top.Name plate: Anodised AluminiumPowder Coating: Pre treated with 7 tank process and duly powder coated.TPN Busbars: 200A Rated Aluminium (current density 1A/sq mm) with colour coded heat shrinkable sleeve. Earth Bar of suitable size to be provided with earthing terminal on both endsSeparate bus bar system to be provided for Emergency and Non Emergency supply outgoingInstrumentation: 1 Set 3 nos phase indicating lamps each backed up with MCB and switch shall be provided for each incomer. 1 no. VAF meter 0-200A with CT, selector switch, and fuse as reqd.Main Incomer- 125A MCCB (microprocessor controlled with earth fault relay Adjustable overload: 0.4-1.0 x In; Adjustable Short Circuit: 1.5-8 x In)DG Incomer - 100A MCCB (Adjustable overload: 0.8-1.0 x In; Adjustable Short Circuit: 6-10 x In)Change Over - 100A Manual ChangeoverNon Emergency Outgoing - 4 Nos 63A MCCBEmergency Outgoing 4 Nos 63A FP MCB, 4 Nos 40A FP MCB, 2 Nos 63A DP MCBOne Section in outgoing section in both emergency and non emergency section be kept spare for future provisions</p>	Set	1	To be quoted online	To be quoted online
67	Supply and installation of MCCB enclosure along with 125 A 4 pole MCCB 36KA breaking capacity with thermal magnetic release, Adjustable	Set	1	To be quoted online	To be quoted online

	overload: 0.8-1.0 x In Adjustable Short Circuit: 6-10 x In				
68	S & I of earth pit comprising of 600mm x 600mm x 3mm. thick copper plate buried at a minimum depth of 2.7 meter including necessary materials like charcoal,salt etc as required conforming to BIS standards having brick masonry chamber with hinged cover and watering arrangement.	Set	1	To be quoted online	To be quoted online
69	S & I of earth pit comprising of G.I. earth pipe 4.5 metre long, 40 mm dia including necessary materials like charcoal,salt etc as required conforming to BIS standards having brick masonry chamber with hinged cover and watering arrangement.	Set	2	To be quoted online	To be quoted online
70	Providing and fixing 25 mm X 5 mm GI strip on surface or in recess for connections etc. as required complete with insulation sleeve	RM	70	To be quoted online	To be quoted online
71	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surfacel recessed conduit / submain wiring / cable as required.	RM	₹ 275.00	To be quoted online	To be quoted online
72	Telephone point primary in PVC conduit:Supply & fixing on wall/ furniture/ partition recessed type modular telephone socket outlet (RJ-11) with mounting box & front plate complete with chase cutting, mending good etc. as required complete including Supply & laying of 1 pair 0.5 mm dia. PVC insulated unarmoured telephone cables through PVC Conduit pipe (HMS) concealed in wall/ floor/ panelling/ partitions or above false ceiling as per requirement drawn from telephone tag block. The work shall also include for cutting chase for conduits and moulded boxes, if required, in the wall/ floor (Without damaging the building/wall) along with clamping the conduit at every 600mm interval & finally finishing the surface & matching the same with the existing surface.The rate should include the cost of all materials, labour, T&P, scaffolding, shifting of furniture, carting away the debris and cleaning the floor etc.The job shall be complete & to the	Each	8	To be quoted online	To be quoted online

	entire satisfaction of the Bank. The above includes supply & fixing modular cover plates, base plates, PVC box/ Gang box in brick wall by making necessary chase/ recess and making good the same. All switches sockets and accessories must be modular. All new points must be provided in concealed/recessed conduit unless directed by architect / engineer in charge. Interconnections to movable furniture, if any, shall be done using flexible PVC Conduit with end couplers.				
73	Providing and fixing of telephone tag block (Krone type) of 50 pair housed in GI box with cover of suitable size including termination	Each	1	To be quoted online	To be quoted online
74	Supply and laying, effecting proper connections, testing & commissioning of the following sizes of 1.1 KV armoured/ unarmoured XLPE insulated PVC sheathed aluminium /copper conductor cables conforming to IS: 7098 Part 1 with latest amendments laid over MS supports in existing RCC ducts/ laid in ground /laid on Cable Trays including clamping the cables to supports in an approved manner as required complete with all accessories. Supply and laying of 4x16 sq mm armoured aluminium cable in existing pipe / cable tray	RM	200	To be quoted online	To be quoted online
75	Supply and laying, effecting proper connections, testing & commissioning of the following sizes of 1.1 KV armoured/ unarmoured XLPE insulated PVC sheathed aluminium /copper conductor cables conforming to IS: 7098 Part 1 with latest amendments laid over MS supports in existing RCC ducts/ laid in ground /laid on Cable Trays including clamping the cables to supports in an approved manner as required complete with all accessories. Supply and laying of 3.5x70 armoured aluminium cable in existing pipe / cable tray	RM	70	To be quoted online	To be quoted online

76	Supply and laying, effecting proper connections, testing & commissioning of the following sizes of 1.1 KV armoured/ unarmoured XLPE insulated PVC sheathed aluminium /copper conductor cables conforming to IS: 7098 Part 1 with latest amendments laid over MS supports in existing RCC ducts/ laid in ground /laid on Cable Trays including clamping the cables to supports in an approved manner as required complete with all accessories. Supply and laying of 3.5x50 armoured aluminium cable in existing pipe / cable tray	RM	70	To be quoted online	To be quoted online
77	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as reqd. End termination of 4x16 aluminium armoured cable	Set	16	To be quoted online	To be quoted online
78	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as reqd. End termination of 3.5x70 aluminium armoured cable	Set	4	To be quoted online	To be quoted online
79	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as reqd. End termination of 3.5x50 aluminium armoured cable	RM	2	To be quoted online	To be quoted online
80	Supply, Installation, testing and commissioning of 2'X2' Recessed type LED LIGHT FITTINGS of 33-36 W, CRCA / Extruded aluminium housing, efficiency of 120 lumens per watt and & Average life not less than 50000 hrs. The light should be hanged/supported by MS chain from ceiling directly and not be kept directly on false ceiling frame. Cutting of ceiling, framing etc. be included in the costs. Standard warranty of light fittings shall be minimum 2 years.	Each	70	To be quoted online	To be quoted online

81	Supply, Installation, testing and commissioning of LED DOWNLIGHT FITTINGS of 15-18 W with minimum lumen level of 1650 lumens with die cast aluminium housing, efficiency of 110 lumens per watt and & Average life not less than 30000 hrs. Cutting of ceiling, modifications required to the ceiling be included in the cost. Standard warranty of light fittings shall be minimum 2 years.	Each	100	To be quoted online	To be quoted online
82	Supply Installation testing and commissioning of 2 ft, 10-12 watt LED batten with 900 lumen output and 2 year warranty	Each	8	To be quoted online	To be quoted online
83	Supply Installation testing and commissioning of 4 ft, 18-20 watt LED batten with 2000 lumen output and 2 year warranty	Each	15	To be quoted online	To be quoted online
84	Supply, Installation, Testing and commissioning of metal body Wall mounted Fan with metal enclosure for motor, 3/4 blade design, sweep 400-450 mm power input max 100 watt, Speed 1300-1330rpm with all accessories.	Each	21	To be quoted online	To be quoted online
85	Supply, Installation, Testing and commissioning of BEE 5 Star rated Ceiling Fan 1200 mm Supply, Installation, Testing and Commissioning of 1200 mm sweep, BEE 5 star rated, ceiling fan with Brush Less Direct Current (BLDC) Motor, 30 cm long down rod, 2 nos. canopies, shackle kit, safety rope, copper winding, remote or electronic regulator unit for speed control and all remaining accessories including safety pin, nut bolts, washers, suitable for 230 V, 50 Hz, single phase AC Supply, earthing etc. complete as required.	Each	2	To be quoted online	To be quoted online
86	Supply Installation Testing and Commissioning of 300 mm metal body and blade heavy duty (industrial type) exhaust fan complete with grill and collapsible louvre. The cost of work includes making necessary framing for installation of fan on window / wall cutout and plug top for connection to nearest point	Each	7	To be quoted online	To be quoted online

87	Supply Installation Testing and Commissioning of 200 mm plastic body exhaust fan complete with collapsible louvre. The cost of work includes making necessary framing for installation of fan on window / wall cutout and plug top for connection to nearest point	Each	2	To be quoted online	To be quoted online
88	Supply, installation, testing and commissioning of public address/ music system comprising of Amplifier of 240 W, RMS output including necessary control wires, jacks etc. any other accessories as required	Each	1	To be quoted online	To be quoted online
89	SITC of DVD player with USB playback & Bluetooth support	Each	1	To be quoted online	To be quoted online
90	SITC of 6-9 W ceiling mounted speakers with line matching transformers with decorative grills, mounting bracket etc. other accessories as required in complete.	Each	20	To be quoted online	To be quoted online
91	Supply and laying Wiring of 1.5 sq mm twin core shielded type of speaker cable with Providing and fixing in position the following FRLS PVC conduits including all accessories concealed/ exposed in Ceiling/ Wall complete as required including 1.6/2.0 mm thick PVC junction or pull boxes with 3 mm thick sheet cover plate	RM	150	To be quoted online	To be quoted online
92	Split AC 1.5 TR 5 Star Split AC Supply of BEE 5 Star rated 1.5 TR Rated Capacity Hi-Wall Split Airconditioner with following: - 5 Star Bureau of Energy Efficiency Star rating (as per ratings valid in March 2024 for room air conditioners). - suitable for operation on single phase 50 Hz 220-240 Volt supply - Rust free cabinet - Wireless remote control - Hermetically sealed inverter type rotary / swing / scroll compressor with 5 year warranty suitable for R-32 refrigerant. - Auto air swing louvres. - Capable of performing Cooling, Dehumidifying, Air Circulating & Filtering. - Drain pan for collecting condensate.	Nos	1	To be quoted online	To be quoted online

	<ul style="list-style-type: none"> - Condenser unit shall be complete with compressor and air cooled condenser - fan evaporating units shall consist of a fan section with dynamically balanced centrifugal fan driven by FHP motor, multi row deep cooling coil of copper tube with aluminium fins, thermostatic expansion valve etc - Hi-Wall indoor unit. - Unit should support Inter Unit Piping Length: 15 meters or higher - Unit shall be charged with refrigerant from factory - Additional top up of refrigerant as required shall be done. - The work is inclusive of providing 20A plug top and wiring up to nearest point within the same room. 				
93	<p>Supply of 1.5 TR BEE 5 Star rated 4 way cassette AC- 5 Star Bureau of Energy Efficiency Star rating (as per ratings valid in March 2024 for room air conditioners).- suitable for operation on single phase 50 Hz 220-240 Volt supply- Rust free cabinet- Wireless remote control- Hermetically sealed inverter type rotary / swing / scroll compressor with 5 year warranty suitable for R-32 refrigerant.- Auto air swing louvres.- Capable of performing Cooling, Dehumidifying, Air Circulating & Filtering.- Drain pan for collecting condensate with drain pan safety.- Condenser unit shall be complete with compressor and air cooled condenser</p> <ul style="list-style-type: none"> - fan evaporating units shall consist of a fan section with dynamically balanced centrifugal fan driven by FHP motor, multi row deep cooling coil of copper tube with aluminium fins, thermostatic expansion valve etc- <p>Indoor / Out Door unit installation height difference: 4 meters or higher- Integral Drain pump kit- Unit should support Inter Unit Piping Length of 20 meters or higher- Unit shall be charged with refrigerant from factory- Additional top up of refrigerant as required shall be done.</p>	Nos	1	To be quoted online	To be quoted online

94	Supply of 2 TR BEE 5 Star rated Hi-Wall Split AC- 5 Star Bureau of Energy Efficiency Star rating (as per ratings valid in March 2024 for room air conditioners).- suitable for operation on single phase 50 Hz 220-240 Volt supply- Rust free cabinet- Wireless remote control- Hermetically sealed inverter type rotary / swing / scroll compressor with 5 year warranty suitable for R-32 refrigerant.- Auto air swing louvres.- Capable of performing Cooling, Dehumidifying, Air Circulating & Filtering.- Drain pan for collecting condensate with drain pan safety.- Condenser unit shall be complete with compressor and air cooled condenser - fan evaporating units shall consist of a fan section with dynamically balanced centrifugal fan driven by FHP motor, multi row deep cooling coil of copper tube with aluminium fins, thermostatic expansion valve etc-Indoor / Out Door unit installation height difference: 4 meters or higher-Integral Drain pump kit- Unit should support Inter Unit Piping Length of 15 meters or higher- Unit shall be charged with refrigerant from factory- Additional top up of refrigerant as required shall be done.	Nos	2	To be quoted online	To be quoted online
95	Supply of 2.5 TR BEE 5 Star rated 4 way cassette AC- 5 Star Bureau of Energy Efficiency Star rating (as per ratings valid in March 2024 for room air conditioners).- suitable for operation on single phase 50 Hz 220-240 Volt supply- Rust free cabinet- Wireless remote control- Hermetically sealed inverter type rotary / swing / scroll compressor with 5 year warranty suitable for R-32 refrigerant.- Auto air swing louvres.- Capable of performing Cooling, Dehumidifying, Air Circulating & Filtering.- Drain pan for collecting condensate with drain pan safety.- Condenser unit shall be complete with compressor and air cooled condenser - fan evaporating units shall consist of a fan section with dynamically balanced centrifugal fan driven by FHP motor, multi row deep cooling coil of copper tube with aluminium fins,	Nos	2	To be quoted online	To be quoted online

	<p>thermostatic expansion valve etc- Indoor / Out Door unit installation height difference: 4 meters of higher- Integral Drain pump kit- Unit should support Inter Unit Piping Length of 20 meters or higher- Unit shall be charged with refrigerant from factory- Additional top up of refrigerant as required shall be done.</p>				
96	<p>Supply of 3.5 TR BEE 5 Star rated 4 way cassette AC- 5 Star Bureau of Energy Efficiency Star rating (as per ratings valid in March 2024 for light commercial airconditioner).- suitable for operation on single phase 50 Hz 220-240 Volt supply- Rust free cabinet- Wireless remote control- Hermetically sealed inverter type rotary / swing / scroll compressor with 5 year warranty suitable for R-32 refrigerant.- Auto air swing louvres.- Capable of performing Cooling, Dehumidifying, Air Circulating & Filtering.- Drain pan for collecting condensate with drain pan safety.- Condenser unit shall be complete with compressor and air cooled condenser - fan evaporating units shall consist of a fan section with dynamically balanced centrifugal fan driven by FHP motor, multi row deep cooling coil of copper tube with aluminium fins, thermostatic expansion valve etc- Indoor / Out Door unit installation height difference: 4 meters of higher- Integral Drain pump kit- Unit should support Inter Unit Piping Length of 20 meters or higher- Unit shall be charged with refrigerant from factory- Additional top up of refrigerant as required shall be done.</p>	Nos	12	To be quoted online	To be quoted online

97	Installation and commissioning of 1.5 TR Hi-Wall Split Airconditioner units supplied as above, using brackets, fasteners, any accessories as required, to the correct alignment ensuring proper flow of condensate water and proper cooling.	Nos	1	To be quoted online	To be quoted online
98	Supply and Installation of wall / floor mounted outdoor stand for 1.5 TR Hi-Wall Split Airconditioner, complete with anchor / dash fasteners and anti vibration rubber pad.	Nos	1	To be quoted online	To be quoted online
99	Supply and laying of copper refrigerant piping (liquid and gas) of size as per manufacturers specifications with foiled nitrile rubber insulation complete with all accessories such as bends, elbows, unions, etc., brazing/soldering, clamping/binding with suitable tie knots, providing insulation etc. including end connections with flare nut / brazing as per manufacturers specifications and suspension of piping from ceiling using hangars for 1.5 Tr Split Airconditioner (material supplied in standard installation kit shall be excluded from the measurement)	RM	5	To be quoted online	To be quoted online
100	Supply and laying of interconnecting cable between indoor and outdoor unit for 1.5 TR Hi-Wall Split Airconditioner as per manufacturer's recommendations. (material supplied in standard installation kit shall be excluded from the measurement)	RM	5	To be quoted online	To be quoted online
101	Installation and commissioning of 1.5 TR cassette Airconditioner units supplied as above, using brackets, fasteners, any accessories as required, to the correct alignment ensuring proper flow of condensate water and proper cooling.	Nos	1	To be quoted online	To be quoted online
102	Supply and Installation of wall / floor mounted outdoor stand for 1.5 TR Cassette Airconditioner, complete with anchor / dash fasteners and anti vibration rubber pad.	Nos	1	To be quoted online	To be quoted online
103	Supply and laying of copper refrigerant piping (liquid and gas) of size as per manufacturers specifications with foiled nitrile rubber insulation complete with all accessories such as bends, elbows, unions, etc., brazing/soldering,	RM	20	To be quoted online	To be quoted online

	clamping/binding with suitable tie knots, providing insulation etc. including end connections with flare nut / brazing as per manufacturers specifications and suspension of piping from ceiling using hangars for 1.5 Tr Cassette Airconditioner				
104	Supply and laying of interconnecting cable between indoor and outdoor unit for 1.5 TR Cassette Airconditioner as per manufacturer's recommendations.	RM	20	To be quoted online	To be quoted online
105	Installation and commissioning of 2 TR cassette Airconditioner units supplied as above, using brackets, fastners, any accessories as required, to the correct alignment ensuring proper flow of condensate water and proper cooling.	Nos	2	To be quoted online	To be quoted online
106	Supply and Installation of wall / floor mounted outdoor stand for 2 TR Cassette Airconditioner, complete with anchor / dash fasteners and anti vibration rubber pad.	Nos	2	To be quoted online	To be quoted online
107	Supply and laying of copper refrigerant piping (liquid and gas) of size as per manufacturers specifications with foiled nitrile rubber insulation complete with all accessories such as bends, elbows, unions, etc., brazing/soldering, clamping/binding with suitable tie knots, providing insulation etc. including end connections with flare nut / brazing as per manufacturers specifications and suspension of piping from ceiling using hangars for 2 Tr Cassette Airconditioner	RM	43	To be quoted online	To be quoted online
108	Supply and laying of interconnecting cable between indoor and outdoor unit for 2 TR Cassette Airconditioner as per manufacturer's recommendations.	RM	43	To be quoted online	To be quoted online
109	Installation and commissioning of 2.5 TR Cassette Airconditioner units supplied as above, using brackets, fastners, any accessories as required, to the correct alignment ensuring proper flow of condensate water and proper cooling.	Nos	2	To be quoted online	To be quoted online
110	Supply and Installation of wall / floor mounted outdoor stand for 2.5 TR Cassette Airconditioner, complete with anchor / dash fasteners and anti vibration rubber pad.	Nos	2	To be quoted online	To be quoted online

111	Supply and laying of copper refrigerant piping (liquid and gas) of size as per manufacturers specifications with foiled nitrile rubber insulation complete with all accessories such as bends, elbows, unions, etc., brazing/soldering, clamping/binding with suitable tie knots, providing insulation etc. including end connections with flare nut / brazing as per manufacturers specifications and suspension of piping from ceiling using hangars for 2.5 Cassette Airconditioner	RM	40	To be quoted online	To be quoted online
112	Supply and laying of interconnecting cable between indoor and outdoor unit for 2.5 TR Cassette Airconditioner as per manufacturer's recommendations.	RM	40	To be quoted online	To be quoted online
113	Installation and commissioning of 3.5 TR Cassette Airconditioner units supplied as above, using brackets, fasteners, any accessories as required, to the correct alignment ensuring proper flow of condensate water and proper cooling.	Nos	12	To be quoted online	To be quoted online
114	Supply and Installation of wall / floor mounted outdoor stand for 3.5 TR Cassette Airconditioner, complete with anchor / dash fasteners and anti vibration rubber pad.	Nos	12	To be quoted online	To be quoted online
115	Supply and laying of copper refrigerant piping (liquid and gas) of size as per manufacturers specifications with foiled nitrile rubber insulation complete with all accessories such as bends, elbows, unions, etc., brazing/soldering, clamping/binding with suitable tie knots, providing insulation etc. including end connections with flare nut / brazing as per manufacturers specifications and suspension of piping from ceiling using hangars for 3.5 Cassette Airconditioner	RM	180	To be quoted online	To be quoted online
116	Supply and laying of interconnecting cable between indoor and outdoor unit for 3.5 TR Cassette Airconditioner as per manufacturer's recommendations.	RM	180	To be quoted online	To be quoted online
117	Supply and Laying 25 mm PVC Condensate Drain Pipe with nitrile insulation complete with bends, tees, elbows and making connection to cassette / split ac unit with flexible connector.	RM	300	To be quoted online	To be quoted online

118	Providing and supplying Sofas of approved make and colour. Sofas shall have mild steel chrome plated legs finished with leatherite. Two seater Leatherette Sofa in black colour	NOS.	1	To be quoted online	To be quoted online
119	Providing and supplying Sofas of approved make and colour. Sofas shall have mild steel chrome plated legs finished with leatherite. Three seater Tandem Sofa with Cushioned seat and back in chrome finish	NOS.	2	To be quoted online	To be quoted online
120	Providing and supplying Sofas of approved make and colour. Sofas shall have mild steel chrome plated legs finished with leatherite. Two seater Tandem Sofa with Cushioned seat and back in chrome finish	NOS.	2	To be quoted online	To be quoted online
121	Providing and supplying medium back chairs as per following specification (1). The chairs has a back inner / outer shell made out up of polypropylene having snap type fittings . (2). Moulded foam (48 DENSITY) is used on the seat and back. (3). A hot presses plywood seat (12 MM THICK) is used as base (4). The arm rest used is made up of soft polyurethane (250 density) having mild steel insert (5).The tilting mechanism used is having only back movement lockable at the front position. (6). The seat to back connecting mild steel plate is 10 MM thick. The handle connecting mild steel plate is 5 MM thick. (7). A seat outer made up of POLYPROPYLENE is used for asthetic appeal. (8). An imported gas lift mechanism is used for seat height adjustment. (9). A mild steel powder coated base (630 MM WIDE) is used having a load capacity of 800 KGS. (10). Twin wheel nylon castore are used having a load bearing capacity of 50 Kgs. Per Caster. Swivel Chair High Back (In Incharge Room) In MS Frame covered with breathable Mesh in Black for Back and Lumber Support, 12mm Moulded Ply for seat with PU on it. PU Adjustable arms,	Nos	1	To be quoted online	To be quoted online

	Chrome base, Haad Rest, Synchro Mech & Gas Lift Etc, Complete.				
122	<p>Providing and supplying medium back chairs as per following specification (1). The chairs has a back inner / outer shell made out up of polypropylene having snap type fittings . (2). Moulded foam (48 DENSITY) is used on the seat and back. (3). A hot presses plyood seat (12 MM THICK) is used as base (4). The arm rest used is made up of soft polyurethane (250 density) having mild steel insert (5).The tilting mechanism used is having only back movement lockable at the front position. (6). The seat to back connecting mild steel plate is 10 MM thick. The handle connecting mild steel plate is 5 MM thick. (7). A seat outer made up of POLYPROPYLENE is used for asthetic appeal. (8). An imported gas lift mechanism is used for seat height adjustment. (9). A mild steel powder coated base (630 MM WIDE) is used having a load capacity of 800 KGS. (10). Twin wheel nylon castore are used having a load bearing capacity of 50 Kgs. Per Caster. Swivel Chair Medium Back (In Comp. Lab & Round table Class Room, Admin, Faculty, Librarian, reception desk, faculty at classroom) In MS Frame covered with breathable Mesh in Black for Back and Lumber Support, 12mm Moulded Ply for seat with PU on it. PU Adjustable arms, Chrome base, Synchro Mech & Gas Lift Etc, Complete.</p>	Nos	78	To be quoted online	To be quoted online

123	Providing and supplying medium back chairs as per following specification (1). The chairs has a back inner / outer shell made out up of polypropylene having snap type fittings . (2). Moulded foam (48 DENSITY) is used on the seat and back. (3). A hot presses plyood seat (12 MM THICK) is used as base (4). The arm rest used is made up of soft polyurethane (250 density) having mild steel insert (5).The tilting mechanism used is having only back movement lockable at the front position. (6). The seat to back connecting mild steel plate is 10 MM thick. The handle connecting mild steel plate is 5 MM thick. (7). A seat outer made up of POLYPROPYLENE is used for asthetic appeal. (8). An imported gas lift mechanism is used for seat height adjustment. (9). A mild steel powder coated base (630 MM WIDE) is used having a load capacity of 800 KGS. (10). Twin wheel nylon castore are used having a load bearing capacity of 50 Kgs. Per Caster. Visitor's Chair (Fixed Chair)Premium Executive Chair, Visitor W/o Arms, with centre tilt mechanism, Upright position locking, soft top fixed arms, tilt tension adj, 7 Nilon Pedestal, of approved colour and shade	Nos	13	To be quoted online	To be quoted online
124	Providing and supplying medium back chairs as per following specification (1). The chairs has a back inner / outer shell made out up of polypropylene having snap type fittings . (2). Moulded foam (48 DENSITY) is used on the seat and back. (3). A hot presses plyood seat (12 MM THICK) is used as base (4). The arm rest used is made up of soft polyurethane (250 density) having mild steel insert (5).The tilting mechanism used is having only back movement lockable at the front position. (6). The seat to back connecting mild steel plate is 10 MM thick. The handle connecting mild steel plate is 5 MM thick. (7). A seat outer made up of POLYPROPYLENE is used for asthetic appeal. (8). An imported gas lift mechanism is used for seat height adjustment. (9). A mild	Nos	48	To be quoted online	To be quoted online

	steel powder coated base (630 MM WIDE) is used having a load capacity of 800 KGS. (10). Twin wheel nylon castore are used having a load bearing capacity of 50 Kgs. Per Caster. Dining Table Chair/ Pantry Stool (In Dining & Library) Cafeteria chairs in MS Powder Coated Understructure of Colour code- Marigold Yellow -023				
125	<p>SINGLE BED WITH BOX AND TWO SIDE TABLES</p> <p>Supplying & Fixing in position Single bed with overall size 36"Wx78"LX15"H alongwith 6" high mattress Size W 36"x L 78" of Sleepon/ Kurlon or equivalent make. The box all four sides and top made of 19mm BWP marked compressed ply board faced with 0.8mm thick laminate on all inner sides and 1.0mm thk laminate of approved shade and make on all the outer sides with teakwood beading on the edges. The height of box will be 15" . The box should have openable lid with full length hinges with center wooden support and holder for lid and the bottom of bed made of 12 mm BWPcompressed ply with .8mm thick laminate on one side. The bed should be provided with bed side table made of 18mm thick medium density fiber/partical board (Action Tessa), all panels of unit are inter connected with rastex , dowel and sockets (Hettich). All the edges provided with machine pressed 0.8mm thick PVC edge bands glued with hot melt EVA glue. The side unit having two drawers made of 18mm thick medium density fiber/partical board (Action Tessa), fitted on full length ball based telescopic channels and 96mm SS handles. The complete bed with side tables duly polished in walnut melamine finish. The Size of Side table Should be 450mm x450mm x450mm with one 6" drawer on telescopic channel.</p>	NOS	2	To be quoted online	To be quoted online
126	Providing and fixing Steel almirah of size 1980mm (H) x 900mm (W) x 480mm (D) manufactured from 22 gauge for body and 20 gauge for doors.	NOS	2	To be quoted online	To be quoted online

	The Almirah should have four doors divided along vertical and horizontal surfaces along the total length and width of the almirah. Each door shall be a single unit with individual locking system. Make- Geeken/ Neelkamal/ Durian				
127	SOFA SETS FOR GUEST ROOM - (FABRIC COST B.R. Rs. 450/MTS. OF APPROVED SHADE, SAMPLE TO BE GOT APPROVED) DOUBLE SEATER Providing and fixing sofa set to detail as shown in drawing about 60cm wide and about 68cm high comprising second class SAL WOOD framework using 50 x 40 with 8mm thick com plywood covering on all sides. Seats finished with spring hooked to MS plate 25mm width fixed to the seat frame. Both seat frame and back covered with layer of jute cloth and 75mm latex rubber (2 layer for seat alone) finished with 12mm foam lining and upholstered to shape with fabric (basic price Rs.300/m) for the rear of the back also and the under surface of the seat finished with Gada cloth 8mm ply below seat. Note: (For sofas materials like foam, latex rubber, gadacloth, spring ,fabric etc., to be approved by the Architects / Bank).	NOS.	2	To be quoted online	To be quoted online
	TOTAL			To be quoted online	To be quoted online

END